INDIANA DEPARTMENT OF TRANSPORTATION
100 North Senate Avenue Room N758-Cont
Indianapolis, Indiana 46204-2218

Letting of October 7, 2026 September 24, 2026

NOTICE OF REVISION NO. 1
TO CONTRACT NO. B -44576-A

The Special Provisions, pages 93, 94, 105, and 106 were revised and are included herewith.

Should you desire to submit a bid, please do so based on the information set out above.

For electronic bids, the prequalified bidders for the above contract shall acknowledge this revision by entering the date of this letter in the appropriate field on the electronic proposal form.

It is the bidder's responsibility to check the Bid Express website for all amendment files prior to the deadline for bid submittal. This includes amendment files that may be generated due to administrative changes to the bidding form, which may not be communicated in a revision letter.

Asfahan Ullah Khan
Senior Pre-Bid Engineer

AUK/mr/drp

Notice: Notification that a revision was released will only be sent by email to those subscribing to the INDOT Listserv address: http://www.in.gov/dot/div/contracts/letting/Email-Form.html. The email message includes a link to the site where the revision may be viewed, downloaded, and printed. The link is: http://erms.indot.in.gov/viewdocs/

104-R-168 SCHEDULE OF OPERATIONS AND TRAFFIC CONTROL FOR UNDERSEALING, CONCRETE PATCHING, PLACING UNDERDRAINS, AND RESURFACING

(Revised 05-01-25)

The Standard Specifications are revised as follows:

SECTION 104, AFTER LINE 362, INSERT AS FOLLOWS:

(e) Schedule of Operations and Traffic Control for Undersealing, Concrete Patching, Placing Underdrains, and Resurfacing

Unless otherwise directed or permitted, the work specified shall be arranged and prosecuted in accordance with the applicable requirements of 107 and 801, and as set out herein.

All necessary barricades, flashing arrow signs, suitable lights, danger signals, signs, flaggers, and other traffic control devices shall be provided, erected and maintained for the protection of the workers and the safety of the public. Such protection shall be in accordance with 107.12 and as shown on the plans or as directed. Traffic shall be maintained such that the flow of traffic is interrupted for the shortest amount of time possible.

1. Construction Sequence

The construction shall be done in the following sequence, unless otherwise directed.

a. Undersealing shall be accomplished before all patching or other work within the pavement area is done.

b. The pavement patching shall be accomplished after undersealing is complete.

c. The underdrains shall be placed after the pavement patching is complete.

d. Resurfacing operations shall then begin.

The names and telephone numbers of the Superintendent and one other responsible employee shall be furnished. They shall be on call or available at night, on weekends, or during other non-working periods. These employees shall oversee the repair or replacement of all traffic control devices which may become damaged or inoperative.

2. Lane Closures

Only one lane in each direction shall be closed at a time, except as noted below. Traffic maintenance setups shall not be spaced closer than 3 mi from one another on a one-way roadway. If a traffic maintenance setup extends beyond one or more ramps, an "Exits Right Lane Only" sign shall be placed.

***1 lane** of through traffic shall be maintained in each direction at all times for the holiday periods listed in 108.08. Traffic shall be maintained on other holidays as directed.*

1 lane *of through traffic shall be maintained in each direction at all times during rush hour periods as directed. When work is performed during center lane closure on a three-lane roadway, the median and center lanes may be closed during times other than rush hour periods as directed. Closure will be permitted for the center lane only at all other times.*

3. Patching

During the patching operation of the outside lane or ramps, closure of such ramps will be permitted for the shortest possible time while patching is being done in the outside lane in the vicinity of ramp exits or entrances. Ramp closures will not be permitted during rush hour periods as directed.

Maintenance of traffic shall include a taper plus an additional length, both as shown on the plans, prior to reaching the construction area. The taper and additional length shall be delineated by drums spaced at intervals of 50 ft. One flashing arrow sign shall be placed at the beginning of the taper. A minimum of two drums or barricades shall be placed on the traffic approach side of each concrete patch or open hole.

4. Resurfacing

During resurfacing operations, ***1 lane*** *of through traffic in each direction shall be maintained at all times from 5:00 a.m. to 9:00 p.m. A minimum of one lane of through traffic in each direction shall be maintained at all times from 9:00 p.m. to 5:00 a.m.*

During the paving operation of the outside lane or ramps, closure of such ramps will be permitted for the shortest possible time while paving is being done in the outside lane in the vicinity of ramp exits or entrances, or in acceleration lanes, deceleration lanes, or gore areas. Ramp closures will not be permitted during rush hour periods as directed. The ramps for two consecutive interchanges shall not be closed at the same time.

During HMA base placement, the paving operation shall be limited to a segment including not more than two interchanges. All HMA base placement shall be completed in such segment prior to commencing with the next segment. When an outside lane is being paved, the adjacent shoulder shall be paved simultaneously.

Extension of a HMA course will be permitted for one lane, or one lane and shoulder, for a full day's placement. Such HMA course shall be placed on the adjacent lane and shoulder on the following day. If the Contractor does not plan to work on the following day, then such HMA course shall be placed on the adjacent lane and shoulder on the same day. An overnight lane closure shall be maintained on all courses over 220 lb/sq yd. Such closure shall be as shown on the plans.

Transverse joints shall be in accordance with 401.15 or 402.14.

801-T-216 LANE CLOSURES

(Revised 11-17-17)

The following closure schedule has been approved for this contract. Lanes shall be closed or restricted only during these times.

Interstate Route: **I-65/I-70**

Segment: **from exit 110B to exit 112 for I-65**
from exit 80 to exit 83A for I-70

Travel direction: Both Directions

Approved closure schedule:

Mainline

- NB I-65/EB I-70 Full Closures for one weekend for Fletcher Ave. and north half of Virginia Ave.
- NB I-65/EB I-70 Full Closures for one weekend for south half of Virginia Ave.
- SB I-65/WB I-70 and SB C-D System Full Closure for one weekend for Fletcher Ave.

Ramp Closures

- Calvary Street Entrance Ramp to NB I-65/EB I-70, 12 week full closure
- Washington Street Entrance Ramp to SB I-65/WB I-70, 1 weekend full closure

Local Roadway

- Fletcher Street, 12 week full closure
- South half of Virginia Street, 12 week full closure
- North half of Virginia Street, 12 week full closure

Additional conditions:

I-65, I-70, ramps and C-D system will be assessed liquidated damages of $1,000/hr for failure to open on time.

Local roadways will be assessed liquidated damages of $1,500/day for failure to open on time.

Shoulders along I-65 and I-70 may be reduced to 2 feet (minimum).

Intermittent 20 minute stoppages for I-65 and I-70 under Fletcher Ave. and Virginia Ave. from 10P to 4A with approval of the Engineer.

The full weekend closure for SB I-65/WB I-70 and SB C-D system shall be concurrent weekend closures.

The full weekend closure for NB I-65/EB I-70 for Fletcher Ave. and north half of Virginia Ave. shall be concurrent.
NB I-65 two lane closures may be allowed for weekend and nighttime.

The north half of Virgina Ave. and the south half of Virginia Ave. shall not be concurrent closures

Weekend closures shall be 9PM Friday night through 5AM Monday morning.

Nighttime single closures shall be 9PM through 5AM.
Nighttime two closures shall be 11PM through 4AM.

Full Closures for ramps and local streets shall be consecutive days

The SB C-D System closure begins south of the exit ramp to Ohio Street. The Washington St. entrance ramp to SB C-D System shall be closed concurrently with the C-D system full weekend closure.

The Contractor shall notify the Engineer of a ramp closure at least **21 days prior to the start of the closure.**

PCMSs shall be in place 14 days in advance of work to notify the traveling public and freight operators.

The Contractor shall coordinate with the Signal Systems group to facilitate signal retiming along the detour routes **21 days prior to the closure.**

The Contractor shall notify the INDOT Indianapolis Traffic Management Center of lane restrictions at least **21 days prior to lane restrictions.**

The Contractor shall notify the Indiana Motor Trucking Association and emergency responders at least **21 days prior to traffic changes.**