DESIGNATION	BRIDGE FILE
2200710	I469-18-07027 ANB & ASB
CONTRACT	
B-44533	

STRUCTURE INFORMATION				
STRUCTURE	TYPE	SPAN AND SKEW	OVER	STATION
I469-18-07027 ANB & ASB	TWIN CONTINUOUS COMPOSITE PLATE GIRDER BRIDGES	4 Spans: 65'-0", 145'-0", 145'-0" & 55'-0" Skew: 56°17'55" Lt.	I-469	15+26.77 Line "PR-1"

KIN PROJECT INFORMATION	
DESIGNATION	PROJECT DESCRIPTION
2200710 (Lead)	Minnich Rd NB over I-469
2200711	Minnich Rd SB over I-469

INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE REHABILITATION PLANS

FOR SPANS OVER 20 FEET

ROUTE: MINNICH ROAD AT: RP 17+71


DESIGNATION NO. 2200710 & 2200711

NO ADDITIONAL RIGHT-OF-WAY REQUIRED FOR THIS PROJECT

Superstructure Replacement on Minnich Road NB & SB over I-469
Located 1.73 Miles West of U.S. 30
Section 24, T-30-N, R-13-E, Adams Township, Allen County, Indiana
& Section 19, T-30-N, R-14-E, Jefferson Township, Allen County, Indiana

SCALE: 1" = 2000'

TRAFFIC DATA		MINNICH RD NB & SB	I-469 NB & SB
A.A.D.T.	(2026)	3,850 V.P.D.	23,910 V.P.D.
A.A.D.T.	(2046)	4,600 V.P.D.	28,550 V.P.D.
D.H.V.	(2046)	500 V.P.H.	15,030 V.P.H.
DIRECTIONAL DISTRIBUTION		51.9 %	50.1 %
TRUCKS		3.7 % A.A.D.T.	41.0 % A.A.D.T.
		2.4 % D.H.V.	28.0 % D.H.V.
DESIGN DATA			
DESIGN SPEED		45 M.P.H.	70 M.P.H.
PROJECT DESIGN CRITERIA		3R (NON-FREEWAY)	3R (FREEWAY)
FUNCTIONAL CLASSIFICATION		LOCAL AGENCY COLLECTOR	PRINCIPAL ARTERIAL
RURAL/URBAN		RURAL	RURAL
TERRAIN		LEVEL	LEVEL
ACCESS CONTROL		NONE	FULL



PROJECT LOCATION SHOWN BY
ALLEN COUNTY

LATITUDE:	41°02'22" N
LONGITUDE:	85°00'04" W

BRIDGE LENGTH:	0.079 MI.
ROADWAY LENGTH:	0.044 MI.
TOTAL LENGTH:	0.123 MI.
MAXIMUM GRADE:	3.13 %

INDIANA DEPARTMENT OF TRANSPORTATION
STANDARD SPECIFICATIONS DATED 2026
TO BE USED WITH THESE PLANS

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

AURY J. HEDENESS — REGISTERED — No. 300129 — STATE OF INDIANA — PROFESSIONAL ENGINEER

PLANS PREPARED BY: ENGINEERING RESOURCES, INC. (260) 490-1025 PHONE NUMBER

CERTIFIED BY: 7/31/2026 DATE

RECOMMENDED FOR LETTING: 09/28/2026 DATE
INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE FILE
I469-18-07027 ANB & ASB
DESIGNATION
2200710 & 2200711
SHEETS: 1 of 62
CONTRACT
B-44533

Jul 31,2026 - 10:53am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 01 - Title Sheet.dwg

UTILITIES

No Known Utilities Within Project Limits

811 Know what's **below.** **Call** before you dig.

INDIANA UNDERGROUND
1-800-382-5544 OR CALL 811
24 HOURS A DAY 7 DAYS A WEEK

GENERAL NOTES

INDEX

SHEET NO.	SUBJECT
1	Title Sheet
2	Index Sheet
3	Typical Cross Sections
4-15	Maintenance of Traffic
16-17	Plan and Profile
18	Pavement Markings
19-20	General Plan
21-22	Removal Details
23-24	Bent Details
25-26	Framing Plan
27-33	Structural Steel Details
34	Bearing Assembly Details
35-46	Floor Details
47-52	Railing Details
53-55	Screeds
56-61	RCBA Details
62	Summary Tables

REVISIONS

SHEET NO.	DATE	SUBJECT

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH
DRAWN: BKH
CHECKED: TRL
CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION


INDEX SHEET

SCALE	BRIDGE FILE
N/A	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	2 of 62
	CONTRACT
	B-44533


Jul 21 2026 - 10:26am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 02 - Index Sheet.dwg




TYPICAL FULL DEPTH SECTION
Scale: 1/4" = 1'-0"



TYPICAL FULL DEPTH SECTION
Scale: 1/4" = 1'-0"



HMA TRANSITION DETAIL
Scale: Not To Scale



Notes: Contractor Shall Verify Existing Berm Elevations

See Standard Drawing E 607-PDST-01 for Additional Information

PAVED SIDE DITCH, TYPE A, MODIFIED
Scale: 3/4" = 1'-0"

LEGEND

- (J2) 10 In., "Compacted Aggregate, No. 53"
- (K) "HMA for Patching, Full Depth, Type B", consisting of 165 #/SY HMA Surface, Type B, on 275 #/SY HMA Intermediate, Type B, on 660 #/SY HMA Base, Type B, on "Subgrade Treatment, Type IC" with "Geogrid, Type IB"
- (P2) "Asphalt for Tack Coat"
- (R) Asphalt Material for Transition 165 #/SY Min. "QC/QA-HMA, 2, 58S, Surface, 9.5mm", on "Milling, Transition"

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH


CHECKED: TRL | CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION


TYPICAL CROSS SECTIONS

SCALE	BRIDGE FILE
1/4" = 1'-0"	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	3 of 62
	CONTRACT
	B-44533


Jul 31, 2026 - 10:26am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd I69 & SB over I-469\Drawings\Plan Sheets\6149 - 04 - Typical Cross Sections.dwg



DETOUR ROUTE MARKER ASSEMBLIES



CONSTRUCTION SIGNS



DETOUR ROUTE
Not To Scale

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH DRAWN: JDI

CHECKED: TRL CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
MINNICH RD - DETOUR


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	4 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:26am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - Minnich.dwg


MINNICH RD - CONSTRUCTION SIGN TABLE

SYMBOL	DESCRIPTION	NUMBER	TYPE	PHASE				QTY.
				1	2	3	4	
(1)	Road Closed Ahead	XW20-3	A	6	6	6	6	6
(2)	Detour Ahead	XW20-2	A	2	2	2	2	2
(3)	Road Closed Ahead 1000 Ft	XW20-3	A	4	4	4	4	4
(4)	Road Closed Ahead 500 Ft	XW20-3	A	4	4	4	4	4
(5)	Road Closure Sign Assembly w/ "Road Closed" Sign	R11-2	**	2	2	2	2	2
(6)	Road Closure Sign Assembly w/ "Road Closed, Local Traffic Only" and "Detour" Signs	R11-3 XM4-10(L or R)	**	2	2	2	2	2
(7)	Road Closure Sign Assembly w/ "Road Closed, Local Traffic Only" Sign	R11-3	**	2	2	2	2	2
(8)	Advanced Notice of Closure Sign	XG20-5	A	2	2	2	2	2
(9)	Road Closure Sign Assembly w/ "Ramp Closed" Sign	R11-Y2b	**	-	-	2	2	2
(A)	Advanced Turn Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-6 M5-1(L or R)	**	9	9	9	9	9
(B)	Directional Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-6 M6-1	**	9	9	9	9	9
(C)	Confirming Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-6 M6-3	**	16	16	16	16	16
(D)	End Detour Route Marker Assembly	XM4-8a M3-(1-4) M1-6 M6-1	**	2	2	2	2	2
(E)	Advanced Turn Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-6 M5-2(L or R)	**	2	2	2	2	2
(F)	Directional Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-6 M6-2(L or R)	**	2	2	2	2	2
(G)	Advanced Turn Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-6 M5-3(L or R)	**	1	1	1	1	1
(H)	Advanced Turn Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-4 M5-1(L or R)	**	-	-	3	3	3
(I)	Directional Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-4 M6-1	**	-	-	3	3	3
(J)	Confirming Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-4 M6-3	**	-	-	8	8	8
(K)	End Detour Route Marker Assembly	XM4-8a M3-(1-4) M1-4 M6-1	**	-	-	2	2	2
(L)	Advanced Turn Detour Route Marker Assembly	XM4-8 M3-(1-4) M1-4 M5-3(L or R)	**	-	-	1	1	1
(3A)	Standard Barricade III-A		**	96 LFT	96 LFT	216 LFT	216 LFT	216 LFT
(3B)	Standard Barricade III-B		**	64 LFT	64 LFT	64 LFT	64 LFT	64 LFT

** Included in pay item other than Construction Sign, Type A, B, or C



ROAD CLOSURE PLAN - PHASES 3 & 4
Not To Scale



ROAD CLOSURE PLAN - PHASES 1 & 2
Not To Scale

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: JDI


CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION


MAINTENANCE OF TRAFFIC
MINNICH RD - DETOUR

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	5 of 62
	CONTRACT
	B-44533


Jul 31,2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - Minnich.dwg



I-469 - EXISTING SECTION
Scale: 1/4" = 1'-0"



I-469 - PHASE 1
Scale: 1/4" = 1'-0"



I-469 - PHASE 2
Scale: 1/4" = 1'-0"

LEGEND

W6 Temporary Pavement Marking, Removable, White, 6 in.

Y6 Temporary Pavement Marking, Removable, Yellow, 6 in.

NOTES

Traffic Control Devices shall be in accordance with INDOT Standard Drawings and Specifications.

CONSTRUCTION ZONE DESIGN SPEED IS 60 MPH

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH


CHECKED: TRL | CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION


MAINTENANCE OF TRAFFIC
I-469 - TYPICAL SECTIONS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	6 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg



I-469 - PHASE 3
Scale: 1/4" = 1'-0"



I-469 - PHASE 4
Scale: 1/4" = 1'-0"

LEGEND

W6 Temporary Pavement Marking, Removable, White, 6 in.

Y6 Temporary Pavement Marking, Removable, Yellow, 6 in.

NOTES

Traffic Control Devices shall be in accordance with INDOT Standard Drawings and Specifications.

CONSTRUCTION ZONE DESIGN SPEED IS 60 MPH

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER 7/31/2026 DATE

DESIGNED: BKH DRAWN: BKH


CHECKED: TRL CHECKED: TRL


INDIANA DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
I-469 - TYPICAL SECTIONS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	7 of 62
	CONTRACT
	B-44533


Jul 31, 2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg






ADVANCED SIGNAGE - PHASES 1, 2, & 3


Not To Scale






ADVANCED SIGNAGE - PHASE 4

Not To Scale



CONSTRUCTION SIGNS



LANE SHIFT DETAIL

Not To Scale

NOTES

Traffic Control Devices shall be in accordance with INDOT Standard Drawings and Specifications.

Spacing of channelizing devices shall be 60 ft on tapers, and 100 ft on all tangents.

Construction clear zone width = 30 ft.

All conflicting pavement markings to be removed/covered and replaced upon completion.

LEGEND

- Channelizing Device
- Direction of Traffic
- Construction Sign
- —x— Pavement Marking Removal/Cover
- (B6) Temporary Pavement Marking, Removable, Black, 6 in.
- (W6) Temporary Pavement Marking, Removable, White, 6 in.
- (Y6) Temporary Pavement Marking, Removable, Yellow, 6 in.

CONSTRUCTION ZONE DESIGN SPEED IS 60 MPH

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF Indiana PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH


CHECKED: TRL | CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
ADVANCED SIGNAGE

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	8 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg



NOTES

Traffic Control Devices shall be in accordance with INDOT Standard Drawings and Specifications.

Spacing of channelizing devices shall be 60 ft on tapers, and 100 ft on all tangents.

Construction clear zone width = 30 ft.

All conflicting pavement markings to be removed/covered and replaced upon completion.

LEGEND

- Channelizing Device
- Work Area
- Direction of Traffic
- Construction Sign
- Pavement Marking Removal/Cover
- B6 — Temporary Pavement Marking, Removable, Black, 6 in.
- W6 — Temporary Pavement Marking, Removable, White, 6 in.
- Y6 — Temporary Pavement Marking, Removable, Yellow, 6 in.

CONSTRUCTION ZONE DESIGN SPEED IS 60 MPH

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT L. HEIDENREICH — REGISTERED — No. 300129 — STATE OF INDIANA — PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH


CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
I-469 PHASE 1


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	9 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg




MOT I-469 - PHASE 2

Scale: 1" = 40'



MOT I-469 - PHASE 2

Scale: 1" = 40'



MOT I-469 - PHASE 2

Scale: 1" = 40'

NOTES

Traffic Control Devices shall be in accordance with INDOT Standard Drawings and Specifications.

Spacing of channelizing devices shall be 60 ft on tapers, and 100 ft on all tangents.

Construction clear zone width = 30 ft.

All conflicting pavement markings to be removed/covered and replaced upon completion.

LEGEND

- Channelizing Device
- Work Area
- Direction of Traffic
- Construction Sign
- Pavement Marking Removal/Cover

CONSTRUCTION ZONE DESIGN SPEED IS 60 MPH

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH
REGISTERED
No. 300129
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH


CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
I-469 PHASE 2

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	10 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg



NOTES

Traffic Control Devices shall be in accordance with INDOT Standard Drawings and Specifications.

Spacing of channelizing devices shall be 60 ft on tapers, and 100 ft on all tangents.

Construction clear zone width = 30 ft.

All conflicting pavement markings to be removed/covered and replaced upon completion.

LEGEND

- Channelizing Device
- Work Area
- Direction of Traffic
- Flashing Arrow Sign
- Construction Sign
- —x— Pavement Marking Removal/Cover
- B6 Temporary Pavement Marking, Removable, Black, 6 in.
- W6 Temporary Pavement Marking, Removable, White, 6 in.
- Y6 Temporary Pavement Marking, Removable, Yellow, 6 in.
- 3A Type IIIA Barricade

CONSTRUCTION ZONE DESIGN SPEED IS 60 MPH

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH
REGISTERED
No. 300129
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH


CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION


MAINTENANCE OF TRAFFIC
I-469 PHASE 3

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	11 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg



MOT I-469 - PHASE 4
Scale: 1" = 40'



MOT I-469 - PHASE 4
Scale: 1" = 40'

NOTES

Traffic Control Devices shall be in accordance with INDOT Standard Drawings and Specifications.

Spacing of channelizing devices shall be 60 ft on tapers, and 100 ft on all tangents.

Construction clear zone width = 30 ft.

All conflicting pavement markings to be removed/covered and replaced upon completion.

LEGEND

•	Channelizing Device
→	Direction of Traffic
◀	Flashing Arrow Sign
⊥⊥	Construction Sign
—x—	Pavement Marking Removal/Cover
B6	Temporary Pavement Marking, Removable, Black, 6 in.
W6	Temporary Pavement Marking, Removable, White, 6 in.
Y6	Temporary Pavement Marking, Removable, Yellow, 6 in.

CONSTRUCTION ZONE DESIGN SPEED IS 60 MPH

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH
REGISTERED
No. 300129
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BKH
CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
I-469 PHASE 4

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	12 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg



MOT I-469 - PHASE 4
Scale: 1" = 40'

MOT I-469 - PHASE 4
Scale: 1" = 40'

MOT I-469 - PHASE 4
Scale: 1" = 40'

NOTES

Traffic Control Devices shall be in accordance with INDOT Standard Drawings and Specifications.

Spacing of channelizing devices shall be 60 ft on tapers, and 100 ft on all tangents.

Construction clear zone width = 30 ft.

All conflicting pavement markings to be removed/covered and replaced upon completion.

LEGEND

- Channelizing Device
- Work Area
- Direction of Traffic
- Flashing Arrow Sign
- Construction Sign
- Pavement Marking Removal/Cover
- B6 — Temporary Pavement Marking, Removable, Black, 6 in.
- W6 — Temporary Pavement Marking, Removable, White, 6 in.
- Y6 — Temporary Pavement Marking, Removable, Yellow, 6 in.

CONSTRUCTION ZONE DESIGN SPEED IS 60 MPH

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH
REGISTERED
No. 300129
STATE OF INDIANA
PROFESSIONAL ENGINEER


RECOMMENDED FOR APPROVAL	DESIGN ENGINEER	7/31/2026 DATE
DESIGNED: BKH	DRAWN: BKH	
CHECKED: TRL	CHECKED: TRL	

INDIANA
DEPARTMENT OF TRANSPORTATION


MAINTENANCE OF TRAFFIC
I-469 PHASE 4

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	13 of 62
	CONTRACT
	B-44533


Jul 31, 2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg



MOT I-469 - PHASE 4
Scale: 1" = 40'



MOT I-469 - PHASE 4
Scale: 1" = 40'



MOT I-469 - PHASE 4
Scale: 1" = 40'

NOTES

Traffic Control Devices shall be in accordance with INDOT Standard Drawings and Specifications.

Spacing of channelizing devices shall be 60 ft on tapers, and 100 ft on all tangents.

Construction clear zone width = 30 ft.

All conflicting pavement markings to be removed/covered and replaced upon completion.

LEGEND

•	Channelizing Device
→	Direction of Traffic
◀	Flashing Arrow Sign
⊥⊥	Construction Sign
—x—	Pavement Marking Removal/Cover
B6	Temporary Pavement Marking, Removable, Black, 6 in.
W6	Temporary Pavement Marking, Removable, White, 6 in.
Y6	Temporary Pavement Marking, Removable, Yellow, 6 in.

CONSTRUCTION ZONE DESIGN SPEED IS 60 MPH

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

AURY J. HEDENCO — REGISTERED — No. 300129 — STATE OF INDIANA — PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH

CHECKED: TRL | CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
I-469 PHASE 4

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	14 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg

MOT SUMMARY TABLE

PAY ITEM	I-469				Minnich Road				UNIT	TOTAL
	PHASE 1	PHASE 2	PHASE 3	PHASE 4	PHASE 1	PHASE 2	PHASE 3	PHASE 4		
Temporary Pavement Markings, Removable 6 in., White	13,070	-	4,660	3,380	-	-	-	-	LFT	21,110
Temporary Pavement Markings, Removable 6 in., Yellow	4,825	-	2,330	5,595	-	-	-	-	LFT	12,750
Temporary Pavement Markings, Removable 6 in., Black	17,710	-	4,660	10,780	-	-	-	-	LFT	33,150
Temporary Traffic Barrier, Type 2, Anchored	1070	870	-	-	-	-	-	-	LFT	1070
Energy Absorbing Terminal, CZ-TL3	2	2	-	-	-	-	-	-	EACH	2
Construction Sign, Type A	48	44	48	52	18	18	18	18	EACH	70
Construction Sign, Type B	20	20	20	20	-	-	-	-	EACH	20
Flashing Arrow Sign	-	-	120	120	-	-	-	-	DAYS	240
Detour Route Marker Assembly	-	-	-	-	40	40	58	58	EACH	58
Road Closure Sign Assembly	-	-	-	-	6	6	8	8	EACH	8
Barricade, III-A	-	-	72	72	96	96	216	216	LFT	288
Barricade, III-B	-	-	-	-	64	64	64	64	LFT	64
Law Enforcement Officer	-	-	-	-	-	-	-	-	HOURS	400
Temporary Worksite Speed Limit Sign Assembly, Continuous	4	4	4	4	-	-	-	-	EACH	4

I-469 CONSTRUCTION SIGN TABLE

DESCRIPTION	NUMBER	TYPE	PHASE 1	PHASE 2	PHASE 3	PHASE 4	TOTAL
Speeding, Max $1000, Reckless Driving, Max 6 Yrs	XW2-6-A	A	6	6	4	4	6
Road Work Ahead	XW20-1	A	6	6	4	4	6
Road Work Ahead 3 Miles (Plaque)	XW 20-1 XW 16-2P	A B	4 4	4 4	4 4	4 4	4 4
Road Work Ahead 2 Miles (Plaque)	XW 20-1 XW 16-2P	A B	4 4	4 4	4 4	4 4	4 4
Road Work Ahead 1 1/2 Miles (Plaque)	XW 20-1 XW 16-2P	A B	4 4	4 4	4 4	4 4	4 4
Right Shoulder Closed Ahead (Plaque)	XW21-5a(R) W16-9P	A B	-	4 4	-	-	4 4
Left Shoulder Closed Ahead (Plaque)	XW21-5a(L) W16-9P	A B	4 4	-	-	-	4 4
Right Shoulder Closed	XW21-5a(R)	A	-	4	-	-	4
Left Shoulder Closed	XW21-5a(L)	A	4	-	-	-	4
Left Lane Closed Ahead	XW20-5(L)	A	-	-	-	4	4
Lane Ends Merge Right	XW9-2-B(R)	A	-	-	-	4	4
Lane Ends, Merge Right Symbol	XW4-2-A(L)	A	-	-	-	4	4
Left Reverse Curve, One Lane	XW1-4-B(L)	A	-	-	-	4	4
Right Reverse Curve, One Lane	XW1-4-B(R)	A	-	-	-	4	4
Left Reverse Curve, Two Lanes	XW1-4b-B(L)	A	2	-	4	-	4
Right Reverse Curve, Two Lanes	XW1-4b-B(R)	A	4	-	2	-	4
End Road Work	XG20-2	A	4	4	4	4	4

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT L. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BKH | CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
I-469 MOT SUMMARY

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	15 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 07 - MOT - I469.dwg



Rbr/Ref Cap Flush (Set)	Mag/Ref Washer Flush (Set)
N: 169327.350 E: 800936.683	N: 169110.106 E: 800895.697
SW EDGE: 9th Guardrail Post 23.1' 7° / 13.8' 164° NW Cor Bridge Ret-Wall / SW EDGE: 5th G-Rail Post 3.7' 74°	No Ref's Available
CONTROL POINT 3002	CONTROL POINT 3005

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BKH
CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE

HORIZONTAL SCALE	BRIDGE FILE
1" = 20'	I469-18-07027 ANB & ASB
VERTICAL SCALE	DESIGNATION
1" = 5'	2200710 & 2200711
	SHEETS
	16 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:27am
S:\Projects\Projects (6000-6999)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 08 - Plan and Profile.dwg



NOTES:

1. Guardrail Transition, Type MGS, Without Curb
2. Guardrail End Treatment, Type OS
3. Concrete Bridge Railing Transition, Type FC

Rbr/Ref Cap Flush (Set) N: 168844.633 E: 800948.884 13.1' 11° 3.2' 124° 23.4' 173° SW EDGE: 5th G-Rail Post NW EDGE: 8th G-Rail Post	Mag/Ref Washer Flush (Set) N: 168852.466 E: 800868.885 No Ref's Available	Mag/Ref Washer Flush (Set) N: 169155.440 E: 801064.723 No Ref's Available
CONTROL POINT 3001	CONTROL POINT 3006	CONTROL POINT 3007

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT L. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BKH | CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE

HORIZONTAL SCALE	BRIDGE FILE
1" = 20'	I469-18-07027 ANB & ASB
VERTICAL SCALE	DESIGNATION
1" = 5'	2200710 & 2200711
	SHEETS
	17 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 08 - Plan and Profile.dwg



PAVEMENT MARKINGS
Scale: 1" = 20'

PAVEMENT MARKINGS SUMMARY OF QUANTITIES

LOCATION	LINE PAINT				TRANSVERSE MARKINGS CROSSHATCH LINE	
	SOLID WHITE 6 IN.	SOLID YELLOW 6 IN.	BROKEN WHITE 6 IN.	BROKEN YELLOW 6 IN.	SOLID YELLOW 12 IN.	SOLID YELLOW 24 IN.
	FT	FT	FT	FT	FT	FT
Line "PR-1"	1,200	1,200		242	530	
TOTALS	1,200	1,200		242	530	

LEGEND

(34) "Line, Paint, Solid, White, 6 in."
(35) "Line, Paint, Solid, Yellow, 6 in."
(36) "Line, Paint, Solid, Yellow, 12 in."
(37) "Line, Paint, Broken, Yellow, 6 in."

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH
REGISTERED
No. 300129
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL
DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH
DRAWN: BKH
CHECKED: TRL
CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKINGS

SCALE	BRIDGE FILE
1" = 20'	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	18 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 24 - Pavement Markings.dwg

GENERAL NOTES

Plans for the existing structure are on file at the Central Office of the Indiana Department of Transportation under bridge file I469-18-07027 NB & SB.

Stations shown along Line "S-11-A" are based on existing plans and are for reference only.

The boundaries of all removal areas shall be saw cut. All saw cuts shall be a minimum of 1" vertical surface.


Where new work is to be fitted to old work, the Contractor shall verify all dimensions and conditions in the field and report any errors or discrepancies to the Engineer and assume responsibility for the correctness and the fit of the new part to the existing.

Reinforcing steel cover shall be 2 1/2" in top and 1" minimum in bottom of floor slab, 3" in footings, except bottom steel which shall be 4", and 2" in all other parts, unless noted.


Chamfer exposed concrete edges 1" unless otherwise noted.

For Sections, Bridge Rehabilitation Key, and Design Data, see Sheet 20.

STRUCTURE TO BE BUILT TO A 940' VERTICAL CURVE



ELEVATION
Scale: 3/64"=1'-0"



PLAN
Scale: 3/64"=1'-0"

TWIN CONTINUOUS COMPOSITE PLATE GIRDER BRIDGES
4 SPANS: 65'-5", 145'-0", 145'-0", 55'-5"
60'-0" CLEAR ROADWAY WIDTH, 56° 17' 55" SKEW LT.
MINNICH ROAD NB & SB OVER I-469
ALLEN COUNTY

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: RPG
CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

GENERAL PLAN

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	19 of 62
	CONTRACT
	B-44533


Jul 21, 2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 28 - General Plan.dwg



EXISTING SECTION
Scale: 1/4" = 1'-0"

LEGEND

Present Structure, Remove Portions



PROPOSED SECTION
Scale: 1/4" = 1'-0"

BRIDGE REHABILITATION KEY

1. Remove the existing 8 1/2" reinforced concrete deck and replace with new 8" (min.) reinforced concrete deck. The existing longitudinal joint between the decks will be eliminated.
2. Install new Type OS deck drains at each quadrant.
3. Install Type 1-A joint between reinforced concrete bridge approach (RCBA) and end of bridge floor.
4. Install new elastomeric bearing pads at each girder at the end bent.
5. Remove the existing W36 and W33 beams in Spans A & D. Remove 2'-0" of existing main span plate girders and splice new tapered plate girders with bolted web and flange splice plate connections. New steel superstructure will be coated.
6. Remaining existing steel superstructure in the main spans to be cleaned and coated.
7. Install new concrete diaphragm between girders at Bents 1 & 5.
8. Remove existing mudwall and install new mudwall at Bents 1 & 5.
9. Remove existing Type SS expansion joint frame and expansion joint. Install new precompressed foam joint between new bridge deck and new mudwall.
10. Remove and replace drainage trough in berm adjacent to end bent.
11. Install inspection holes in slopewall and fill voids with flowable fill, non-removable.
12. Patch existing pier columns (approx. 40 sft).
13. Remove the existing Concrete Bridge Railings. Construct new Concrete Bridge Railings, Type FC and apply surface seal.
14. Remove the existing RCBA's and install new 12" RCBA's on subbase for PCCP. Connect the new RCBA's to the new deck using threaded tie-bar assemblies. Connect the new RCBA's to the wingwalls with dowels.
15. Remove the existing Concrete Bridge Railing Transitions. Construct new Concrete Bridge Railing Transitions, Type TFC, on the new RCBA's and apply surface seal.
16. Remove the existing guardrail. Install MGS Guardrail Transition without Curb, MGS W-Beam Guardrail, and Guardrail Terminal System, Type OS at all four corners.
17. Remove and replace 3 feet of full depth HMA adjacent to each RCBA.
18. Mill 50 feet of approach pavement and transition the profile grade.
19. Replace pavement markings within project limits. If any temporary pavement markings are required, they shall be removable only. No removal by water, blasting, or grinding will be permitted on the new wearing surface or RCBA's.
20. Install new barrier delineators.

DESIGN STRENGTH

CONCRETE

Class C	f'c = 4,000 psi
Class B	f'c = 3,000 psi
Class A	f'c = 3,500 psi

REINFORCING STEEL

Grade 60	f'y = 60,000 psi

CONSTRUCTION LOADING
The exterior girder has been checked for strength, deflection, and overturning using the construction loads shown below. Cantilever overhang brackets were assumed for support of the deck overhang past the edge of the exterior girder. Finishing machine was assumed to be supported 6 in. outside the vertical coping form. The bottom overhang brackets were assumed to be braced against the intersection of the girder bottom flange and web.

DECK FALSEWORK LOADS
Designed for 15 psf for permanent metal stay-in-place deck forms, removable deck forms, and a 2-ft exterior walkway.

CONSTRUCTION LIVE LOAD
Designed for 20 psf extending 2 ft past the edge of coping and 75 psf vertical force applied at a distance of 6 in. outside the face of coping over a 30-ft length of the deck centered with the finishing machine.

FINISHING-MACHINE LOAD
4500 lb distributed over 10 ft along the coping.

DESIGN DATA

LIVE LOAD
Deck and new superstructure designed for HL-93 loading, in accordance with AASHTO LRFD Bridge Design Specifications, Ninth Edition, 2020 and interims revisions.

DEAD LOAD
Actual weight plus 35 psf for future wearing surface and 15 psf for permanent metal deck forms.

Substructure and original superstructure designed for HS20-44 loading in accordance with the 1983 AASHTO specifications.

TWIN CONTINUOUS COMPOSITE PLATE GIRDER BRIDGES
4 SPANS: 65'-5", 145'-0", 145'-0", 55'-5"
60'-0" CLEAR ROADWAY WIDTH, 56° 17' 55" SKEW LT.
MINNICH ROAD NB & SB OVER I-469
ALLEN COUNTY

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH DRAWN: RPG
CHECKED: TRL CHECKED: TRL


INDIANA
DEPARTMENT OF TRANSPORTATION

GENERAL PLAN


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	20 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 28 - General Plan.dwg


STRUCTURE IS BUILT TO A 940' VERTICAL CURVE



ELEVATION



PLAN
Scale: 3/64" = 1'-0"



EXISTING SECTION
Scale: 1/4" = 1'-0"

LEGEND

- Present Structure, Remove Portions
- Pavement Removal

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT L. HEIDENREICH — REGISTERED — No. 300129 — STATE OF INDIANA — PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 — DATE

DESIGNED: BKH | DRAWN: BKH


CHECKED: TRL | CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION


REMOVAL DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	21 of 62
	CONTRACT
	B-44533


Jul 31,2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 29 - Removal Details.dwg




TYPICAL END SPAN SPLICE REMOVAL DETAIL
Scale: 1/2" = 1'-0"




WINGWALL "A" ELEVATION - BENT NO. 1
Scale: 1/4" = 1'-0"




WINGWALL "B" ELEVATION - BENT NO. 1
Scale: 1/4" = 1'-0"




SECTION A-A
Scale: 1/4" = 1'-0"



WINGWALL "D" ELEVATION - BENT NO. 5
Scale: 1/4" = 1'-0"



WINGWALL "C" ELEVATION - BENT NO. 5
Scale: 1/4" = 1'-0"



TYPICAL END BENT SECTION
Scale: 1/2" = 1'-0"

LEGEND

- Present Structure, Remove Portions
- Pavement Removal

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH
REGISTERED
No. 300129
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BKH
CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

REMOVAL DETAILS


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	22 of 62
	CONTRACT
	B-44533

Jul 21 2026 - 10:27am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 29 - Removal Details.dwg



TYPICAL END BENT PLAN
Scale: 3/4" = 1'-0"

* in Field Drilled Hole in Concrete



* in Field Drilled Hole in Concrete

TYPICAL END BENT ELEVATION (LOOKING AT FRONT FACE)
Scale: 1/4" = 1'-0"

NOTES

For End Bent Section, Bill of Materials, and Bar Bending Details, see Sheet 26.

For Sections W-W and X-X, see RCBA Details, Sheet 62.

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH DRAWN: MRD
CHECKED: TRL CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

BENT DETAILS


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	23 of 62
	CONTRACT
	B-44533

Sep 28,2026 - 10:57am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 30 - Bent Details.dwg



* in Field Drilled Hole in Concrete. Embed Bar 6 in. using an approved anchor system.

SECTION A-A
Scale: 3/4" = 1'-0"



BAR BENDING DETAILS
Not To Scale


BILL OF MATERIALS
ONE END BENT
(TWO REQUIRED)

EPOXY COATED REINFORCING BARS			
MARK OR SIZE	NO. REQ'D	LENGTH	WEIGHT
520E	8	7'-7"	
521E	109	5'-10"	
522E	2	6'-4"	
523E	3	7'-0"	
524E	6	3'-11"	
525E	6	4'-5"	
526E	6	4'-8"	
527E	6	4'-11"	
528E	103	4'-7"	
529E	4	6'-5"	
530E	105	5'-5"	
531E	4	5'-2"	
532E	2	4'-9"	
533E	4	3'-0"	
534E	4	1'-9"	
#5E	12	28'-2"	
#5E	36	27'-9"	
#5E	4	27'-3"	
#5E	120	4'-0"	
Total #5 Epoxy Coated Reinf. Bars			4,047#
Total Epoxy Coated Reinf. Bars			4,047#

CONCRETE	
Concrete, Class A, Substructure (Bent No. 1)	34.6 CYS
Concrete, Class A, Substructure (Bent No. 5)	33.6 CYS

MISCELLANEOUS	
Aggregate for End Bent Backfill	50 CYS
Concrete Surface Coating, Armor X*	330 SFT
Geotextiles for Pavement, Type 2B	100 SYS
Field Drilled Holes in Concrete	237 EA
Threaded Tie Bar Assembly, Epoxy Coated	34 EA


* Estimated Quantity. To be paid for as "LS".




* Contractor to Field Verify Dimensions

CONCRETE SURFACE COATING BLOCKOUT PLAN
Scale: 3/4" = 1'-0"


LEGEND
Concrete Surface Coating Area (See Special Provisions)




CONCRETE SURFACE COATING SECTION @ JOINT IN MUDWALL
Scale: 3/4" = 1'-0"



CONCRETE SURFACE COATING SECTION BETWEEN BEARINGS
Scale: 3/4" = 1'-0"



CONCRETE SURFACE COATING SECTION @ BEARING PAD
Scale: 3/4" = 1'-0"



THREADED TIE BAR ASSEMBLY
Not To Scale

NOTES

For Plan and Elevation, see Sheet 25.

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025 www.eri.consulting
4175 New Vision Drive Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH DRAWN: MRD


CHECKED: TRL CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

BENT DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	24 of 62
	CONTRACT
	B-44533

Sep 28, 2026 - 11:34am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 30 - Bent Details.dwg



FRAMING PLAN - SPAN A

Scale: 1/8" = 1'-0"

NOTES

All structural steel shall be coated A709, Grade 50, unless noted otherwise.

All bolts shall be 7/8" Dia. High Strength F3125 ASTM A325, Type 1 in 15/16" Dia. holes, unless noted otherwise.

All bolted splice connections shall be prepared as Class B connections.

Clean Existing steel and coat all new and existing steel except for top of beams and shear connectors.

Estimated Weight of Structural Steel is 207,430 lbs.

Construction Sequence

The suggested partial superstructure replacement was designed in accordance with the following sequence:

1. Removal of the existing bridge railing and deck.

2. Removal of the existing cross-frames in Spans A and D.


3. Removal of the existing beam, pin, and hanger connection, and portion of girder (to splice location shown on plans) from Spans A and D (Salvage retrofitted pin and hangar connections from Span A, Beams 1, 6, 7, and 8 - See Special Provisions).

4. Install new girders and web splice plates shown on Framing Plan.

5. Install flange splice plates shown on Framing Plan.


6. Install cross frames and shear studs.

7. Follow Screed Procedure and Notes. After approval from Engineer, pour diaphragms and deck in accordance with the Pour Diagram and Notes.




BOTTOM TAPER WELD DETAIL

Scale: 1 1/2" = 1'-0"




TOP TAPER WELD DETAIL

Scale: 1 1/2" = 1'-0"




TYPICAL STIFFENER OR CONNECTION PLATE TO EXISTING GIRDER DETAIL

Scale: 1" = 1'-0"




TOP TAPER DETAIL

Scale: 1" = 1'-0"



BOTTOM TAPER DETAIL

Scale: 1" = 1'-0"



TYPICAL STIFFENER OR CONNECTION PLATE TO PROPOSED GIRDER DETAIL

Scale: 1" = 1'-0"

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

AURY J. HEDENECK REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH

CHECKED: TRL | CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

FRAMING PLAN

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	25 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 31 - Framing Plan.dwg


NOTES

All structural steel shall be coated A709, Grade 50, unless noted otherwise.

All bolts shall be 7/8" Dia. High Strength F3125 ASTM A325, Type 1 in 15/16" Dia. holes, unless noted otherwise.


All bolted splice connections shall be prepared as Class B connections.

Clean Existing steel and coat all new and existing steel except for top of beams and shear connectors.




FRAMING PLAN - SPAN D


Scale: 1/8" = 1'-0"



TOP FLANGE PLAN




BOT FLANGE PLAN



ELEVATION


END OF GIRDER DETAIL

Scale: 3/4" = 1'-0"




END OF STIFFENER OR CONNECTION PLATE DETAIL

Not To Scale




SHEAR STUD CONNECTOR DETAIL

Scale: 1 1/2" = 1'-0"



BEARING STIFFENER DETAIL

Scale: 1" = 1'-0"



SHEAR STUD CONNECTOR @ SPLICE DETAIL

Scale: 1 1/2" = 1'-0"

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KARL J. HEDENSKOG REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL	DESIGN ENGINEER	7/31/2026 DATE
DESIGNED: BKH	DRAWN: BKH	
CHECKED: TRL	CHECKED: TRL	

INDIANA
DEPARTMENT OF TRANSPORTATION

FRAMING PLAN

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	26 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Mimtech Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 31 - Framing Plan.dwg

NOTES


All structural steel shall be coated A709, Grade 50, unless noted otherwise.

All bolts shall be 7/8" Dia. High Strength F3125 ASTM A325, Type 1 in 15/16" Dia. holes, unless noted otherwise.

All bolted splice connections shall be prepared as Class B connections.

Clean Existing steel and coat all new and existing steel except for top of beams and shear connectors.

Shear studs shall be automatically welded to the girder by the use of a stud weld gun. The welds shall be of sufficient strength to permit the studs to be bent 30°. Top of beams to be cleaned prior to installation of shear studs. As a minimum, studs shall be embedded 2" into the bottom of the slab.




GIRDERS 1 & 5 ELEVATION - SPAN A

Scale: 1/4" = 1'-0"

*1" x 8" Connection Plate
on West Side of Girder
(See K-Frame Detail - Span A)

1" x 8" Transverse Stiffener
on East Side of Girder
(See Typical Stiffener or Connection Plate to Proposed Girder Detail)



GIRDERS 4 & 8 ELEVATION - SPAN A

Scale: 1/4" = 1'-0"

*1" x 8" Transverse Stiffener
on West Side of Girder
(See Typical Stiffener or Connection Plate to Proposed Girder Detail)

1" x 8" Connection Plate
on East Side of Girder
(See Cross-Frame Detail - Span A)

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH DRAWN: BKH

CHECKED: TRL CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

STRUCTURAL STEEL DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	27 of 62
	CONTRACT
	B-44533

Jul 21, 2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 31 - Framing Plan.dwg

NOTES


All structural steel shall be coated A709, Grade 50, unless noted otherwise.

All bolts shall be 7/8" Dia. High Strength F3125 ASTM A325, Type 1 in 15/16" Dia. holes, unless noted otherwise.

All bolted splice connections shall be prepared as Class B connections.

Clean Existing steel and coat all new and existing steel except for top of beams and shear connectors.


Shear studs shall be automatically welded to the girder by the use of a stud weld gun. The welds shall be of sufficient strength to permit the studs to be bent 30°. Top of beams to be cleaned prior to installation of shear studs. As a minimum, studs shall be embedded 2" into the bottom of the slab.



GIRDERS 2, 3, 6 & 7 WEST ELEVATION - SPAN A

Scale: 1/4" = 1'-0"

*1" x 8" Connection Plate (See K-Frame Detail - Span A)



GIRDERS 2, 3, 6 & 7 EAST ELEVATION - SPAN A

Scale: 1/4" = 1'-0"

*1" x 8" Connection Plate (See Cross-Frame Detail - Span A)

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH


CHECKED: TRL | CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

STRUCTURAL STEEL DETAILS


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	28 of 62
	CONTRACT
	B-44533

Jul 21, 2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 31 - Framing Plan.dwg




SPLICE SECTION - SPAN A

Scale: 1" = 1'-0"




WEB SPLICE - SPAN A

Scale: 1" = 1'-0"




FLANGE SPLICES - SPAN A

Scale: 1 1/2" = 1'-0"




TOP FLANGE SPLICE - SPAN D

Scale: 1 1/2" = 1'-0"




EXISTING GIRDER SPLICE SECTION - SPAN D

Scale: 1" = 1'-0"




PROPOSED GIRDER SPLICE SECTION - SPAN D

Scale: 1" = 1'-0"



WEB SPLICE - SPAN D

Scale: 1" = 1'-0"



BOTTOM FLANGE SPLICE - SPAN D

Scale: 1 1/2" = 1'-0"

NOTES

All structural steel shall be coated A709, Grade 50, unless noted otherwise.

All bolts shall be 7/8" Dia. High Strength F3125 ASTM A325, Type 1 in 15/16" Dia. holes, unless noted otherwise.

All bolted splice connections shall be prepared as Class B connections.

Clean Existing steel and coat all new and existing steel except for top of beams and shear connectors.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH
REGISTERED
No. 300129
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL
DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH
DRAWN: MRD
CHECKED: TRL
CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

STRUCTURAL STEEL DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	29 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 31 - Framing Plan.dwg

NOTES


All structural steel shall be coated A709, Grade 50, unless noted otherwise.

All bolts shall be 7/8" Dia. High Strength F3125 ASTM A325, Type 1 in 15/16" Dia. holes, unless noted otherwise.

All bolted splice connections shall be prepared as Class B connections.

Clean Existing steel and coat all new and existing steel except for top of beams and shear connectors.

Shear studs shall be automatically welded to the girder by the use of a stud weld gun. The welds shall be of sufficient strength to permit the studs to be bent 30°. Top of beams to be cleaned prior to installation of shear studs. As a minimum, studs shall be embedded 2" into the bottom of the slab.




GIRDERS 1 & 5 ELEVATION - SPAN D

Scale: 1/4" = 1'-0"

*1" x 8" Connection Plate
on West Side of Girder
(See Cross-Frame Detail - Span D)

1" x 8" Transverse Stiffener
on East Side of Girder
(See Typical Stiffener or Connection Plate to Proposed Girder Detail)



GIRDERS 4 & 8 ELEVATION - SPAN D

Scale: 1/4" = 1'-0"

*1" x 8" Transverse Stiffener
on West Side of Girder
(See Typical Stiffener or Connection Plate to Proposed Girder Detail)

1" x 8" Connection Plate
on East Side of Girder
(See Diaphragm Detail - Span D)

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH DRAWN: BKH

CHECKED: TRL CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

STRUCTURAL STEEL DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	30 of 62
	CONTRACT
	B-44533

Jul 21, 2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 31 - Framing Plan.dwg

NOTES


All structural steel shall be coated A709, Grade 50, unless noted otherwise.

All bolts shall be 7/8" Dia. High Strength F3125 ASTM A325, Type 1 in 15/16" Dia. holes, unless noted otherwise.

All bolted splice connections shall be prepared as Class B connections.

Clean Existing steel and coat all new and existing steel except for top of beams and shear connectors.


Shear studs shall be automatically welded to the girder by the use of a stud weld gun. The welds shall be of sufficient strength to permit the studs to be bent 30°. Top of beams to be cleaned prior to installation of shear studs. As a minimum, studs shall be embedded 2" into the bottom of the slab.



GIRDERS 2, 3, 6 & 7 WEST FACE ELEVATION - SPAN D

Scale: 1/4" = 1'-0"

*1" x 8" Connection Plate (See Cross-Frame Detail - Span D)



GIRDERS 2, 3, 6 & 7 EAST FACE ELEVATION - SPAN D

Scale: 1/4" = 1'-0"

*1" x 8" Connection Plate (See Diaphragm Detail - Span D)

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH


CHECKED: TRL | CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

STRUCTURAL STEEL DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	31 of 62
	CONTRACT
	B-44533

Jul 21, 2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 31 - Framing Plan.dwg




TENSION & COMPRESSION ELEVATION

Scale: 1/16" = 1'-0" Horiz.
1/8" = 1'-0" Vert.


LEGEND

(T) - TENSION
(C) - COMPRESSION
(R) - REVERSAL



COATING DETAIL

Scale: 1/16" = 1'-0" Horiz.
1/8" = 1'-0" Vert.



GIRDER SECTION

Scale: 1/2" = 1'-0"

NOTES

All structural steel shall be coated A709, Grade 50, unless noted otherwise.

All bolts shall be 7/8" Dia. High Strength F3125 ASTM A325, Type 1 in 15/16" Dia. holes, unless noted otherwise.

All bolted splice connections shall be prepared as Class B connections.

Clean Existing steel and coat all new and existing steel except for top of beams and shear connectors.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: MRD
CHECKED: TRL | CHECKED: TRL

INDIANA
DEPARTMENT OF TRANSPORTATION

STRUCTURAL STEEL DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	32 of 62
	CONTRACT
	B-44533


Jul 31,2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 31 - Framing Plan.dwg

NOTES


All structural steel shall be coated A709, Grade 50, unless noted otherwise.

All bolts shall be 7/8" Dia. High Strength F3125 ASTM A325, Type 1 in 15/16" Dia. holes, unless noted otherwise.


Clean Existing steel and coat all new and existing steel except for top of beams and shear connectors.




K-FRAME - SPAN D CONNECTION PLATE DETAIL
Scale: 1 1/2" = 1'-0"




K-FRAME - SPAN A CONNECTION PLATE DETAIL
Scale: 1 1/2" = 1'-0"




DIAPHRAGM DETAIL - SPAN D
Scale: 3/4" = 1'-0"




DIAPHRAGM DETAIL - SPAN A
Scale: 3/4" = 1'-0"




SECTION Y-Y
Scale: 1 1/2" = 1'-0"




SECTION X-X
Scale: 1 1/2" = 1'-0"




CROSS-FRAME DETAIL - SPAN D
Scale: 3/4" = 1'-0"




CROSS-FRAME DETAIL - SPAN A
Scale: 3/4" = 1'-0"



TYPICAL FRAME BOLTED CONNECTION DETAIL
Scale: 1 1/2" = 1'-0"



K-FRAME DETAIL - SPAN D
Scale: 3/4" = 1'-0"



K-FRAME DETAIL - SPAN A
Scale: 3/4" = 1'-0"

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH — REGISTERED No. 300129 STATE OF INDIANA — PROFESSIONAL ENGINEER


RECOMMENDED FOR APPROVAL	DESIGN ENGINEER	7/31/2026 DATE
DESIGNED: BKH	DRAWN: BKH	
CHECKED: TRL	CHECKED: TRL	

INDIANA
DEPARTMENT OF TRANSPORTATION


STRUCTURAL STEEL DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	33 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Munich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 31 - Framing Plan.dwg




ELEVATION



SECTION A-A


ELASTOMERIC BEARING ASSEMBLY - BENT NO. 1

Scale: 1 1/2" = 1'-0"




FLANGE CONNECTION PLATE DETAIL - BENT NO. 1

Scale: 1 1/2" = 1'-0"




BEARING TOP PLATE DETAIL - BENT NO. 1

Scale: 1 1/2" = 1'-0"




ELEVATION



SECTION B-B


ELASTOMERIC BEARING ASSEMBLY - BENT NO. 5

Scale: 1 1/2" = 1'-0"




FLANGE CONNECTION PLATE DETAIL - BENT NO. 5

Scale: 1 1/2" = 1'-0"




BEARING TOP PLATE DETAIL - BENT NO. 5

Scale: 1 1/2" = 1'-0"



PLAN


NOTE: See Standard Drawing E 726-BEBP-05 for Additional Information



SECTION C-C


ELASTOMERIC BEARING PAD DETAIL, S5-B

Scale: 1 1/2" = 1'-0"




SWEDGED ANCHOR BOLT DETAIL

Scale: 1 1/2" = 1'-0"



PLAN VIEW



ELEVATION VIEW

SIDE RETAINER DETAIL

Scale: 3" = 1'-0"

SHIM PLATE TABLE

	Bent No. 1	Bent No. 5
Beam Line 1	1 1/16"	3/4"
Beam Line 2	1 1/8"	11/16"
Beam Line 3	1 7/16"	7/16"
Beam Line 4	1 5/16"	1/16"
Beam Line 5	1 7/16"	7/8"
Beam Line 6	1 7/8"	5/8"
Beam Line 7	2 3/16"	0"
Beam Line 8	2 3/8"	3/16"

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH DRAWN: MRD


CHECKED: TRL CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

BEARING ASSEMBLY DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	34 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Mimich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 34 - Bearing Assembly Details.dwg



SLAB PLAN - TOP BARS

Scale: 3/16" = 1'-0"

NOTES

For Deck Drain Detail, See Sheet 46.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bar Bending Details and Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: RPG


CHECKED: AJI | CHECKED: AJI

INDIANA DEPARTMENT OF TRANSPORTATION

FLOOR DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	35 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg



SLAB PLAN - TOP BARS
Scale: 3/16" = 1'-0"

NOTES

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bar Bending Details and Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: RPG
CHECKED: AJI | CHECKED: AJI

INDIANA DEPARTMENT OF TRANSPORTATION

FLOOR DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	36 of 62
	CONTRACT
	B-44533

Jul 21, 2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg



SLAB PLAN - TOP BARS
Scale: 3/16" = 1'-0"

NOTES

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bar Bending Details and Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: RPG
CHECKED: AJI | CHECKED: AJI

INDIANA
DEPARTMENT OF TRANSPORTATION

FLOOR DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	37 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg



SLAB PLAN - TOP BARS

Scale: 3/16" = 1'-0"

NOTES

For Deck Drain Detail, See Sheet 46.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bar Bending Details and Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEDENSKOG REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: RPG | CHECKED: AJI | CHECKED: AJI

INDIANA DEPARTMENT OF TRANSPORTATION

FLOOR DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	38 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Mmnch Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg



SLAB PLAN - BOTTOM BARS

Scale: 3/16" = 1'-0"

NOTES

For Deck Drain Detail, See Sheet 46.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bar Bending Details and Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KARL J. HEDGENCOCK REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: RPG


CHECKED: AJI | CHECKED: AJI

INDIANA DEPARTMENT OF TRANSPORTATION

FLOOR DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	39 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg



SLAB PLAN - BOTTOM BARS
Scale: 3/16" = 1'-0"

NOTES

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bar Bending Details and Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH — REGISTERED — No. 300129 — STATE OF INDIANA — PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: RPG
CHECKED: AJI | CHECKED: AJI

INDIANA
DEPARTMENT OF TRANSPORTATION

FLOOR DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	40 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg



SLAB PLAN - BOTTOM BARS

Scale: 3/16" = 1'-0"

NOTES

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bar Bending Details and Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH
REGISTERED
No. 300129
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: RPG


CHECKED: AJI | CHECKED: AJI

INDIANA DEPARTMENT OF TRANSPORTATION

FLOOR DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	41 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:28am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg



SLAB PLAN - BOTTOM BARS

Scale: 3/16" = 1'-0"

NOTES

For Deck Drain Detail, See Sheet 46.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bar Bending Details and Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH DRAWN: RPG


CHECKED: AJI CHECKED: AJI

INDIANA
DEPARTMENT OF TRANSPORTATION

FLOOR DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	42 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg



POUR DIAGRAM
Not to Scale

POUR DIAGRAM NOTES

Diaphragms at Bent No. 1 and Bent No. 5 shall be poured before the slab is poured.

Pour numbers indicate sequence of pours. Pours over interior supports shall be made last to reduce the effect of the slab dead load in the negative moment area.

All pour sequences and procedures shall be submitted in accordance with Section 704.04 of the Standard Specifications.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: RPG
CHECKED: AJI | CHECKED: AJI

INDIANA
DEPARTMENT OF TRANSPORTATION

FLOOR DETAILS


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	43 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg



TYPICAL CONCRETE DIAPHRAM PLAN


Scale: 1/4" = 1'-0"



Front Elevation Notes - Dimensions are Measured Along ℄ Bearing
- Girder Locations and Reinforcement Shown along ℄ Bearing for Clarity

TYPICAL CONCRETE DIAPHRAM FRONT ELEVATION

Scale: 1/4" = 1'-0"



Rear Elevation Notes - Dimensions are Measured Along ℄ Bearing
- Girder Locations and Reinforcement Shown along ℄ Bearing for Clarity

TYPICAL CONCRETE DIAPHRAM REAR ELEVATION

Scale: 1/4" = 1'-0"

NOTES

For Section X-X and Shear Studs Detail, See Sheet 45.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: JDI


CHECKED: AJI | CHECKED: AJI

INDIANA
DEPARTMENT OF TRANSPORTATION


FLOOR DETAILS

SCALE	BRIDGE FILE
1/4" = 1'-0"	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	44 of 62
	CONTRACT
	B-44533


Jul 31, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg




SECTION X-X
Scale: 3/4" = 1'-0"




SHEAR STUDS DETAIL
Scale: 3/4" = 1'-0"




SECTION Y-Y
Scale: 3/4" = 1'-0"



TYPICAL SECTION - PROPOSED JOINT LIMITS
Scale: 1/4" = 1'-0"



RAILING JOINT DETAIL
Scale: 3/4" = 1'-0"



JOINT DETAIL
Scale: 1" = 1'-0"

NOTES

For Front Elevation and Rear Elevation, See Sheet 44.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

All Reinforcing Bars shall be epoxy-coated.

For Bill of Materials, see Sheet 46.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: JDI


CHECKED: AJI | CHECKED: AJI

INDIANA DEPARTMENT OF TRANSPORTATION


FLOOR DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	45 of 62
	CONTRACT
	B-44533


Jul 21, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg




BAR BENDING DETAILS
Not to Scale



BAR CUTTING DIAGRAM #1
36 - #6E X 36'-4"



BAR CUTTING DIAGRAM #2
30 - #6E X 36'-0"



BAR CUTTING DIAGRAM #3
36 - 605E

NOTES

For Slab Plans, See Sheets 35 through 42.

All reinforcing bars shall be epoxy-coated.


For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

BILL OF MATERIALS
ONE CONCRETE DIAPHRAM
(TWO REQUIRED)

EPOXY COATED REINFORCING BARS			
MARK OR SIZE	NO. REQ'D	LENGTH	WEIGHT
#7E	16	30'-6"	
#7E	24	15'-10"	
#7E	4	8'-2"	
Total #7 Epoxy Coated Reinf. Bars			1,842#
611E	90	8'-11"	
612E	14	8'-2"	
613E	90	9'-6"	
#6E	24	5'-0"	
Total #6 Epoxy Coated Reinf. Bars			2,842#
Total Epoxy Coated Reinf. Bars			4,684#
CONCRETE			
Concrete, Class C, Superstructure			23.6 CYS

BILL OF MATERIALS
BRIDGE DECK


EPOXY COATED REINFORCING BARS			
MARK OR SIZE	NO. REQ'D	LENGTH	WEIGHT
601E	8	3'-6"	
602E	4	3'-10"	
603E	1242	4'-5"	
604E	1096	33'-5"	
605E	72	37'-8"	
#6E	12	38'-4"	
#6E	1140	38'-0"	
#6E	72	36'-4"	
#6E	120	36'-0"	
#6E	1096	33'-0"	
#6E	188	32'-9"	
#6E	376	31'-8"	
#6E	282	29'-4"	
Total #6 Epoxy Coated Reinf. Bars			237,444#
#5E	1046	39'-11"	
#5E	32	3'-6"	
Total #5 Epoxy Coated Reinf. Bars			43,668#
Total Epoxy Coated Reinf. Bars			281,112#
CONCRETE			
Concrete, Class C, Superstructure			679.4 CYS
MISCELLANEOUS			
Grates, Basins, and Fittings, Cast Iron			4 EA
Longitudinal Grooving			2,906 SYS



	Dim. "A"*
NE Corner	9'-10 1/2"
SE Corner	4'-1 3/4"
NW Corner	4'-1 3/4"
SW Corner	9'-10 1/2"

DECK DRAIN DETAIL
Scale: 1/2" = 1'-0"
(Northwest Corner Shown, Other Corners Sim.)


*Contractor to Field Verify Location of Deck Drains to Coordinate with Existing Drain Outlet Locations Below.



SECTION THROUGH FLOOR DRAIN

TYPICAL PLAN

DECK DRAIN DETAIL
Scale: 3/4" = 1'-0"



TYPICAL SECTION
Scale: 1/4" = 1'-0"

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH — REGISTERED — No. 300129 — STATE OF INDIANA — PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: RPG | CHECKED: AJI | CHECKED: AJI


INDIANA DEPARTMENT OF TRANSPORTATION


FLOOR DETAILS


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	46 of 62
	CONTRACT
	B-44533

Jul 21, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 35 - Floor Details.dwg









EAST BRIDGE RAILING ELEVATION

Scale: 1/2" = 1'-0"

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For details of Concrete Bridge Railing Transition, Type TFC, see Standard Drawings E 706-TTFC-01 through -03.

For additional details of Concrete Bridge Railing, Type FC, see Standard Drawing E 706-BRSF-02.

For Bar Bending Details, Bill of Materials, and Sections A-A, B-B, and C-C, see Sheet 49.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BAD
CHECKED: TRL | CHECKED: BKH

INDIANA
DEPARTMENT OF TRANSPORTATION

RAILING DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	47 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 37 - Railing Details.dwg



EAST BRIDGE RAILING ELEVATION

Scale: 1/2" = 1'-0"

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For details of Concrete Bridge Railing Transition, Type TFC, see Standard Drawings E 706-TTFC-01 through -03.

For additional details of Concrete Bridge Railing, Type FC, see Standard Drawing E 706-BRSF-02.

For Bar Bending Details, Bill of Materials, and Sections A-A, B-B, and C-C, see Sheet 49.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BAD | CHECKED: TRL | CHECKED: BKH

INDIANA DEPARTMENT OF TRANSPORTATION


RAILING DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	48 of 62
	CONTRACT
	B-44533


Jul 31,2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Mimich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 37 - Railing Details.dwg




EAST BRIDGE RAILING ELEVATION
Scale: 1/2" = 1'-0"




SECTION A-A
Scale: 1" = 1'-0"



SECTION B-B
Scale: 1" = 1'-0"



SECTION C-C
Scale: 1" = 1'-0"



BAR BENDING DETAILS
Not To Scale

BILL OF MATERIALS
EAST BRIDGE RAILING

EPOXY COATED REINFORCING BARS			
MARK OR SIZE	NO. REQ'D	LENGTH	WEIGHT
5701E	623	5'-6"	
5704E	1246	3'-0"	
5705E	6	2'-8"	
5802E	10	5'-3"	
5808E	10	4'-7"	
5816E	10	2'-10"	
#5E	104	34'-9"	
#5E	22	6'-6"	
#5E	6	2'-6"	
Total #5 Epoxy Coated Bars			11,556#
TFC Transitions - 2 @ 551#			1,102#
Total Epoxy Coated Reinforcing Bars			12,658#

CONCRETE	
Railing, Concrete, FC	39.6 CYS
Railing, Concrete, FC Modified	1.0 CYS
Bridge Railing Transition, TFC	2 EA
MISCELLANEOUS	
Surface Seal, FC*	2711 SFT
Surface Seal, TFC*	200 SFT
Barrier Delineator	13 EA

* Estimated Quantity. To be paid for as "LS".

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For details of Concrete Bridge Railing Transition, Type TFC, see Standard Drawings E 706-TTFC-01 through -03.

For additional details of Concrete Bridge Railing, Type FC, see Standard Drawing E 706-BRSF-02.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH
DRAWN: BAD
CHECKED: TRL
CHECKED: BKH


INDIANA DEPARTMENT OF TRANSPORTATION


RAILING DETAILS


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	49 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 37 - Railing Details.dwg









WEST BRIDGE RAILING ELEVATION
Scale: 1/2" = 1'-0"

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For details of Concrete Bridge Railing Transition, Type TFC, see Standard Drawings E 706-TTFC-01 through -03.

For additional details of Concrete Bridge Railing, Type FC, see Standard Drawing E 706-BRSF-02.

For Bar Bending Details, Bill of Materials, and Sections A-A, B-B, and C-C, see Sheet 52.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BAD
CHECKED: TRL | CHECKED: BKH


INDIANA
DEPARTMENT OF TRANSPORTATION


RAILING DETAILS


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	50 of 62
	CONTRACT
	B-44533

Jul 31,2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 37 - Railing Details.dwg









WEST BRIDGE RAILING ELEVATION
Scale: 1/2" = 1'-0"

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For details of Concrete Bridge Railing Transition, Type TFC, see Standard Drawings E 706-TTFC-01 through -03.

For additional details of Concrete Bridge Railing, Type FC, see Standard Drawing E 706-BRSF-02.

For Bar Bending Details, Bill of Materials, and Sections A-A, B-B, and C-C, see Sheet 52.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BAD
CHECKED: TRL | CHECKED: BKH

INDIANA DEPARTMENT OF TRANSPORTATION


RAILING DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	51 of 62
	CONTRACT
	B-44533


Jul 31,2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 37 - Railing Details.dwg




WEST BRIDGE RAILING ELEVATION
Scale: 1/2" = 1'-0"




SECTION A-A
Scale: 1" = 1'-0"



SECTION B-B
Scale: 1" = 1'-0"



SECTION C-C
Scale: 1" = 1'-0"



BAR BENDING DETAILS
Not To Scale

BILL OF MATERIALS
WEST BRIDGE RAILING

EPOXY COATED REINFORCING BARS			
MARK OR SIZE	NO. REQ'D	LENGTH	WEIGHT
5701E	623	5'-6"	
5704E	1246	3'-0"	
5705E	6	2'-8"	
5802E	10	5'-3"	
5808E	10	4'-7"	
5816E	10	2'-10"	
#5E	104	34'-9"	
#5E	22	6'-6"	
#5E	6	2'-6"	
Total #5 Epoxy Coated Bars			11,556#
TFC Transitions - 2 @ 551#			1,102#
Total Epoxy Coated Reinforcing Bars			12,658#

CONCRETE	
Railing, Concrete, FC	39.6 CYS
Railing, Concrete, FC Modified	1.0 CYS
Bridge Railing Transition, TFC	2 EA
MISCELLANEOUS	
Surface Seal, FC*	2711 SFT
Surface Seal, TFC*	200 SFT
Barrier Delineator	13 EA

* Estimated Quantity. To be paid for as "LS".

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For details of Concrete Bridge Railing Transition, Type TFC, see Standard Drawings E 706-TTFC-01 through -03.

For additional details of Concrete Bridge Railing, Type FC, see Standard Drawing E 706-BRSF-02.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH
DRAWN: BAD
CHECKED: TRL
CHECKED: BKH

INDIANA DEPARTMENT OF TRANSPORTATION


RAILING DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	52 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 37 - Railing Details.dwg



SCREED PLAN
Scale: 3/64" = 1'-0"



TYPICAL SECTION
Scale: 1/4" = 1'-0"

PROCEDURE AND NOTES

1. The existing top of girder elevations are unknown. After the new girders are installed, take elevations at all screed points on top of girders. Enter these elevations in the table. Subtract these elevations from the tabulated elevations and use the resulting dimensions as the height for setting screed forms above these points. Due to the unknown nature of the existing girder elevations, adjustments to the elevations may be necessary. Provide this data to the Engineer for review and approval.
2. Do not set screed forms by leveling.
3. No concrete in the floor slab shall be poured without approval from the Engineer.
4. Screed Elevations as shown in the table include an allowance for concrete dead load deflections.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: RPG

CHECKED: AJI | CHECKED: AJI

INDIANA DEPARTMENT OF TRANSPORTATION

SCREEDS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	53 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 39 - Screeds.dwg

TABLE OF SCREED ELEVATIONS

SCREED LINE

	POINT:	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35
A	Top of Coping Forms	818.750	818.880	819.040	819.190	819.330	819.470	819.610	819.720	819.835	819.975	820.245	820.245	820.365	820.465	820.555	820.625	820.685	820.725	820.760	820.790	820.815	820.845	820.865	820.895	820.925	820.960	820.995	821.020	821.040	821.045	821.035	821.010	820.965	820.910	820.845
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
B	Top of Coping Forms	818.835	818.965	819.125	819.275	819.410	819.550	819.685	819.795	819.905	820.045	820.185	820.310	820.425	820.530	820.610	820.680	820.735	820.780	820.810	820.840	820.865	820.890	820.910	820.935	820.965	821.000	821.030	821.055	821.070	821.075	821.060	821.035	820.990	820.930	820.860
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
C	Top of Coping Forms	819.195	819.320	819.470	819.610	819.740	819.865	819.995	820.100	820.200	820.335	820.460	820.580	820.685	820.780	820.855	820.915	820.960	820.995	821.020	821.035	821.050	821.070	821.080	821.100	821.125	821.145	821.170	821.185	821.190	821.185	821.165	821.130	821.075	821.005	820.930
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
D	Top of Coping Forms	819.545	819.665	819.805	819.935	820.055	820.175	820.295	820.390	820.485	820.610	820.730	820.840	820.935	821.020	821.085	821.135	821.175	821.195	821.210	821.220	821.230	821.240	821.245	821.255	821.270	821.280	821.295	821.305	821.300	821.285	821.255	821.210	821.150	821.070	820.985
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
E	Top of Coping Forms	819.885	819.995	820.125	820.250	820.360	820.470	820.580	820.670	820.755	820.870	820.985	821.085	821.170	821.245	821.305	821.345	821.375	821.390	821.395	821.395	821.395	821.395	821.390	821.395	821.400	821.405	821.410	821.410	821.400	821.375	821.335	821.280	821.210	821.125	821.025
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
F	Top of Coping Forms	819.970	820.080	820.210	820.330	820.435	820.545	820.655	820.740	820.825	820.940	821.050	821.145	821.230	821.305	821.360	821.400	821.425	821.435	821.440	821.440	821.435	821.430	821.430	821.430	821.435	821.435	821.440	821.435	821.425	821.395	821.355	821.300	821.225	821.135	821.035
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
G	Top of Coping Forms	819.985	820.090	820.220	820.335	820.440	820.545	820.650	820.735	820.820	820.930	821.040	821.135	821.215	821.290	821.340	821.375	821.400	821.410	821.410	821.405	821.400	821.395	821.390	821.395	821.390	821.395	821.395	821.385	821.370	821.340	821.295	821.240	821.165	821.075	820.970
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
H	Top of Coping Forms	820.020	820.120	820.240	820.345	820.445	820.540	820.640	820.715	820.795	820.895	820.995	821.080	821.155	821.215	821.260	821.285	821.300	821.305	821.295	821.280	821.265	821.255	821.240	821.235	821.225	821.220	821.210	821.195	821.170	821.130	821.075	821.010	820.925	820.825	820.715
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
I	Top of Coping Forms	820.050	820.140	820.250	820.350	820.435	820.525	820.615	820.685	820.755	820.845	820.935	821.015	821.080	821.130	821.165	821.185	821.190	821.185	821.165	821.145	821.120	821.095	821.080	821.065	821.045	821.030	821.010	820.990	820.955	820.905	820.845	820.770	820.675	820.565	820.445
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
J	Top of Coping Forms	820.060	820.145	820.250	820.340	820.415	820.495	820.575	820.640	820.705	820.785	820.865	820.935	820.990	821.035	821.060	821.070	821.070	821.050	821.025	820.995	820.960	820.930	820.905	820.885	820.855	820.830	820.805	820.770	820.730	820.670	820.600	820.515	820.410	820.295	820.165
	Top of Girder																																			
	Top of Girder to Top of Coping																																			
K	Top of Coping Forms	820.065	820.145	820.245	820.335	820.410	820.485	820.565	820.625	820.690	820.770	820.850	820.915	820.970	821.010	821.035	821.040	821.035	821.020	820.990	820.955	820.920	820.885	820.860	820.840	820.810	820.780	820.755	820.715	820.675	820.615	820.540	820.455	820.350	820.230	820.100
	Top of Girder																																			
	Top of Girder to Top of Coping																																			

PROCEDURE AND NOTES

1. The existing top of girder elevations are unknown. After the new girders are installed, take elevations at all screed points on top of girders. Enter these elevations in the table. Subtract these elevations from the tabulated elevations and use the resulting dimensions as the height for setting screed forms above these points. Due to the unknown nature of the existing girder elevations, adjustments to the elevations may be necessary. Provide this data to the Engineer for review and approval.
2. Do not set screed forms by leveling.
3. No concrete in the floor slab shall be poured without approval from the Engineer.
4. Screed Elevations as shown in the table include an allowance for concrete dead load deflections.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH — REGISTERED — No. 300129 — STATE OF INDIANA — PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: RPG | CHECKED: AJI | CHECKED: AJI

INDIANA DEPARTMENT OF TRANSPORTATION


SCREEDS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	54 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 39 - Screeds.dwg

TABLE OF SCREED ELEVATIONS

		POINT:	36	37	38	39	40	41	42	43	44
SCREED LINE	A	Top of Coping Forms	820.765	820.680	820.615	820.575	820.505	820.425	820.330	820.230	820.150
		Top of Girder									
		Top of Girder to Top of Coping									
	B	Top of Coping Forms	820.780	820.695	820.625	820.585	820.515	820.430	820.335	820.230	820.150
		Top of Girder									
		Top of Girder to Top of Coping									
	C	Top of Coping Forms	820.835	820.745	820.670	820.620	820.540	820.450	820.345	820.230	820.140
		Top of Girder									
		Top of Girder to Top of Coping									
	D	Top of Coping Forms	820.885	820.780	820.700	820.645	820.555	820.455	820.340	820.220	820.120
		Top of Girder									
		Top of Girder to Top of Coping									
	E	Top of Coping Forms	820.920	820.805	820.720	820.655	820.560	820.450	820.325	820.195	820.090
		Top of Girder									
		Top of Girder to Top of Coping									
	F	Top of Coping Forms	820.925	820.810	820.720	820.655	820.560	820.445	820.320	820.185	820.080
		Top of Girder									
		Top of Girder to Top of Coping									
	G	Top of Coping Forms	820.855	820.740	820.650	820.580	820.485	820.365	820.240	820.105	819.995
		Top of Girder									
		Top of Girder to Top of Coping									
	H	Top of Coping Forms	820.590	820.465	820.370	820.295	820.185	820.060	819.925	819.780	819.665
		Top of Girder									
		Top of Girder to Top of Coping									
	I	Top of Coping Forms	820.315	820.180	820.075	819.995	819.875	819.745	819.600	819.445	819.325
		Top of Girder									
		Top of Girder to Top of Coping									
	J	Top of Coping Forms	820.025	819.880	819.770	819.685	819.555	819.415	819.260	819.095	818.970
		Top of Girder									
		Top of Girder to Top of Coping									
	K	Top of Coping Forms	819.955	819.810	819.695	819.605	819.480	819.335	819.175	819.015	818.885
		Top of Girder									
		Top of Girder to Top of Coping									



CONCRETE DEAD LOAD DEFLECTION DIAGRAM

Not to Scale

PROCEDURE AND NOTES

1. The existing top of girder elevations are unknown. After the new girders are installed, take elevations at all screed points on top of girders. Enter these elevations in the table. Subtract these elevations from the tabulated elevations and use the resulting dimensions as the height for setting screed forms above these points. Due to the unknown nature of the existing girder elevations, adjustments to the elevations may be necessary. Provide this data to the Engineer for review and approval.
2. Do not set screed forms by leveling.
3. No concrete in the floor slab shall be poured without approval from the Engineer.
4. Screed Elevations as shown in the table include an allowance for concrete dead load deflections.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KARL J. HEDENSKOG REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH DRAWN: RPG


CHECKED: AJI CHECKED: AJI

INDIANA DEPARTMENT OF TRANSPORTATION

SCREEDS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	55 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 39 - Screeds.dwg



NORTH RCBA PLAN - BOTTOM BARS

Scale: 3/16" = 1'-0"

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For RCBA Details, See Standard Drawing E 609-RCBA-03 and 04.

For RCBA Extension, See Standard Drawing E 609-TBAE-02.

For Type 1A Joint Details, See Standard Drawing E 609-BRJT-01.

For Bill of Materials, see Sheet 57.

For Pavement Ledge Detail and Sections W-W, X-X, Y-Y, and Z-Z, see Sheet 60.

For Bar Cutting Diagrams and Bar Bending Details, see Sheet 61.


ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT L. HEIDENREICH — REGISTERED — No. 300129 — STATE OF INDIANA — PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER	7/31/2026 DATE	INDIANA DEPARTMENT OF TRANSPORTATION
DESIGNED: BKH	DRAWN: BAD	RCBA DETAILS
CHECKED: TRL	CHECKED: BKH	

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	56 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 40 - RCBA Details.dwg



NORTH RCBA PLAN - TOP BARS
Scale: 3/16" = 1'-0"

BILL OF MATERIALS
NORTH RCBA

EPOXY COATED REINFORCING BARS

MARK OR SIZE	NO. REQ'D	LENGTH	WEIGHT
5901E	81	4'-4"	
591E	120	20'-9"	
5921E	2	3'-10"	
#5E	2	38'-11"	
#5E	21	37'-11"	
#5E	23	36'-11"	
#5E	16	36'-4"	
#5E	15	35'-6"	
#5E	1	34'-4"	
#5E	1	33'-10"	
#5E	1	33'-3"	
#5E	15	28'-11"	
#5E	11	28'-4"	
#5E	2	28'-0"	
#5E	1	25'-4"	
#5E	29	23'-4"	
#5E	21	22'-11"	
#5E	7	22'-0"	
#5E	86	21'-6"	
#5E	93	20'-2"	
#5E	5	19'-3"	
#5E	5	18'-1"	
#5E	15	17'-7"	
#5E	5	16'-8"	
#5E	42	15'-6"	
#5E	18	5'-0"	
#5E	7	3'-0"	
#5E	41	1'-6"	
Total #5 Epoxy Coated Reinf. Bars			13,567#
Total Epoxy Coated Reinf. Bars			13,567#

MISCELLANEOUS	
Reinforced Concrete Bridge Approach, 12 in.	245 SYS
Subbase for PCCP	62 CYS
Threaded Tie-Bar Assembly, Epoxy Coated	78 EA
Geotextile for Pavement, Type 2B	245 SYS
Longitudinal Grooving	245 SYS

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For RCBA Details, See Standard Drawing E 609-RCBA-03 and 04.

For RCBA Extension, See Standard Drawing E 609-TBAE-02.

For Type 1A Joint Details, See Standard Drawing E 609-BRJT-01.

For North RCBA Plan, see Sheet 59.

For Pavement Ledge and Sections W-W, X-X, Y-Y, and Z-Z, see Sheet 60.

For Bar Cutting Diagrams and Bar Bending Details, see Sheet 61.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH DRAWN: BAD
CHECKED: TRL CHECKED: BKH

INDIANA DEPARTMENT OF TRANSPORTATION

RCBA DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	57 of 62
	CONTRACT
	B-44533

Jul 21, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 40 - RCBA Details.dwg



SOUTH RCBA PLAN - BOTTOM BARS

Scale: 3/16" = 1'-0"

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For RCBA Details, See Standard Drawing E 609-RCBA-03 and 04.

For RCBA Extension, See Standard Drawing E 609-TBAE-02.

For Type 1A Joint Details, See Standard Drawing E 609-BRJT-01.

For Bill of Materials, see Sheet 59.

For Pavement Ledge and Sections W-W, X-X, Y-Y, and Z-Z, see Sheet 60.

For Bar Cutting Diagrams and Bar Bending Details, see Sheet 61.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE


DESIGNED: BKH | DRAWN: BAD | CHECKED: TRL | CHECKED: BKH

INDIANA DEPARTMENT OF TRANSPORTATION

RCBA DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	58 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Mensch Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 40 - RCBA Details.dwg



SOUTH RCBA PLAN - TOP BARS

Scale: 3/16" = 1'-0"

BILL OF MATERIALS
SOUTH RCBA

EPOXY COATED REINFORCING BARS

MARK OR SIZE	NO. REQ'D	LENGTH	WEIGHT
5901E	81	4'-4"	
591E	120	20'-9"	
5921E	2	3'-10"	
#5E	2	38'-11"	
#5E	21	37'-11"	
#5E	23	36'-11"	
#5E	16	36'-4"	
#5E	15	35'-6"	
#5E	1	34'-4"	
#5E	1	33'-10"	
#5E	1	33'-3"	
#5E	15	28'-11"	
#5E	11	28'-4"	
#5E	2	28'-0"	
#5E	1	25'-4"	
#5E	29	23'-4"	
#5E	21	22'-11"	
#5E	7	22'-0"	
#5E	86	21'-6"	
#5E	93	20'-2"	
#5E	5	19'-3"	
#5E	5	18'-1"	
#5E	15	17'-7"	
#5E	5	16'-8"	
#5E	42	15'-6"	
#5E	18	5'-0"	
#5E	7	3'-0"	
#5E	41	1'-6"	
Total #5 Epoxy Coated Reinf. Bars			13,567#
Total Epoxy Coated Reinf. Bars			13,567#

MISCELLANEOUS	
Reinforced Concrete Bridge Approach, 12 in.	245 SYS
Subbase for PCCP	62 CYS
Threaded Tie-Bar Assembly, Epoxy Coated	78 EA
Geotextile for Pavement, Type 2B	245 SYS
Longitudinal Grooving	245 SYS

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For RCBA Details, See Standard Drawing E 609-RCBA-03 and 04.

For RCBA Extension, See Standard Drawing E 609-TBAE-02.

For Type 1A Joint Details, See Standard Drawing E 609-BRJT-01.

For South RCBA Plan, see Sheet 58.

For Pavement Ledge and Sections W-W, X-X, Y-Y, and Z-Z, see Sheet 60.

For Bar Cutting Diagrams and Bar Bending Details, see Sheet 61.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH DRAWN: BAD


CHECKED: TRL CHECKED: BKH

INDIANA DEPARTMENT OF TRANSPORTATION


RCBA DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	59 of 62
	CONTRACT
	B-44533


Jul 21, 2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 40 - RCBA Details.dwg




SECTION W-W
Scale: 1/2" = 1'-0"




SECTION Z-Z
Scale: 1/2" = 1'-0"



SECTION X-X
Scale: 1/2" = 1'-0"



SECTION Y-Y
Scale: 1/2" = 1'-0"



PAVEMENT LEDGE DETAIL
Scale: 3/4" = 1'-0"

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For RCBA Details, See Standard Drawing E 609-RCBA-03 and 04.

For RCBA Extension, See Standard Drawing E 609-TBAE-02.

For Type 1A Joint Details, See Standard Drawing E 609-BRJT-01.

For Full Depth HMA Details, See Sheet 3.

For RCBA Plan and Bill of Materials, see Sheets 56-59.

For Bar Cutting Diagrams and Bar Bending Details, see Sheet 61.


Jul 31,2026 - 10:29am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 40 - RCBA Details.dwg

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845


KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL	DESIGN ENGINEER	7/31/2026 DATE	INDIANA DEPARTMENT OF TRANSPORTATION
DESIGNED: BKH	DRAWN: BAD		RCBA DETAILS
CHECKED: TRL	CHECKED: BKH		


SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	60 of 62
	CONTRACT
	B-44533




BAR CUTTING DIAGRAM #1
21 - #5E X 36'-11"




BAR CUTTING DIAGRAM #2
15 - #5E X 28'-11"




BAR CUTTING DIAGRAM #3
21 - #5E X 37'-11"




BAR CUTTING DIAGRAM #4
7 - #5E X 22'-0"




BAR CUTTING DIAGRAM #5
5 - #5E X 16'-8"




BAR CUTTING DIAGRAM #6
7 - #5E X 23'-4"




BAR CUTTING DIAGRAM #7
15 - #5E X 35'-6"




BAR CUTTING DIAGRAM #8
11 - #5E X 28'-4"




BAR CUTTING DIAGRAM #9
16 - #5E X 36'-4"




BAR CUTTING DIAGRAM #10
21 - #5E X 22'-11"



BAR CUTTING DIAGRAM #11
15 - #5E X 17'-7"



BAR CUTTING DIAGRAM #12
22 - #5E X 23'-4"




510E
#5E x 4'-6"


THREADED TIE BAR ASSEMBLY, EPOXY COATED
Not to Scale



591E
#5E x 20'-9"



5901E
#5E x 4'-4"



5921E
#5E x 3'-10"

BAR BENDING DETAILS
Not to Scale

NOTES

All reinforcing bars shall be epoxy-coated.

For Reinforcing Bar Notes, see Standard Drawing E 703-BRST-01.

For RCBA Details, See Standard Drawing E 609-RCBA-03 and 04.

For RCBA Extension, See Standard Drawing E 609-TBAE-02.

For Type 1A Joint Details, See Standard Drawing E 609-BRJT-01.

For RCBA Plan and Bill of Materials, see Sheets 56-59.

For Pavement Ledge and Sections W-W, X-X, Y-Y, and Z-Z, see Sheet 60.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH
REGISTERED
No. 300129
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL
DESIGN ENGINEER — DATE 7/31/2026

DESIGNED: BKH
DRAWN: BAD
CHECKED: TRL
CHECKED: BKH

INDIANA
DEPARTMENT OF TRANSPORTATION

RCBA DETAILS

SCALE	BRIDGE FILE
AS NOTED	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	61 of 62
	CONTRACT
	B-44533

Jul 31, 2026 - 10:20am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 40 - RCBA Details.dwg

SUMMARY OF BRIDGE QUANTITIES

LOCATION	CONCRETE		PRESENT STRUCTURE, REMOVE PORTIONS	AGGREGATE FOR END BENT BACKFILL	FLOWABLE BACKFILL, NON-REMOVABLE	GEOTEXTILE FOR PAVEMENT, TYPE 2B	SUBBASE FOR PCCP	BARRIER DELIN-EATORS	PAVED SIDE DITCH, TYPE A, MODIFIED	REINF. CONC. BRIDGE APPROACH 12 IN.	INSPECTION HOLE	MOB. & DEMOB. FOR SEEDING	MULCHED SEEDING, R	GRATES, BASINS, & FITTINGS, CAST IRON	FIELD DRILLED HOLE IN CONCRETE	REINF. BARS, EPOXY COATED	THREADED TIE BAR ASSEMBLY, EPOXY COATED	RAILING, CONCRETE, TYPE FC	RAILING, CONCRETE, TYPE FC, MODIFIED	CONCRETE BRIDGE RAILING TRANSITION TFC	SURFACE SEAL*	CONCRETE SURFACE COATING, ARMOR X*	PATCHING CONCRETE STRUCT.	STRUCT. STEEL, FIELD CUT
	CLASS C	CLASS A																						
	SUPERSTR	SUBSTR																						
	CYS	CYS	LSUM	CYS	CYS	SYS	CYS	EACH	LFT	SYS	EA	EA	SYS	EACH	EA	LBS	EA	CYS	CYS	EACH	SFT	SFT	SFT	SQIN
NB STRUCTURE																								
SUPERSTRUCTURE	363.3		1					13				1	585	2		157,898		39.6	1.0	2	2,911		100	584
SUBSTRUCTURE		34.6		50	15				107		4				237	4,047	34					330		
RCBA						346	62			245						13,567	78							
SB STRUCTURE																								
SUPERSTRUCTURE	363.3		1					13				1	500	2		157,898		39.6	1.0	2	2,911		100	584
SUBSTRUCTURE		33.6		50	15				107		4				237	4,047	34					330		
RCBA						346	62			245						13,567	78							
TOTALS	726.6	68.2		100	30	692	124	26	214	490	8	2	1,085	4	474	351,024	224	79.2	2.0	4	5,822	660	200	1,168

* - Estimated Quantity to be Paid for as 'LSUM'

SUMMARY OF BRIDGE QUANTITIES

LOCATION	STRUCT. STEEL	DRILLED HOLE	STUD SHEAR CONN.	LONG. GROOVING	EXP. JOINT TYPE PCF, REPLACE	BEARING ASSEMBLY ELAST.
	LBS	EA	EA	SYS	LFT	EACH
NB STRUCTURE						
SUPERSTRUCTURE	103,715	544	621	1,453		
SUBSTRUCTURE					111	8
RCBA				245		
SB STRUCTURE						
SUPERSTRUCTURE	103,715	544	621	1,453		
SUBSTRUCTURE					111	8
RCBA				245		
TOTALS	207,430	1,088	1,242	3,396	222	16

GUARDRAIL SUMMARY TABLE

LOCATION				MGS W-BEAM GUARDRAIL LENGTH							
FROM STATION	TO STATION	LEFT	RIGHT	STANDARD POST AT 6 FT 3 IN. SPA.	STANDARD POST AT 3 FT 1.5 IN. SPA.	DOUBLE FACED AT 6 FT 3 IN. SPA.	DOUBLE FACED AT 3 FT. 1.5 IN. SPA.	GUARDRAIL, MGS TRANSITION WITHOUT CURB	GUARDRAIL END TREATMENT TYPE OS	GUARDRAIL REMOVE	REMARKS
				LFT	LFT	LFT	LFT	EACH	EACH	LFT	
10+46	13+38		X	200				1	1	300	
11+13	12+70	X		43.75				1	1	140	
17+94	19+11		X	25				1	1	115	
17+05	20+16	X		218.75				1	1	300	
TOTALS				488				4	4	855	

PAVEMENT QUANTITIES

LOCATION	HMA FOR PATCHING, FULL DEPTH				PAVEMENT REMOVAL	EXCAVATION, COMMON	SUBGRADE TREATMENT, TYPE IC	GEOGRID, TYPE IB	MILLING, TRANSITION	HMA MATERIAL FOR:		JOINT ADHESIVE	COMPACTED AGGREGATE NO. 53		REMARKS
	HMA SURFACE, TYPE B	HMA INTERMEDIATE, TYPE B	HMA BASE, TYPE B	QC/QA-HMA, 2, 58S, SURFACE, 9.5 MM						CRACKS IN ASPHALT PAVEMENT, FILL	TACK COAT		DEPTH		
	LBS. PER SYD.												10"		
	165	275	660	165											
	TON	TON	TON	TON	SYS	CYS	SYS	SYS	SYS	TON	TON	LFT	TON	TON	
NB LANES	2	3	5	21	260	170	15	15	244		1	106	95		
SB LANES	2	3	5	21	260	165	15	15	244		1	106	90		
TOTALS	4	6	10	42	520	335	30	30	488		2	212	185		

BRIDGE COATING LOCATIONS AND INFORMATION

CONTRACT BRIDGE NO. (1)	DES. NO.	BRIDGE FILE NUMBER	ROUTE AND CROSSING	ROUTE	REF. POST	COUNTY	LOCATION	YEAR BUILT	YEAR LAST PAINTED	EXISTING PRIMER TYPE (HAZARDOUS OR NON-HAZARDOUS)	NO. SPANS	SPAN LENGTHS	SURF. AREA STRUCTURAL STEEL (SFT) (2)	NEW COATING COLOR NAME (NUMBER) (3)
1	2200710	I469-18-07027 ANB	MINNICH ROAD OVER I-469	MINNICH ROAD	17+71	ALLEN	1.73 MILES WEST OF U.S. 30	1989	2007	HAZARDOUS	4	65'-5", 145'-0", 145'-0" & 55'-5"	22,332	LIGHT BLUE
2	2200711	I469-18-07027 ASB	MINNICH ROAD OVER I-469	MINNICH ROAD	17+71	ALLEN	1.73 MILES WEST OF U.S. 30	1989	2007	HAZARDOUS	4	65'-5", 145'-0", 145'-0" & 55'-5"	22,332	LIGHT BLUE

(1) See RSP 101-B-042, Bridge Numbers for Pay Item
(2) Quantities shown are approximate. The Contractor shall determine the quantities upon which to base its bid.
(3) See Standard Specifications section 909.02 for allowable color numbers for full or partial bridge coating. Color numbers should only be included in the table for color names not listed in 909.02.

ENGINEERING RESOURCES, INC.
Ph: (260) 490-1025
www.eri.consulting
4175 New Vision Drive
Fort Wayne, Indiana 46845

KURT J. HEIDENREICH REGISTERED No. 300129 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 7/31/2026 DATE

DESIGNED: BKH | DRAWN: BKH

CHECKED: TRL | CHECKED: TRL

INDIANA DEPARTMENT OF TRANSPORTATION

SUMMARY TABLES

SCALE	BRIDGE FILE
N/A	I469-18-07027 ANB & ASB
	DESIGNATION
	2200710 & 2200711
	SHEETS
	62 of 62
	CONTRACT
	B-44533

Sep 28,2026 - 10:58am
S:\Projects\Projects (6000-6999)\Projects (6100-6149)\6149-INDOT-Minnich Rd NB & SB over I-469\Drawings\Plan Sheets\6149 - 42 - Summary Tables.dwg