DESIGNATION	BRIDGE FILE
2200946	001-90-00230 C
CONTRACT	
B-44532	

INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE PREVENTIVE MAINTENANCE PLANS

FOR SPANS OVER 20 FEET

ROUTE: SR 1 AT: RP 125+07


DESIGNATION NO. 2200946


NO ADDITIONAL RIGHT-OF-WAY
REQUIRED FOR THIS PROJECT

STRUCTURE INFORMATION				
STRUCTURE	TYPE	SPAN AND SKEW	OVER	STATION
001-90-00230 C	Reinforced Concrete Arch	4 Clear Spans @ 72'-0" Each Skew: 15° Lt.	Wabash River	66+10.00 Line "A"

KIN PROJECT INFORMATION	
DESIGNATION	PROJECT DESCRIPTION
2200946 (LEAD)	BRIDGE DECK OVERLAY ON SR 1 OVER WABASH RIVER
2200957	BRIDGE DECK OVERLAY ON US 224 OVER EIGHT MILE CREEK
2200542	BRIDGE THIN DECK OVERLAY ON SR 1 OVER SIX MILE CREEK

Bridge Deck Overlay on SR 1 over Wabash River
Located 0.05 Miles South of SR 124
Sections 4 & 33, T-26-N & T-27-N, R-12-E, Lancaster & Harrison Townships, Wells County, Indiana





PROJECT LOCATION SHOWN BY
Wells County

TRAFFIC DATA		
A.A.D.T.	(2027)	22,035 V.P.D.
A.A.D.T.	(2047)	23,282 V.P.D.
D.H.V.	(2047)	2,596 V.P.H.
DIRECTIONAL DISTRIBUTION		54 %
TRUCKS		5 % A.A.D.T.
		3 % D.H.V.

DESIGN DATA	
DESIGN SPEED	30 M.P.H.
PROJECT DESIGN CRITERIA	3R (NON-FREEWAY)
FUNCTIONAL CLASSIFICATION	PRINCIPAL ARTERIAL
RURAL/URBAN	URBAN (BUILT-UP)
TERRAIN	LEVEL
ACCESS CONTROL	NONE

LATITUDE: 40° 44' 32" N LONGITUDE: 85° 10' 17" W

BRIDGE LENGTH:	0.067	MI.
ROADWAY LENGTH:	0.000	MI.
TOTAL LENGTH:	0.067	MI.
MAX. GRADE:	0.00	%

HUC: 051201010801
051201010802

Plans Prepared By:

fishbeck
Engineers | Architects | Scientists | Constructors

INDIANA DEPARTMENT OF TRANSPORTATION
STANDARD SPECIFICATIONS DATED 2026
TO BE USED WITH THESE PLANS.

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

PLANS PREPARED BY: FISHBECK (317)-577-9050 PHONE NUMBER

CERTIFIED BY: 4/9/2026 DATE

RECOMMENDED FOR LETTING: Stephanie J. Wagner 09/03/2026 DATE
INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE FILE
001-90-00230 C
DESIGNATION
2200946
SHEETS
1 of 18
CONTRACT
B-44532

Plot: 4/9/2026
File: BR_Title Sheet.dgn
Model: Title Sheet

UTILITIES

Cable TV: Mediacom
532 Fairview Blvd.
Kendallville, IN 46755
Attn: Victor Gregory
Phone: (845)-395-6004
Email: victor.gregory@mediacomcc.com

Communications: AdamsWells Telecom (Craigville Telephone Company)
2351 N Main Street
Craigville, IN 46731
Attn: Martin Stout
Phone: (260)-565-3131
Email: martin@adamswells.net

Gas: NIPSCO
1501 Hale Ave.
Fort Wayne, IN 46802
Attn: Vanessa Chimitt
Phone: (260)-222-3103
Email: vrivera@nisource.com

811 Know what's below. Call before you dig.

INDIANA UNDERGROUND
1-800-382-5544 OR CALL 811
24 HOURS A DAY 7 DAYS A WEEK

REVISIONS

SHEET NO.	DATE	REVISED

INDEX

SHEET NO.	SUBJECT
1	TITLE SHEET
2	INDEX
3-10	MAINTENANCE OF TRAFFIC
11-12	APPROACH CONSTRUCTION DETAILS
13-14	GENERAL PLAN
15-16	BRIDGE DETAILS
17	BRIDGE SUMMARY
18	ROAD SUMMARY

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ 4/9/2026
DESIGN ENGINEER DATE


DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026
CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

INDEX


SCALE	BRIDGE FILE
NONE	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	2 of 18
	CONTRACT
	B-44532

Plot: 4/9/2026
File: BR_Index.dgn
Model: Index




EXISTING SECTION

Scale: 1" = 5'



PHASE 1 CONSTRUCTION

Scale: 1" = 5'



PHASE 2 CONSTRUCTION

Scale: 1" = 5'

NOTES:

1. Only Removable Tape Pavement Markings will be allowed for temporary MOT on bridge deck and bridge approach wearing surfaces.

   Permanent markings will only be allowed once the final wearing surface is placed on the deck and approach slabs.

   No grinding, blasting, nor any harsh removal method shall be allowed on the final wearing surface. Any damages sustained by the final wearing surfaces before project accpetance will be removed and replaced at the Contractor's expense.

2. Both sidewalks on the structure will be closed during Phase 1 and 2 construction. Pedestrian traffic will be detoured to the adjacent pedestrain bridge. See pedestrian maintenance of traffic on sheet 10.

Plot: 4/9/2026

File: 2200946_MOT Sections.dgn
Model:Sections

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE


DESIGNED: CPM 4/9/2026 | DRAWN: CPM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
TYPICAL SECTIONS

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	3 of 18
	CONTRACT
	B-44532



NOTES

1. SR 1 shall remain open at all times. The intersection with SR 124 shall remain accessible at all times.
2. Construction zone design speed is 30 mph.
3. Traffic control devices shall be in accordance with INDOT Standard Specifications, Standard Drawings, and the Indiana Manual of Uniform Traffic Control Devices.
4. Taper lengths are based on posted speed limit prior to construction (30 mph).
5. Spacing of channelizing devices shall be 25 ft on all tapers and 50 ft on all tangents.
6. Only Removable Tape Pavement Markings will be allowed for temporary MOT on bridge deck and bridge approach wearing surfaces. Permanent markings will only be allowed once the final wearing surface is placed on the deck and approach slabs. No grinding, blasting, nor any harsh removal method shall be allowed on the final wearing surface. Any damages sustained by the final wearing surface before project acceptance will be removed and replaced at the Contractor's expense.
7. See sheet 10 for pedestrian MOT.
8. See special provisions for waterway MOT.
9. Place a XW20-YWR(A) "Wide Load Restriction 1¼ Mile" in the southeast quadrant of the SR 1 / SR 116 intersection south of the project location.

PLAN

Scale: 1" = 30'-0"

LEGEND

- Lane Direction
- Construction Work Zone
- Construction Drum
- Construction Sign
- Type III Barricade
- Pavement Marking Removal or Covering

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026


CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
SR 1 - PHASE 1

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	4 of 18
	CONTRACT
	B-44532

Plot: 4/9/2026
File: BR_MOT.dgn
Model:Phase 1 - South Approach



PLAN
Scale: 1" = 30'-0"

NOTES

1. SR 1 shall remain open at all times. The intersection with SR 124 shall remain accessible at all times.
2. Construction zone design speed is 30 mph.
3. Traffic control devices shall be in accordance with INDOT Standard Specifications, Standard Drawings, and the Indiana Manual of Uniform Traffic Control Devices.
4. Taper lengths are based on posted speed limit prior to construction (30 mph).
5. Spacing of channelizing devices shall be 25 ft on all tapers and 50 ft on all tangents.
6. Only Removable Tape Pavement Markings will be allowed for temporary MOT on bridge deck and bridge approach wearing surfaces. Permanent markings will only be allowed once the final wearing surface is placed on the deck and approach slabs. No grinding, blasting, nor any harsh removal method shall be allowed on the final wearing surface. Any damages sustained by the final wearing surface before project acceptance will be removed and replaced at the Contractor's expense.
7. See sheet 10 for pedestrian MOT.
8. Access to Kehoe Park via the Kehoe Park access drive shall be maintained at all times, except as coordinated with the City of Bluffton Parks Department. See special provisions.
9. See special provisions for waterway MOT.

LEGEND

- Lane Direction
- Construction Work Zone
- Construction Drum
- Construction Sign
- Barricade
- Pavement Marking Removal or Covering

Plot: 4/9/2026
File: BR_MOT.dgn
Model: Phase 1 - Bridge

ADAM MONCZNIK
REGISTERED
No.11700255
STATE OF
INDIANA
PROFESSIONAL ENGINEER


RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026
CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
SR 1 - PHASE 1

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	5 of 18
	CONTRACT
	B-44532



PLAN

Scale: 1" = 30'-0"

NOTES

1. SR 1 shall remain open at all times. The intersection with SR 124 shall remain accessible at all times.
2. Construction zone design speed is 30 mph.
3. Traffic control devices shall be in accordance with INDOT Standard Specifications, Standard Drawings, and the Indiana Manual of Uniform Traffic Control Devices.
4. Taper lengths are based on posted speed limit prior to construction (30 mph).
5. Spacing of channelizing devices shall be 25 ft on all tapers and 50 ft on all tangents.
6. Only Removable Tape Pavement Markings will be allowed for temporary MOT on bridge deck and bridge approach wearing surfaces. Permanent markings will only be allowed once the final wearing surface is placed on the deck and approach slabs. No grinding, blasting, nor any harsh removal method shall be allowed on the final wearing surface. Any damages sustained by the final wearing surface before project acceptance will be removed and replaced at the Contractor's expense.
7. See sheet 10 for pedestrian MOT.
8. See special provisions for waterway MOT.
9. Place sign in the northwest quadrant of the SR 1 / SR 124 intersection

LEGEND

- Lane Direction
- Construction Work Zone
- Construction Drum
- Construction Sign
- Barricade
- Pavement Marking Removal or Covering

Plot: 4/9/2026

File: BR_MOT.dgn
Model: Phase 1 - North Approach


ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL	DESIGN ENGINEER	4/9/2026 DATE	
DESIGNED: ASU	4/9/2026	DRAWN: ASU	4/9/2026
CHECKED: APM	4/9/2026	CHECKED: APM	4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
SR 1 - PHASE 1

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	6 of 18
	CONTRACT
	B-44532



PLAN

Scale: 1" = 30'-0"

NOTES

1. SR 1 shall remain open at all times. The intersection with SR 124 shall remain accessible at all times.
2. Construction zone design speed is 30 mph.
3. Traffic control devices shall be in accordance with INDOT Standard Specifications, Standard Drawings, and the Indiana Manual of Uniform Traffic Control Devices.
4. Taper lengths are based on posted speed limit prior to construction (30 mph).
5. Spacing of channelizing devices shall be 25 ft on all tapers and 50 ft on all tangents.
6. Only Removable Tape Pavement Markings will be allowed for temporary MOT on bridge deck and bridge approach wearing surfaces. Permanent markings will only be allowed once the final wearing surface is placed on the deck and approach slabs. No grinding, blasting, nor any harsh removal method shall be allowed on the final wearing surface. Any damages sustained by the final wearing surface before project acceptance will be removed and replaced at the Contractor's expense.
7. See sheet 10 for pedestrian MOT.
8. See special provisions for waterway MOT.
9. Place a XW20-YWR(A) "Wide Load Restriction 1¼ Mile" in the southeast quadrant of the SR 1 / SR 116 intersection south of the project location.

LEGEND

- Lane Direction
- Construction Drum
- Barricade
- Construction Work Zone
- Construction Sign
- Pavement Marking Removal or Covering

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026


INDIANA DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
SR 1 - PHASE 2

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	7 of 18
	CONTRACT
	B-44532

Plot: 4/9/2026

File: BR_MOT.dgn
Model: Phase 2 - South Approach



PLAN

Scale: 1" = 30'-0"

NOTES

1. SR 1 shall remain open at all times. The intersection with SR 124 shall remain accessible at all times.
2. Construction zone design speed is 30 mph.
3. Traffic control devices shall be in accordance with INDOT Standard Specifications, Standard Drawings, and the Indiana Manual of Uniform Traffic Control Devices.
4. Taper lengths are based on posted speed limit prior to construction (30 mph).
5. Spacing of channelizing devices shall be 25 ft on all tapers and 50 ft on all tangents.
6. Only Removable Tape Pavement Markings will be allowed for temporary MOT on bridge deck and bridge approach wearing surfaces. Permanent markings will only be allowed once the final wearing surface is placed on the deck and approach slabs. No grinding, blasting, nor any harsh removal method shall be allowed on the final wearing surface. Any damages sustained by the final wearing surface before project acceptance will be removed and replaced at the Contractor's expense.
7. See sheet 10 for pedestrian MOT.
8. Access to Kehoe Park via the Kehoe Park access drive shall be maintained at all times, except as coordinated with the City of Bluffton Parks Department. See special provisons.
9. See special provisions for waterway MOT.

LEGEND

- Lane Direction
- Construction Drum
- Barricade
- Construction Work Zone
- Construction Sign
- Pavement Marking Removal or Covering

Plot: 4/9/2026

File: BR_MOT.dgn
Model: Phase 2 - Bridge

ADAM MONCZNIK
REGISTERED
No. 11700255
STATE OF
INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE


DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
SR 1 - PHASE 2

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	8 of 18
	CONTRACT
	B-44532



PLAN

Scale: 1" = 30'-0"

NOTES

1. SR 1 shall remain open at all times. The intersection with SR 124 shall remain accessible at all times.
2. Construction zone design speed is 30 mph.
3. Traffic control devices shall be in accordance with INDOT Standard Specifications, Standard Drawings, and the Indiana Manual of Uniform Traffic Control Devices.
4. Taper lengths are based on posted speed limit prior to construction (30 mph).
5. Spacing of channelizing devices shall be 25 ft on all tapers and 50 ft on all tangents.
6. Only Removable Tape Pavement Markings will be allowed for temporary MOT on bridge deck and bridge approach wearing surfaces. Permanent markings will only be allowed once the final wearing surface is placed on the deck and approach slabs. No grinding, blasting, nor any harsh removal method shall be allowed on the final wearing surface. Any damages sustained by the final wearing surface before project acceptance will be removed and replaced at the Contractor's expense.
7. See sheet 10 for pedestrian MOT.
8. See special provisions for waterway MOT.
9. Place sign in the northwest quadrant of the SR 1 / SR 124 intersection.

LEGEND

- Lane Direction
- Construction Work Zone
- Construction Drum
- Construction Sign
- Barricade
- Pavement Marking Removal or Covering

Plot: 4/9/2026

File: BR_MOT.dgn
Model: Phase 2 - North Approach

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE


DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
SR 1 - PHASE 2

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	9 of 18
	CONTRACT
	B-44532



PLAN

Scale: 1" = 30'-0"
(Vehicular MOT Not Shown)

MAINTENANCE OF TRAFFIC SUMMARY TABLE

DESCRIPTION	UNIT	PHASE 1	PHASE 2	PAY ITEM TOTAL
Temporary Pavement Message Marking, Removable, Lane Indication Arrow	EACH	4	4	8
Road Closure Sign Assembly	EACH	7	7	7
Temporary Pavement Marking, Removable, 6 in. (Yellow)	LFT	2432	1762	4194
Temporary Pavement Marking, Removable, 6 in. (White)	LFT	1148	540	1688
Temporary Transverse Pavement Marking, Removable, 24 in. (White)	LFT	12	12	24
Temporary Pavement Marking, Removable, 8 in. (Black)	LFT	1541	267	1808
Detour Route Marker Assembly	EACH	5	5	5
Construction Sign, Type A	EACH	38	38	40
Construction Sign, Type B	EACH	3	3	4
Energy Absorbing Terminal, CZ TL-2	EACH	2	2	2
Barricade, Type III-A	LFT	54	58	58
Barricade, Type III-B	LFT	348	200	348
Temporary Traffic Barrier, Type 2	LFT	500	500	500
Temporary Pavement Marking, Removable, 25 in. (Black)	LFT	36	14	50
Temporary Pedestrian Channelizer	LFT	48	48	48
Temporary Worksite Speed Limit Sign Assembly, Continuous	EACH	4	4	4
Signal Head Relocate	EACH	3	9	12
Pavement Message Marking, Remove	SYD	16	2	18
Line, Remove	LFT	335	4	339
Pavement Message Marking, Preformed Plastic, Lane Indication Arrow	EACH	0	8	8

NOTES

1. Traffic control devices shall be in accordance with INDOT Standard Specifications, Standard Drawings, and the Indiana Manual of Uniform Traffic Control Devices.
2. Only Removable Tape Pavement Markings will be allowed for temporary MOT on bridge deck and bridge approach wearing surfaces. Permanent markings will only be allowed once the final wearing surface is placed on the deck and approach slabs. No grinding, blasting, nor any harsh removal method shall be allowed on the final wearing surface. Any damages sustained by the final wearing surface before project acceptance will be removed and replaced at the Contractor's expense.
3. Access to Kehoe Park via the Kehoe Park Access Drive shall be maintained at all times, except as coordinated with the City of Bluffton Parks Department. See special provisions.
4. See special provisions for waterway MOT.

LEGEND

- Construction Work Zone
- Temporary Pedestrian Channelizer
- Construction Sign

Plot: 4/9/2026
File: BR_MOT.dgn
Model: Pedestrian + Quantities

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE


DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
PEDESTRIAN DETOUR - PHASES 1 & 2

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	10 of 18
	CONTRACT
	B-44532



APPROACH ROADWAY PLAN


Scale: 1" = 20'-0"

BENCHMARK INFORMATION

TBM #1
Cut Square At SW Corner of Concrete Utility Vault
Sta. 64+30.57, 32.73' Lt., Line "A"
El. 816.32


TBM #2
Spike in East Face of Utility Pole w/ No Number
Sta. 68+06.43, 74.24' Lt., Line "A"
El. 817.22

TBM #3
Cut "X" on SW Mounting Bolt of Strain Pole at SE Corner of Intersection
Sta. 69+20.96, 46.34' Rt., Line "A"
El. 816.74



DRIVE DETAIL

Scale: ¼" = 1'-0"



HMA WEDGE DETAIL

Not to Scale

LEGEND

- (K) 165 lbs/syd QC/QA-HMA, 3, 58H, Surface, 9.5 mm on 275 lbs/syd QC/QA-HMA, 3, 58H, Intermediate, 19.0 mm on 440 lbs/syd QC/QA-HMA, 3, 58S, Base, 25.0 mm on 770 lbs/syd QC/QA-HMA, 3, 58S, Base, 25.0 mm on 6 inches of Compacted Aggregate, No. 53 on Subgrade Treatment, Type IC on Geotextile for Pavement, Type 2B
- (P2) Asphalt for Tack Coat
- (R) 165 lbs/syd QC/QA-HMA, 3, 58H, Surface, 9.5 mm on Milling, Transition
- (29) Linear Grading
- (39) 10 in. Solid Yellow Thermoplastic Line
- (40) 24 in. Yellow Thermoplastic Transverse Marking
- (41) 6 in. Solid Yellow Multi-Component Line
- (42) 6 in. Broken White Multi-Component Line
- (43) 6 in. Solid White Multi-Component Line
- (62) Curb, Concrete
- (63) Sidewalk, Concrete
- (64) PCCP for Approaches, 9 in, on Dense Graded Subbase, 6 in., on Geogrid Type 1B, on Subgrade Treatment Type II
- (65) Curb and Gutter, Concrete
- (66) Casting, Inlet, Adjust to Grade

NOTES

1. See Standard Drawing E 605-CCCG for Curb and Gutter Details.
2. See Standard Drawing E 605-CCSJ for Curb Details.
3. See Standard Drawings E 604-SDWK for Sidewalk Details.
4. After milling, the existing pavement surface shall be inspected and any visible cracks that are ¼ inch wide or wider shall be sealed prior to application of tack coat. The material used to fill the cracks shall be PG 58S-28 only; no emulsion shall be used.

ALIGNMENT REFERENCE TIES

100
Type of Marker: Mag Nail
Northing: 188473.54
Easting: 809130.40
Sta. 69+32.23, 119.41' Lt. Line "A"

10000
Type of Marker: Mag Nail
Northing: 187930.20
Easting: 809119.77
Sta. 64+01.96, 59.35' Lt. Line "A"

10001
Type of Marker: Mag Nail
Northing: 188362.50
Easting: 809178.39
Sta. 68+35.58, 53.32' Lt. Line "A"

10117
Type of Marker: Mag Nail
Northing: 188499.21
Easting: 809053.94
Sta. 69+41.54, 199.44' Lt. Line "A"

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE


DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026
CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

APPROACH CONSTRUCTION DETAILS


SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	11 of 18
	CONTRACT
	B-44532

Plot: 4/9/2026
File: BR_Approach Details.dgn
Model:BR_Approach Details




TYPICAL SECTION - SOUTH HMA WEDGE

Scale: 1" = 5'-0"




TYPICAL SECTION - SOUTH FULL DEPTH HMA

Scale: 1" = 5'-0"



TYPICAL SECTION - NORTH FULL DEPTH HMA

Scale: 1" = 5'-0"



TYPICAL SECTION - NORTH HMA WEDGE

Scale: 1" = 5'-0"

NOTES

1. See Standard Drawing E 605-CCCG for Curb and Gutter Details.
2. See Standard Drawing E 605-CCSJ for Curb Details.
3. See Standard Drawings E 604-SDWK for Sidewalk Details.
4. After milling, the existing pavement surface shall be inspected and any visible cracks that are ¼ inch wide or wider shall be sealed prior to application of tack coat. The material used to fill the cracks shall be PG 58S-28 only; no emulsion shall be used.

LEGEND

- (K) 165 lbs/syd QC/QA-HMA, 3, 58H, Surface, 9.5 mm on 275 lbs/syd QC/QA-HMA, 3, 58H, Intermediate, 19.0 mm on 440 lbs/syd QC/QA-HMA, 3, 58S, Base, 25.0 mm on 770 lbs/syd QC/QA-HMA, 3, 58S, Base, 25.0 mm on 6 inches of Compacted Aggregate, No. 53 on Subgrade Treatment, Type IC on Geotextile for Pavement, Type 2B
- (P2) Asphalt for Tack Coat
- (R) 165 lbs/syd QC/QA-HMA, 3, 58H, Surface, 9.5 mm on Milling, Transition
- (29) Linear Grading
- (39) 10 in. Solid Yellow Thermoplastic Line
- (40) 24 in. Yellow Thermoplastic Transverse Marking
- (41) 6 in. Solid Yellow Multi-Component Line
- (42) 6 in. Broken White Multi-Component Line
- (43) 6 in. Solid White Multi-Component Line
- (62) Curb, Concrete
- (63) Sidewalk, Concrete
- (64) PCCP for Approaches, 9 in, on Dense Graded Subbase, 6 in., on Geogrid Type 1B, on Subgrade Treatment Type II
- (65) Curb and Gutter, Concrete
- (66) Casting, Inlet, Adjust to Grade

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026


INDIANA DEPARTMENT OF TRANSPORTATION

APPROACH CONSTRUCTION DETAILS

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	12 of 18
	CONTRACT
	B-44532


Plot: 4/9/2026

File: BR_Approach Details.dgn
Model: Typical Appr. Sections



ELEVATION

Scale: 1" = 20'-0"



PLAN

Scale: 1" = 20'-0"

GENERAL NOTES

1. Plans for the existing structure are on file in the Central Office of the Indiana Department of Transportation under bridge file 001-90-00230 B.
2. Stations and profile grade elevations shown are based on existing plans, converted from metric units, and are for reference only.
3. When patching concrete, the minimum depth of the reinforcing steel cover will be 2 inches and shall not extend beyond the neat lines of the original surface. The final surface will meet the original neat line of the surface to be patched. If 2 inches of cover over the reinforcing steel cannot be acheived without extending beyond the original neat lines, less cover will be allowed if approved by the Engineer.
4. The boundaries of all removal areas shall be saw cut. All saw cuts shall be a minimum of 1" deep.
5. All support devices for reinforcing bars shall be epoxy coated steel in accordance with Spec. 910.01(b)11.
6. Where new work is to be fitted to old work, the Contractor shall verify all dimensions and conditions in the field and report any errors or discrepancies to the Engineer and assume responsibility for the correctness and the fit of the new part to the existing.
7. Chamfer exposed concrete edges 1" unless otherwise noted.
8. Reinforcing steel cover shall be 2 1/2" in top, 2" minimum in bottom of floor slab, and 2" in all other parts unless otherwise noted.
9. No additional construction joints (including longitudinal construction joints) shall be added without the approval of the INDOT Fort Wayne Bridge Asset Engineer.
10. Full depth patching shall be performed in accordance with Spec. 722.06 and 722.07. Where deck concrete is removed for more than half of its original depth, the remaining concrete will be removed, and full depth patching performed in accordance with Spec. 722.06 and 722.07.
11. Only Temporary Pavement Marking Tape Type I shall be used for maintaining traffic on bridge deck and approach slab wearing surfaces. Permanent pavement markings will only be allowed once the final wearing surface is placed on the deck and approach slabs. No grinding, blasting, or any harsh removal method shall be used on the final wearing surfaces. Any damage sustained by the final wearing surface due to pavement marking removals shall be repaired in accordance with Spec. 105.11.

DESIGN DATA

LIVE LOAD

2004 reconstruction designed for 83.5 psf in accordance with 2002 AASHTO Specifications. Load Factor = 2.17.

DEAD LOAD

Only actual loads were considered in the design of the original structure, no future wearing surface and metal deck form loads were assumed. Load Factor = 1.30.

DESIGN STRENGTH

CONCRETE

Class C f'c = 4 ksi

REINFORCING STEEL

Grade 60 fy = 60 ksi

MATERIAL NOTES

Bridge Deck Overlay:

1½" (Min.) Latex Modified Portland Cement Concrete
OR
1½" (Min.) Silica Fume Modified Structural Concrete

HYDRAULIC DATA

Drainage Area	530 Sq. Mi.
Design Discharge	16,300 cfs
Q100 Elevation	811.12 ft

HYDRAULIC SCOUR DATA

Q100 Contraction Scour	2.27 ft
Q100 Total Scour	11.01 ft
Flowline Elevation	790.71 ft
Q100 Low Scour Elevation	779.70 ft
Q100 Max Velocity	6.49 ft/s
Q100 Average Velocity	4.54 ft/s

BRIDGE MAINTENANCE KEY

(1) Mill the existing deck a minimum depth of 1" and remove unsound concrete using hydrodemolition. Immediately following completion of hydrodemolition the Engineer shall contact the District Bridge Asset Engineer and Engineer of Record and provide the quantity of removals performed during hydrodemolition (see Special Provisions). Epoxy inject cracks remaining after hydrodemolition at locations determined by the Engineer (Est. Qty. = 15 Lft). Construct full depth patches at locations determined by the Engineer (Est. Qty. = 250 Sq. Ft.). Install a concrete overlay with a depth of 1 1/2".

(2) Perform concrete patching on bridge railing (Est. Qty. = 12 Sq. Ft.), spandrel walls (Est. Qty. = 12 Sq. Ft.), pier joints (Est. Qty. = 105 Sq. Ft.), pier columns (Est. Qty. = 184 Sq. Ft.), curbs (Est. Qty. = 6 Sq. Ft.), and arch rings (Est. Qty. = 1138 Sq. Ft.). Epoxy inject cracks in arch rings and arch ring construction joints (Est. Qty. = 920 Lft). Apply fiber wrap along arch ring patches, see Bridge Details (Est. Qty. = 1600 Sft).

(3) Apply surface seal to sidewalks and patched portions of bridge rails and spandrel walls. Surface seal applied to patched portions of bridge rails and spandrel walls shall have a color closely matching Federal Color Standard 595a, Color No. 27778 (Antique Ivory). See Special Provisions. The existing masonry coating on the bridge rails and spandrel walls not disturbed by repairs shall be left in place.

(4) Remove existing HMA terminal joint lugs, and install retrofit concrete terminal joint lugs with precompressed foam joints, see Bridge Details.

(5) Remove and reconstruct existing drive and sidewalk ramps. Remove portions of existing reinforced bridge approach sidewalk and reconstruct to tie into reconstructed sidewalk ramp. See Approach Construction Details for drive and sidewalk reconstruction details. See Bridge Details for reinforced bridge approach sidewalk reconstruction details.

(6) Replace existing concrete approach pavement with full depth HMA. See Approach Construction Details.

(7) Mill 50 feet of approach pavment and overlay with HMA. See Approach Construction Details.

(8) Remove existing river gage well cover. Install new river gage cover and perform full depth patching (Est. Qty. = 6 Sft) to restore concrete removed during existing river gage well cover removal. See Bridge Details.

(9) Clear debris from channel.

(10) Replace damaged sidewalk panels and curb northwest and southwest of the structure. See Approach Construction Details.

(11) Remove existing joint filler material from longitudinal and transverse deck joints. Install precompressed foam joints in longitudinal and transverse deck joints, see Bridge Details.

(12) Taper overlaid deck surface to meet existing drain castings, see Bridge Details.

(13) Remove deteriorated concrete and perform full depth patching around circular inlet casting. Adjust inlet casting to grade.

REINFORCED CONCRETE ARCH BRIDGE
4 CLEAR SPANS @ 72'-0"
45'-3¼" CLEAR ROADWAY WITH 2 - 4'-3⅜" SIDEWALKS; SKEW 15° LT.
SR 1 OVER WABASH RIVER
WELLS COUNTY

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026


CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

GENERAL PLAN


SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	13 of 18
	CONTRACT
	B-44532

Plot: 4/9/2026
File: BR_General Plan.dgn
Model:BR_General Plan



EXISTING TYPICAL SECTION

Scale: ½" = 1'-0"



PROPOSED TYPICAL SECTION

Scale: ½" = 1'-0"

NOTE

1. Full depth patching shall be performed in accordance with Spec. 722.06 and 722.07. Where deck concrete is removed for more than half of its original depth, the remaining concrete will be removed, and full depth patching performed in accordance with Spec. 722.06 and 722.07.

LEGEND

- Indicates Removal

REINFORCED CONCRETE ARCH BRIDGE
4 CLEAR SPANS @ 72'-0"
45'-3¼" CLEAR ROADWAY WITH 2 - 4'-3⅜" SIDEWALKS; SKEW 15° LT.
SR 1 OVER WABASH RIVER
WELLS COUNTY

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026


INDIANA DEPARTMENT OF TRANSPORTATION

GENERAL PLAN

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	14 of 18
	CONTRACT
	B-44532


Plot: 4/9/2026

File: BR_General Plan.dgn
Model: Typical Section




JOINT LAYOUT PLAN

Scale: 1" = 20'-0"




OVERLAY AT DECK DRAIN DETAILS

Scale: 1" = 1'-0"




SECTION B-B

Scale: 1" = 1'-0"




REMOVAL



PROPOSED


SECTION A-A

Scale: ½" = 1'-0"



OVERLAY DAM DETAIL


Scale: ½" = 1'-0"



590 x 3'-1"

BAR BENDING DIAGRAM

Not to Scale



TYPE PCF BRIDGE EXPANSION JOINT DETAIL

Type PCF Joint at Terminal Joint Shown, Internal Bridge Deck PCF Joints Similar
Not to Scale

NOTES

1. Proposed PCF joint locations shown on deck surface are based on existing plans. Proposed PCF joints shall be placed in the same location as existing deck joints.

2. Reinforcing bars in retrofit terminal joint lug shall be epoxy coated.

3. The Type PCF Bridge Expansion Joint at the terminal joint lug/bridge deck interface shall be able to accommodate both the minimum and maximum joint opening widths as shown below.

W(min.) = 1.3 in.
W(max.) = 3.7 in.

4. The Type PCF Bridge Expansion Joints within the bridge deck shall match the existing joint opening width of 0.5 in. and be able to accommodate both the minimum and maximum joint opening widths as shown below.

W(min.) = 0.2 in.
W(max.) = 0.8 in.

5. Tining or grooving of the concrete shall be terminated 6 in. in advance of the joint opening.

6. For reinforcing bar notes, see Standard Drawing E 703-BRST-01.

7. Type PCF Joint models shall be selected by the manufacturer in accordance with Spec. 724.03(c).

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE


DESIGNED: CPM 4/9/2026 | DRAWN: CPM 4/9/2026 | CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

BRIDGE DETAILS


SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	15 of 18
	CONTRACT
	B-44532

Plot: 4/9/2026
File: BR_Joint.dgn
Model:BR_General Plan




SOUTHEAST SIDEWALK RECONSTRUCTION DETAILS

Scale: ¼" = 1'-0"




SECTION C-C

Scale: ¼" = 1'-0"



SECTION F-F


Scale: ¼" = 1'-0"



BAR CUTTING DIMENSIONS


Not to Scale

SIZE & MARK	L	A	B	C	D	INC.	N	DESCRIPTION
401a	15'-0"	8'-6"	6'-6"	7'-7⅛"	7'-4⅞"	2⅛"	5	6 - #4 x 15'-0" cuts 12 - 401a
501a	15'-0"	8'-6"	6'-6"	7'-8⅜"	7'-3⅝"	4¾"	2	3 - #5 x 15'-0" cuts 6 - 501a




RIVER GAGE WELL REMOVAL DETAIL

Scale: 1" = 1'-0"




PROPOSED RIVER GAGE WELL DETAIL

Scale: 1" = 1'-0"




SECTION A-A

Scale: 1" = 1'-0"




SECTION D-D

Scale: 1" = 1'-0"



ARCH RING REPAIR DETAIL

Not to Scale
Applies to All Arch Rings



SECTION E-E

Not to Scale

BILL OF MATERIALS
SOUTHEAST SIDEWALK

EPOXY-COATED REINFORCING BARS			
SIZE OR MARK	NUMBER OF BARS	LENGTH (FT-IN)	WEIGHT (LBS)
#6	30	12'-0"	
		Total #6	541
501a	3	15'-0"	
#5	1	6'-6"	
		Total #5	54
401a	6	15'-0"	
#4	1	6'-6"	
		Total #4	64
Total Epoxy Coated Reinforcing Bars			659
CONCRETE			
Concrete, C, Superstructure			2.7 Cys

NOTES

1. All reinforcing bars shall be epoxy coated.
2. For reinforcing bar notes, see Standard Drawing E 703-BRST-01.
3. Remove all debris generated during construction from the river gage well chamber.

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: DLC 4/9/2026 | DRAWN: DLC 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE DETAILS

SCALE	BRIDGE FILE
AS NOTED	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	16 of 18
	CONTRACT
	B-44532

Plot: 4/9/2026

File: BR_Misc Structure Details.dgn
Model:Untitled Sheet

SUMMARY OF BRIDGE QUANTITIES

ITEM	CONCRETE CLASS C SUPERSTR	REINF. BARS, EPOXY COATED	GRATES, BASINS, & FITTINGS, CAST IRON	SURFACE SEAL**	SURFACE SEAL, DECORATIVE STAIN**	FIBER WRAP CONCRETE CASING SYSTEM**	PATCHING CONCRETE STRUCTURES	BRIDGE DECK OVERLAY, RIGID	HYDRO-DEMOLITION	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	LONGITUDINAL GROOVING	BRIDGE DECK PATCHING, FULL DEPTH	OVERLAY DAM	BRIDGE EXPANSION JOINT SEAL, TYPE PCF, REPLACE	EPOXY INJECTION, CRACK PREPARATION	EPOXY INJECTION, EPOXY MATERIAL	TERMINAL JOINT, TYPE HMA MODIFIED	FIELD DRILLED HOLE IN CONCRETE
	CYS	LBS	EACH	SFT	SFT	SFT	SFT	SYS	SYS	SYS	SYS	SFT	SFT	LFT	LFT	GAL	LFT	EACH
Slab and Sidewalks	2.7	659	1	3,707			6	1,795	1,784	1,795	1,795	256	95	1,121	15	1	95	380
Arch					117	1,600	1,439								920	29		
Bridge Railing					12		12											
TOTALS	2.7	659	1	3,707	129	1,600	1,457	1,795	1,784	1,795	1,795	256	95	1,121	935	30	95	380

** Estimated Quantity

Plot: 4/9/2026

File: BR_Summary.dgn
Model:BR_Summary

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

BRIDGE SUMMARY

SCALE	BRIDGE FILE
NONE	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	17 of 18
	CONTRACT
	B-44532

PAVEMENT QUANTITIES AND APPROACH TABLE

LOCATION		WIDTH	LENGTH	EXCAVATION		HMA			CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	ASPHALT MATERIAL FOR		COMPACTED AGGREGATE FOR BASE NO. 53		JOINT ADHESIVE	MILLING, TRANSITION	LINEAR GRADING	SUBGRADE TREATMENT, TYPE II	SUBGRADE TREATMENT, TYPE IC	GEOGRID, TYPE IB	GEOTEXTILE FOR PAVEMENT, TYPE 2B	DENSE GRADED SUBBASE	SIDEWALK, CONCRETE	CURB, CONCRETE	CURB AND GUTTER, CONCRETE	PCCP FOR APPROACHES, 9 IN.,	CASTING, INLET, ADJUST TO GRADE	CASTING, MANHOLE, ADJ. TO GRADE	REMARKS
						SURFACE QC/QA, 3, 58H, 9.5mm	INTERMD QC/QA, 3, 58H, 19mm	BASE QC/QA, 3, 58S, 25mm		PRIME COAT	TACK COAT	DEPTH 6 IN.																	
						LBS PER SYD																						
				CUT	FILL	165	275	1210																				
		FT	FT	CYS	CYS	TONS	TONS	TONS	TON	SYS	TON	CYS	TONS	LFT	SYS	LFT	SYS	SYS	SYS	SYS	CYS	LFT	LFT	LFT	SYS	EACH	EACH	
LINE "A"																												
Sta. 63+64 to 64+14	South HMA Wedge	45.88	50			23			0.5		0.2			150	272									20				
Sta. 64+14 to 64+34	South Full Depth	45.29	20	30		9	14	63			0.3	18		120		22		107		107		24	32			2	1	
Sta. 67+94 to 68+14	North Full Depth	45.29	20	30		9	16	70			0.3	20		120		20		119		119		4		40		2		
Sta. 68+14 to 68+64	North HMA Wedge	54.01	50			27			0.5		0.2			150	325	53								107				
Sta. 64+26	Drive Approach	12.75	8.33														12		12		2				12			
TOTALS				60		68	30	133	1		1	38		540	597	95	12	226	12	226	2	28	52	147	12	4	1	

PAVEMENT MARKINGS TABLE

LOCATION	LINE, MULTI-COMPONENT			LINE, THERMO-PLASTIC	TRANSVERSE MARKING, THERMO-PLASTIC	GROOVING FOR PAVEMENT MARKINGS*
	BROKEN WHITE 6 IN.	SOLID YELLOW 6 IN.	SOLID WHITE 6 IN.	SOLID YELLOW 10 IN.	CROSSHATCH YELLOW LINE 24 IN.	
	FT	FT	FT	FT	FT	FT
63+15 to 69+29	156					64
63+47 to 69+08	140					51
64+20 to 69+16		994				272
68+64 to 69+29			65			65
63+50 to 64+20				145	22	145
59+84 to 73+83						
TOTALS	296	994	65	145	22	597

* Do Not Groove for Pavement Markings on Bridge Slab or Terminal Joints

PERMANENT EROSION CONTROL

LOCATION AT	LEFT	MEDIAN	RIGHT	MULCHED SEEDING, U	
				SYS	
South Approach	X			6	
			X	7	
North Approach	X			40	
TOTAL				53	

Plot: 4/9/2026

File: RD_Summary.dgn
Model:RD_Summary

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: ASU 4/9/2026 | DRAWN: ASU 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

ROAD SUMMARY

SCALE	BRIDGE FILE
NONE	001-90-00230 C
	DESIGNATION
	2200946
	SHEETS
	18 of 18
	CONTRACT
	B-44532