DESIGNATION	BRIDGE FILE
2200652	044-73-10858
CONTRACT	
B-44483	

STRUCTURE INFORMATION

STRUCTURE	TYPE	SPAN AND SKEW	OVER	STATION
044-73-10858	SIMPLE SPAN REINFORCED CONCRETE SLAB BRIDGE	SINGLE SPAN @ 30'-0" SKEW: 45° LT.	BRANCH OF LITTLE BLUE RIVER	507+75.00 LINE "PR-PR"

KIN PROJECT INFORMATION

DESIGNATION	PROJECT DESCRIPTION
2200652 (LEAD)	SR 44 over Branch of Little Blue River, 5.75 Miles East of I-74
2200653	SR 44 over Mud Creek, 7.46 Miles West of US 52

INDIANA DEPARTMENT OF TRANSPORTATION


BRIDGE PLANS

FOR SPANS OVER 20 FEET

ROUTE: SR 44 AT: RP 44+27

DESIGNATION NO. 2200652

Bridge Replacement on SR 44 over Branch of Little Blue River
Located approximately 5.75 miles East of I-74
Section 21, T-13-N, R-8-E, Union Township, Shelby County



Scale: 1" = 2,000'


SHELBY COUNTY

TRAFFIC DATA

A.A.D.T.	(2026)	6,037 V.P.D.
A.A.D.T.	(2046)	6,947 V.P.D.
D.H.V	(2046)	621 V.P.H.
DIRECTIONAL DISTRIBUTION		50 %
TRUCKS		8 % A.A.D.T.
		8 % D.H.V.

DESIGN DATA

DESIGN SPEED	55 MPH
PROJECT DESIGN CRITERIA	3R (NON-FREEWAY)
FUNCTIONAL CLASSIFICATION	MINOR ARTERIAL
RURAL/URBAN	RURAL
TERRAIN	LEVEL
ACCESS CONTROL	NONE



PROJECT LOCATION SHOWN BY
SHELBY COUNTY

LATITUDE: 39° 34' 00" N LONGITUDE: 85° 38' 27" W

BRIDGE LENGTH:	0.006	MI.
ROADWAY LENGTH:	0.041	MI.
TOTAL LENGTH:	0.047	MI.
MAX. GRADE:	+0.730	%

HUC: 051202040205

Plans Prepared By:

SJCA
9102 North Meridian Street, Suite 200, Indianapolis, IN 46260
Phone: (317) 566-0629

INDIANA DEPARTMENT OF TRANSPORTATION
STANDARD SPECIFICATIONS DATED 2026
TO BE USED WITH THESE PLANS.

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

PLANS PREPARED BY: SJCA, INC. (317) 566-0629 PHONE NUMBER

CERTIFIED BY: Michael J. Ficcaglia 06/15/2026 DATE

APPROVED FOR LETTING: Stephanie J. Wagner INDIANA DEPARTMENT OF TRANSPORTATION 09/03/2026 DATE

BRIDGE FILE
044-73-10858
DESIGNATION
2200652

SHEETS		
1	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:21:24 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Title.dgn
Model: Title

UTILITIES

DUKE ENERGY DISTRIBUTION
Clay Carrie
800 Old Wheatland Road
Vincennes, IN 47591
Clay.Carrie@duke-energy.com
(812) 887-3751

AT&T DISTRIBUTION
Troy Bishop
tb2932@att.com
(812) 390-7253

NINE STAR CONNECT
Jason Warrick
2243 E. Main Street
Greenfield, IN 46140
jwarrick@ninestarconnect.com
O: (317) 323-2078
C: (317) 694-9305

COMCAST
Troy Kunkel
troy.kunkel@bsmgroups.com
(812) 498-8970

811 Know what's below. Call before you dig.

INDIANA UNDERGROUND
1-800-382-5544 OR CALL 811
24 HOURS A DAY 7 DAYS A WEEK

INDEX

SHEET NO.	SUBJECT
1	TITLE
2	INDEX
3	TYPICAL SECTIONS
4	PLAT NO. 1
5 - 7	MAINTENANCE OF TRAFFIC
8	EROSION CONTROL
9 - 10	SOIL BORINGS
11	LAYOUT
12	GENERAL PLAN
13 - 17	SUPERSTRUCTURE DETAILS
18	RAILING DETAILS
19	REINFORCED CONCRETE BRIDGE APPROACH
20	BRIDGE SUMMARY TABLE
21	MISCELLANEOUS TABLES
22 - 29	CROSS SECTIONS - LINE "PR-PR"

REVISIONS

SHEET NO.	DATE	REVISED

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL Michael J. Ficcaglia 06/15/2026
DESIGN ENGINEER DATE

DESIGNED: DSR DRAWN: DSR
CHECKED: MJF CHECKED: MHF


INDIANA
DEPARTMENT OF TRANSPORTATION

INDEX

SCALE	BRIDGE FILE
N/A	044-73-10858
	DESIGNATION
	2200652


SHEETS: 2 of 29
CONTRACT: B-44483

Plot:5/28/2026 7:21:29 PM
File:H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Index.dgn
Model:Index




AGGREGATE SHOULDER WIDENING TYPICAL SECTION

Sta. 505+10.00 "PR-PR" to Sta. 505+40.00 "PR-PR"
Sta. 509+75.00 "PR-PR" to Sta. 509+92.00 "PR-PR"
Scale: ¼" = 1'-0"



SAFETY EDGE DETAIL

Not to Scale




THIS SIDE SHOWN W/ GUARDRAIL

THIS SIDE SHOWN W/O GUARDRAIL


TYPICAL OVERLAY AND WIDENING INCIDENTAL SECTION

Sta. 505+40.00 "PR-PR" to Sta. 506+00.00 "PR-PR"
Sta. 508+50.00 "PR-PR" to Sta. 509+75.00 "PR-PR"
Scale: ¼" = 1'-0"



RIPRAP SIDE DITCH DETAIL

See Profile for Locations
Not to Scale



THIS SIDE SHOWN W/ GUARDRAIL

THIS SIDE SHOWN W/O GUARDRAIL

TYPICAL FULL-DEPTH SECTION

Sta. 506+00.00 "PR-PR" to Sta. 507+38.56 "PR-PR"
Sta. 508+11.44 "PR-PR" to Sta. 508+50.00 "PR-PR"
Scale: ¼" = 1'-0"

Paving Exception
Sta. 507+38.56 "PR-PR" to Sta. 508+11.44 "PR-PR"

LEGEND

- (K) 165 lbs/syd QC/QA-HMA, 3, 58H, Surface, 9.5 mm on
  275 lbs/syd QC/QA-HMA, 3, 58H, Intermediate, 19.0 mm on
  880 lbs/syd QC/QA-HMA, 3, 58S, Base, 25.0 mm on
  Subgrade Treatment, Type IC on
  Geogrid, Type IB
- (M) HMA for Approaches, Type B
  165#/syd HMA Surface Type B on
  275#/syd HMA Intermediate Type B on
  6" Compacted Aggregate No. 53, on
  Subgrade Treatment Type II (6 in. Coarse Aggregate No. 53)
- (O) Variable-Depth Compacted Aggregate, No. 53 (12" Max.)
- (P1) Joint Adhesive required for Surface layer at longitudinal joints
- (P2) Joint Adhesive required for Surface and
  Intermediate layers at longitudinal joints
- (R) 165 lbs/syd (Min.) QC/QA-HMA, 3, 58H, Surface, 9.5 mm on
  Milling, Asphalt, $1\frac{1}{2}$ in.
- (1) Slope Treatment: Mulched Seeding 'R' for Slopes 3:1 or flatter.
  Erosion Control Blankets for Slopes steeper than 3:1.
- Subgrade Treatment, Type IC

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL Michael J. Ficcaglia 06/15/2026
DESIGN ENGINEER DATE

DESIGNED: MHF DRAWN: MHF
CHECKED: MJF CHECKED: MJF


INDIANA
DEPARTMENT OF TRANSPORTATION

TYPICAL SECTIONS

SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS		
3	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:21:35 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_TypSec.dgn
Model: Typ Sec - Typical Sections [Sheet]



NOTE

Apparent Existing R/W was Acquired in 1941 but not Recorded in a Timely Fashion. Reacquisition Required.

PROPERTY OWNER

1. TRUSTEES OF THE CHARLOTTE N. GORDON IRR. TRUST
2. PAUL & LYNNE RALSTON
3. CAROLYN BLAIR, SHARON REESE, CHARLES KELLER AND SANDRA ESTES

SJCA

MICHAEL J. FICCAGLIA
REGISTERED
No. PE11800778
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 06/15/2026 DATE

DESIGNED: MHF | DRAWN: MHF

CHECKED: DS | CHECKED: DS

INDIANA
DEPARTMENT OF TRANSPORTATION

PLAT NO. 1


SCALE	BRIDGE FILE
1" = 100'	044-73-10858
	DESIGNATION
	2200652

SHEETS: 4 of 29

CONTRACT
B-44483

Plot: 5/28/2026 7:21:42 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Plat1.dgn
Model: LINE C Plat [Sheet]



DETOUR PLAN
Scale: 1" = 5,000'

DETOUR ROUTE MARKER ASSEMBLY LEGEND

DETOUR / EAST/WEST	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")		
INDIANA 44	M1-5 (24" x 24")		
	M6-3 (21" x 15")		
XRMA-1 (1)			

DETOUR / EAST/WEST	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")		
INDIANA 44	M1-5 (24" x 24")		
	M6-1(L or R) (21" x 15")		
XRMA-2 (2)			

DETOUR / EAST/WEST	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")		
INDIANA 44	M1-5 (24" x 24")		
	M5-1(L or R) (21" x 15")		
XRMA-3 (3)			

DETOUR / EAST/WEST	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")		
INDIANA 44	M1-5 (24" x 24")		
	M5-2(L or R) (21" x 15")		
XRMA-4 (4)			

DETOUR / EAST/WEST	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")		
INDIANA 44	M1-5 (24" x 24")		
	M6-2(L or R) (21" x 15")		
XRMA-5 (5)			

END DETOUR / EAST/WEST	XM4-8a (24" x 18") / M3-2 or M3-4 (24" X 12")		
INDIANA 44	M1-5 (24" x 24")		
	M6-1(L or R) (21" x 15")		
XRMA-7 (6)			

NOTES
1. Detour route marker assemblies shall be in accordance with standard drawing 801-TCDT-04.
2. Sign spacing shall be in compliance with current IMUTCD, INDOT standard drawings E801-TCSC-01, and INDOT standard specifications.
3. Type B construction warning lights shall be used with all signs located on barricades.
4. Type A construction warning lights shall be used on all other construction signs.
5. Access to property owners shall be provided during construction.
6. See Sheet No. 6 for Detail "A" and Detail "B".
7. See Sheet No. 7 for Detail "C" and Detail "D".

LEGEND
- (A) "ROAD CLOSED AHEAD" - XW20-3
- (B) "DETOUR AHEAD" - XW20-2
- (C) ROAD CLOSURE SIGN ASSEMBLY WITH "ROAD CLOSED X MILES AHEAD LOCAL TRAFFIC ONLY" - R11-3 "DETOUR ARROW" - XM4-10 (L or R) AND TYPE III-B BARRICADES STAGGERED - 24 LFT REQUIRED
- (D) "ROAD CLOSED 1000 FT." - XW20-3
- (E) "ROAD CLOSED 500 FT." - XW20-3
- (F) ROAD CLOSURE NOTICE SIGN - XG20-5
- (G) ROAD CLOSURE SIGN ASSEMBLY WITH "ROAD CLOSED" - R11-2 AND TYPE III-A BARRICADES - 48 LFT REQUIRED
- (H) "EAST" OR "WEST" - M3-2 or M3-4 "STATE ROAD" - M1-5 "DETOUR AHEAD" - XW20-2
- SIGN ASSEMBLY
- DETOUR ROUTE

MAINTENANCE OF TRAFFIC QUANTITIES

ITEM	DESCRIPTION	SIZE (IN.)	TOTAL QTY	UNIT
Construction Sign, A			22	EACH
Road Closure Sign Assembly			9	EACH
Barricades, III-A			96	LFT
Barricades, III-B			96	LFT
Detour Route Marker Assembly			54	EACH

TWO ROAD CLOSURE NOTICE SIGNS XG20-5 REQUIRED (ONE AT EACH END) PLACED AT SITE A MINIMUM OF 14 DAYS PRIOR TO ROAD CLOSURE

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER 06/15/2026 DATE

DESIGNED: MHF DRAWN: MHF CHECKED: MAH CHECKED: MAH

INDIANA DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC DETOUR ROUTE


SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS 5 of 29


CONTRACT B-44483

Plot: 5/28/2026 7:21:46 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_MOT.dgn
Model: Unnamed Plan - MOT [Sheet]



DETAIL "A"
Scale: 1" = 300'



DETAIL "B"
Scale: 1" = 500'

DETOUR ROUTE MARKER ASSEMBLY LEGEND

DETOUR / EAST/WEST	DETOUR / EAST/WEST	DETOUR / EAST/WEST	DETOUR / EAST/WEST	DETOUR / EAST/WEST	END DETOUR / EAST/WEST
XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8a (24" x 18") / M3-2 or M3-4 (24" X 12")
INDIANA 44 / M1-5 (24" x 24")	INDIANA 44 / M1-5 (24" x 24")	INDIANA 44 / M1-5 (24" x 24")	INDIANA 44 / M1-5 (24" x 24")	INDIANA 44 / M1-5 (24" x 24")	INDIANA 44 / M1-5 (24" x 24")
M6-3 (21" x 15")	M6-1(L or R) (21" x 15")	M5-1(L or R) (21" x 15")	M5-2(L or R) (21" x 15")	M6-2(L or R) (21" x 15")	M6-1(L or R) (21" x 15")
XRMA-1 (1)	XRMA-2 (2)	XRMA-3 (3)	XRMA-4 (4)	XRMA-5 (5)	XRMA-6 (6)

LEGEND

- (A) "ROAD CLOSED AHEAD" - XW20-3
- (B) "DETOUR AHEAD" - XW20-2
- (C) ROAD CLOSURE SIGN ASSEMBLY WITH "ROAD CLOSED X MILES AHEAD LOCAL TRAFFIC ONLY" - R11-3 "DETOUR ARROW" - XM4-10 (L or R) AND TYPE III-B BARRICADES STAGGERED - 24 LFT REQUIRED
- (D) "ROAD CLOSED 1000 FT." - XW20-3
- (E) "ROAD CLOSED 500 FT." - XW20-3
- (F) ROAD CLOSURE NOTICE SIGN - XG20-5
- (G) ROAD CLOSURE SIGN ASSEMBLY WITH "ROAD CLOSED" - R11-2 AND TYPE III-A BARRICADES - 48 LFT REQUIRED
- (H) "EAST" OR "WEST" - M3-2 or M3-4 "STATE ROAD" - M1-5 "DETOUR AHEAD" - XW20-2
- SIGN ASSEMBLY
- DETOUR ROUTE

NOTES

1. Detour route marker assemblies shall be in accordance with standard drawing 801-TCDT-04.
2. Sign spacing shall be in compliance with current IMUTCD, INDOT standard drawings E801-TCSC-01, and INDOT standard specifications.
3. Type B construction warning lights shall be used with all signs located on barricades.
4. Type A construction warning lights shall be used on all other construction signs.
5. Access to property owners shall be provided during construction.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER — 06/15/2026 DATE

DESIGNED: MHF | DRAWN: MHF

CHECKED: MAH | CHECKED: MAH

INDIANA
DEPARTMENT OF TRANSPORTATION


MAINTENANCE OF TRAFFIC
DETAILS

SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652


SHEETS		
6	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:21:47 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_MOT.dgn
Model: Unnamed Plan-1 - Detail B [Sheet]



DETAIL "C"
Scale: 1" = 500'



DETAIL "D"
Scale: 1" = 500'

DETOUR ROUTE MARKER ASSEMBLY LEGEND

DETOUR / EAST/WEST	DETOUR / EAST/WEST	DETOUR / EAST/WEST	DETOUR / EAST/WEST	DETOUR / EAST/WEST	END DETOUR / EAST/WEST
XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8 (24" X 12") / M3-2 or M3-4 (24" X 12")	XM4-8a (24" x 18") / M3-2 or M3-4 (24" X 12")
INDIANA 44 M1-5 (24" x 24")	INDIANA 44 M1-5 (24" x 24")	INDIANA 44 M1-5 (24" x 24")	INDIANA 44 M1-5 (24" x 24")	INDIANA 44 M1-5 (24" x 24")	INDIANA 44 M1-5 (24" x 24")
M6-3 (21" x 15")	M6-1(L or R) (21" x 15")	M5-1(L or R) (21" x 15")	M5-2(L or R) (21" x 15")	M6-2(L or R) (21" x 15")	M6-1(L or R) (21" x 15")
XRMA-1 (1)	XRMA-2 (2)	XRMA-3 (3)	XRMA-4 (4)	XRMA-5 (5)	XRMA-6 (6)

LEGEND

- (A) "ROAD CLOSED AHEAD" - XW20-3
- (B) "DETOUR AHEAD" - XW20-2
- (C) ROAD CLOSURE SIGN ASSEMBLY WITH "ROAD CLOSED X MILES AHEAD LOCAL TRAFFIC ONLY" - R11-3 "DETOUR ARROW" - XM4-10 (L or R) AND TYPE III-B BARRICADES STAGGERED - 24 LFT REQUIRED
- (D) "ROAD CLOSED 1000 FT." - XW20-3
- (E) "ROAD CLOSED 500 FT." - XW20-3
- (F) ROAD CLOSURE NOTICE SIGN - XG20-5
- (G) ROAD CLOSURE SIGN ASSEMBLY WITH "ROAD CLOSED" - R11-2 AND TYPE III-A BARRICADES - 48 LFT REQUIRED
- (H) "EAST" OR "WEST" - M3-2 or M3-4 "STATE ROAD" - M1-5 "DETOUR AHEAD" - XW20-2
- SIGN ASSEMBLY
- DETOUR ROUTE

NOTES

1. Detour route marker assemblies shall be in accordance with standard drawing 801-TCDT-04.
2. Sign spacing shall be in compliance with current IMUTCD, INDOT standard drawings E801-TCSC-01, and INDOT standard specifications.
3. Type B construction warning lights shall be used with all signs located on barricades.
4. Type A construction warning lights shall be used on all other construction signs.
5. Access to property owners shall be provided during construction.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER — 06/15/2026 DATE

DESIGNED: MHF | DRAWN: MHF

CHECKED: MAH | CHECKED: MAH

INDIANA
DEPARTMENT OF TRANSPORTATION


MAINTENANCE OF TRAFFIC
DETAILS

SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS		
7	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:21:47 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_MOT.dgn
Model: Unnamed Plan-1 - Detail C [Sheet]



PLAN

Scale: 1" = 20'

NOTES

1. All R/W and existing topography referenced from Line "C" unless otherwise noted.
2. Existing R/W was Acquired in 1941 but not Recorded in a Timely Fashion. Reacquisition Required.
3. Line "PR-PR" to be Constructed.

TEMPORARY EROSION CONTROL TABLE

STATION	LOCATION			TEMPORARY FILTER SOCK	TEMPORARY NO. 5 STONE	TEMPORARY GEOTEXTILE	TEMP SEDIMENT REMOVE	TEMPORARY CHECK DAM, REVETMENT RIPRAP	TEMPORARY NO. 2 STONE	TEMPORARY SEEDING	MOBILIZATION / DEMOBILIZATION FOR SURFACE STABILIZATION	REMARKS
	LEFT	MEDIAN	RIGHT	LFT	TON	SYS	CYS	TON	TON	LBS	EACH	
LINE "PR-PR"												
505+09 to 508+03			X	296			6					
505+40 to 506+82	X			145			3					
507+41 to 508+12	X			85			2					
508+24 to 509+75	X			164			4					
508+98 to 509+92			X	102			3					
507+68			X		2	12		5				
508+56	X				2	12		5				
UNDISTRIBUTED						235			100	40	2	
TOTALS				**792**	**4**	**259**	**18**	**10**	**100**	**40**	**2**	

LEGEND

- Cofferdam w/ Impervious Sheeting
- FS - Filter Sock
- SC - Secondary Containment (Rock Filter Berm)
- DF - Diffuser (Energy Dissipator) on Riprap with Geotextile
- SDP - Stream Diversion Pump
- DWP - Dewatering Pump
- ESZ - Embankment Stabilized Zone to prevent erosion during pump activation
- FB - Filter Bag on Leveling Pad w/ Filter Fabric
- SH/PI - Sump Hole / Pump Intake
- TCD - Temporary Check Dam, Revetment Riprap

NOTES

1. Any areas in addition to those called out, left undisturbed for a period exceeding 7 days shall be required to have Temporary Seeding.
2. All disturbed areas shall be permanently Seeded in accordance with INDOT Standard Specifications as soon as possible upon completion of work in that area.
3. Upon completion of grading, permanent Erosion Control measures specified on road plans shall be implemented.
4. Erosion Control Blankets will be used on all slopes steeper than 3:1.
5. Refer to Standard Drawings 205-TECD, 205-TEC1, 205-TECP for Erosion Control measures.
6. Pump around operation shall remain in place until all work in the channel is complete.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER 06/15/2026 DATE

DESIGNED: MHF DRAWN: MHF

CHECKED: DS CHECKED: DS

INDIANA DEPARTMENT OF TRANSPORTATION

EROSION CONTROL DETAILS


SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS 8 of 29

CONTRACT B-44483

Plot: 5/28/2026 7:21:57 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_ErosCont.dgn
Model: PR-PR - Plan [Sheet]



PLAN

Not To Scale

SUMMARY OF PILE LOADING FOR GEOTECHNICAL TESTING

	Bent No. 1	Bent No. 2
Pile Size, Type, and Grade	14-in Dia. X 0.250 in. CEP Pile, Grade 3	
Factored Design Load, Q_f (kips)	142	142
Design Soil Resistance, R_R (kips)	142	142
Resistance Factor for Axial Compression Φ_{dyn}	0.7	0.7
Downdrag Load, DD (kips)	N/A	N/A
Nominal Soil Resistance, R_n (kips)	202.9	202.9
Downdrag friction, $R_{s\,dd}$ (kips)	N/A	N/A
Scour Zone Friction, $R_{s\,scour}$ (kips)	N/A	N/A
Relaxation in Shale (kip)	N/A	N/A
Nominal Driving Resistance, R_{ndr} (kips)	202.9	202.9
Estimated Pile Top Elevation (ft)	872.97	872.83
Minimum Pile Tip Elevation* (ft)	820.97	820.83
Estimated Pile Tip Elevation (ft)	841.97	839.83
Testing Method	INDOT Standard Specification Section 701.05(b)	

* - In Accordance With INDOT Design Manual Figures 408-3B and 408-3D

RESOURCE INTERNATIONAL, INC.

BORING LOG

BORING NO.: TB-01
SHEET 1 OF 4
LATITUDE: 39.566563
LONGITUDE: -85.640925
DATUM: NAD 83
DATE STARTED: 07-14-25
DATE COMPLETED: 07-16-25

ROUTE #: SR 44 COUNTY: Shelby
PROJECT TYPE: Bridge Replacement
LOCATION: SR 44 over Little Blue River
DES NO.: 2200652 RII PROJECT NO.: I-24-095

ELEVATION	877.6 ft	BORING METHOD	3.25" - HSA
STATION	507+29	RIG TYPE	Mobile B57
OFFSET	16.0 ft Left	CASING DIA.	N/A
LINE	PR-PR	CORE SIZE	2.0"NQ
DEPTH	89.9 ft	HAMMER	Auto
		DRILLER/INSP	SB/BH
		TEMPERATURE	80's °F
		WEATHER	Sunny

GROUNDWATER: Encountered at 18.5 ft; At completion N/A; Caved in at 26.5 ft

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	DRY UNIT WEIGHT, PCF	ATTERBERG LIMITS LL	PL	PI	POCKET PEN., tsf	UNCONF. COMP., ksf
876.8	1	**9.75" - Asphalt**. 0.8											
876.5		**3.75" - Aggregate Base**. 1.1											
	2	**Silty Loam A-6**, Brownish Gray To Brown, Slightly Moist To Very Moist, Very Soft To Soft, (Same as Lab-1).	SS 1	1 2 3	56	5	10					2.0	
	4		SS 2	0 2 3	78	5	21					2.0	
	6		SS 3	2 1 0	71	1	20					2.5	
869.6	8	8.0											
	9	**Sandy Loam A-4 (0)**, Brownish Gray, Moist, Soft To Very Stiff, (Lab-2).	SS 4	2 3 6	83	9	10					1.5	
	12		SS 5	3 8 11	94	19	10					4.5	
	14		SS 6	6 12 9	83	21	8					4.5	
	17		ST 7		94		7		15	8	7	4.5	5.11
	19		SS 8	1 3 5	78	8	11					4.0	
	22		SS 9	0 3 5	97	8	11					2.0	
	24		SS 10	0 1 4	100	5	10					2.0	

Continued on next page

RESOURCE INTERNATIONAL, INC.

BORING LOG

BORING NO.: TB-01
SHEET 2 OF 4
LATITUDE: 39.566563
LONGITUDE: -85.640925
DATUM: NAD 83

ROUTE #: SR 44 COUNTY: Shelby
PROJECT TYPE: Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	DRY UNIT WEIGHT, PCF	ATTERBERG LIMITS LL	PL	PI	POCKET PEN., tsf	UNCONF. COMP., ksf
	26	**Sandy Loam A-4 (0)**, Brownish Gray, Moist, Soft To Very Stiff, (Lab-2).	SS 11	1 2 12	89	14	12					1.5	
849.6	28	28.0											
	29	**Sandy Gravel A-1-a**, Brownish Gray, Wet, Medium Dense To Dense, (Lab-3).	SS 12	3 6 6	78	12							
	31	Heaving sand encountered at depths 28.5' and 33.5'.											
	33	Mud added at 33.5'.	SS 13	4 11 13	50	24			NP	NP	NP		
	36												
	38		SS 14	23 20 13	42	33							
	41												
	43		SS 15	6 13 16	61	29	18					4.5	
832.6	45	45.0											
	46	**Sandy Loam A-4 (1)**, Brownish Gray, Slightly Moist, Very Dense, (Lab-4).											
	48												
	49		SS 16	13 41 50/5"	85		8					4.5+	
	52												
	54		SS 17	20 25 37	86	62	10		21	12	9	4.5	

Continued on next page

RESOURCE INTERNATIONAL, INC.

BORING LOG

BORING NO.: TB-01
SHEET 3 OF 4
LATITUDE: 39.566563
LONGITUDE: -85.640925
DATUM: NAD 83

ROUTE #: SR 44 COUNTY: Shelby
PROJECT TYPE: Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	DRY UNIT WEIGHT, PCF	ATTERBERG LIMITS LL	PL	PI	POCKET PEN., tsf	UNCONF. COMP., ksf
	56	**Sandy Loam A-4 (1)**, Brownish Gray, Slightly Moist, Very Dense, (Lab-4).											
	59		SS 18	50/3"	100		13					4.5	
	64		SS 19	50/2"	100		13					4.5+	
	66	*Auger Refusal at 65.5 feet.*											
	67	*Cored from 65.5' to 70.5'. 2 inches of gravel recovered.*	RC 1 RQD= 0%		3								
	71		SS 20	50/4"	100		8					4.5+	
	74		SS 21	10 27 39	100	66	15						
	79		SS 22	8 50/5"	100		8					4.5	
	84		SS 23	18 50/5"	91		10					4.5	

Continued on next page

RESOURCE INTERNATIONAL, INC.

BORING LOG

BORING NO.: TB-01
SHEET 4 OF 4
LATITUDE: 39.566563
LONGITUDE: -85.640925
DATUM: NAD 83

ROUTE #: SR 44 COUNTY: Shelby
PROJECT TYPE: Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	DRY UNIT WEIGHT, PCF	ATTERBERG LIMITS LL	PL	PI	POCKET PEN., tsf	UNCONF. COMP., ksf
	87	**Sandy Loam A-4 (1)**, Brownish Gray, Slightly Moist, Very Dense, (Lab-4).											
	89		SS 24	12 36 50/5"	100		8					4.5	
787.7	90	Bottom of Boring at 89.9 ft 89.9											
	91	Grouted with a mixture of cement and bentonite chips to a depth of 10.0' followed by backfilling with a mixture of bentonite chips and soil cuttings to a depth of 1.0'. Pavement patched with concrete.											

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL Michael J. Ficcaglia 06/15/2026
DESIGN ENGINEER DATE

DESIGNED: MHF DRAWN: MHF
CHECKED: DS CHECKED: DS


INDIANA
DEPARTMENT OF TRANSPORTATION

SOIL BORINGS
TB-01

SCALE	BRIDGE FILE
N/A	044-73-10858
	DESIGNATION
	2200652

SHEETS 9 of 29
CONTRACT
B-44483

Plot:5/28/2026 7:22:11 PM
File:H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_SoilBoring.dgn
Model:Borings 01-01



PLAN

Not To Scale

RESOURCE INTERNATIONAL, INC.

BORING LOG

BORING NO.: TB-02
SHEET 1 OF 4
LATITUDE: 39.566615
LONGITUDE: -85.640594
DATUM: NAD 83
DATE STARTED: 07-15-25
DATE COMPLETED: 07-16-25

ROUTE #: SR 44 COUNTY: Shelby
PROJECT TYPE: Bridge Replacement
LOCATION: SR 44 over Little Blue River
DES NO.: 2200652 RII PROJECT NO.: I-24-095

ELEVATION: 877.9 ft	BORING METHOD: 3.25" - HSA	HAMMER: Auto
STATION: 508+20	RIG TYPE: Mobile B57	DRILLER/INSP: SB/BH
OFFSET: 14.0 ft Right	CASING DIA.: N/A	TEMPERATURE: 80's °F
LINE: "PR-PR"	CORE SIZE: N/A	WEATHER: Sunny
DEPTH: 90.0 ft		

GROUNDWATER: ▽ Encountered at N/A ▼ At completion 13.5 ft ⊠ Caved in at 89.5 ft

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	DRY UNIT WEIGHT, PCF	ATTERBERG LIMITS LL	PL	PI	POCKET PEN., tsf	UNCONF. COMP., ksf
877.2	1	**8.75" - Asphalt**. 0.7											
876.7		**5.75" - Aggregate Base**. 1.2											
	2	**Silty Loam A-4 (2)**, Brownish Gray, Moist To Very Moist, Very Soft To Soft, (Lab-5).	SS 1	3 2 2	69	4	24	102	24	16	8	2.0	
	3												
	4		SS 2	1 0 0	0	2							
	5		SS 2A	2 2	100		21					0.5	
	6												
	7		SS 3	2 3 2	100	5	16					1.5	
	8												
	9		SS 4	0 0 0	72	0	16					0.5	
867.4	10	10.5											
	11	**Sandy Loam A-4 (1)**, Brown, Slightly Moist To Moist, Very Stiff To Hard, (Lab-6).											
	12		SS 5	4 10 16	100	26	9					4.5	
	13												
	14		SS 6	6 15 21	89	36	8					4.5	
	15												
	16		SS 7	14 24 22	81	46	7					4.5	
	17												
	18												
	19		SS 8	23 46 34	100	80	7					4.5	
	20												
	21												
	22		SS 9	22 38 15	44	53	11					4.5	
	23												
	24		SS 10	24 11 12	83	23	10		17	9	8	4.0	
	25												

Continued on next page

RESOURCE INTERNATIONAL, INC.

BORING LOG

BORING NO.: TB-02
SHEET 2 OF 4
LATITUDE: 39.566615
LONGITUDE: -85.640594
DATUM: NAD 83

ROUTE #: SR 44 COUNTY: Shelby
PROJECT TYPE: Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	DRY UNIT WEIGHT, PCF	ATTERBERG LIMITS LL	PL	PI	POCKET PEN., tsf	UNCONF. COMP., ksf
852.4	26	25.5											
	27	**Silty Loam A-6**, Brownish Gray, Moist To Wet, Medium Dense To Very Dense, (Same as Lab-1).	ST 11		25		15					1.0	
	28												
	29	Hard drilling condition observed at a depth of 26.0 feet. Water added at 26.0 feet.	SS 12	17 17 7	47	24	10					3.5	
	30												
	31												
	32												
	33												
	34		SS 13	50/5"	100							2.0	
	35												
841.9	36	36.0											
	37	**Sandy Gravel A-1-a**, Brownish Gray, Wet, Dense To Very Dense, (Same as Lab-3).											
	38												
	39		SS 14	38 24 20	42	44							
	40												
	41												
	42												
	43												
	44		SS 15	24 12 14	100	26							
	45												
	46												
830.9	47	47.0											
	48	**Sandy Loam A-6 (1)**, Brownish Gray, Slightly Moist, Hard, (Lab-7).											
	49												
	50	Mud added at 48.5'.	SS 16	16 30 40	100	70						3.5	
	51												
	52												
	53												
	54												
	55		SS 17	14 39 50/3"	100		11					4.5	

Continued on next page

RESOURCE INTERNATIONAL, INC.

BORING LOG

BORING NO.: TB-02
SHEET 3 OF 4
LATITUDE: 39.566615
LONGITUDE: -85.640594
DATUM: NAD 83

ROUTE #: SR 44 COUNTY: Shelby
PROJECT TYPE: Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	DRY UNIT WEIGHT, PCF	ATTERBERG LIMITS LL	PL	PI	POCKET PEN., tsf	UNCONF. COMP., ksf
	56	**Sandy Loam A-6 (1)**, Brownish Gray, Slightly Moist, Hard, (Lab-7).											
	57												
	58												
	59		SS 18	11 31 46	100	77	7					4.5	
	60												
	61												
	62												
	63												
	64		SS 19	17 44 50/5"	94		8					4.5	
	65												
	66												
	67												
	68												
	69		SS 20	20 34 50/6"	100		11		19	8	11	4.5	
	70												
	71												
	72												
	73												
	74		SS 21	10 50/5"	100		11					4.5	
	75												
	76												
	77												
	78												
	79		SS 22	10 33 50/6"	100		6					4.5	
	80												
	81												
	82												
	83												
	84		SS 23	7 47 50/3"	100		10					4.5	
	85	Heaving sand encountered at depths 83.5' and 89.5'.											
	86												

Continued on next page

RESOURCE INTERNATIONAL, INC.

BORING LOG

BORING NO.: TB-02
SHEET 4 OF 4
LATITUDE: 39.566615
LONGITUDE: -85.640594
DATUM: NAD 83

ROUTE #: SR 44 COUNTY: Shelby
PROJECT TYPE: Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	DRY UNIT WEIGHT, PCF	ATTERBERG LIMITS LL	PL	PI	POCKET PEN., tsf	UNCONF. COMP., ksf
	87	**Sandy Loam A-6 (1)**, Brownish Gray, Slightly Moist, Hard, (Lab-7).											
	88												
	89												
787.9	90	90.0	SS 24	24 31 50/6"	100		10					4.5	
		Bottom of Boring at 90.0 ft											
		Grouted with a mixture of cement and bentonite chips to a depth of 10.0' followed by backfilling with a mixture of bentonite chips and soil cuttings to a depth of 1.0'. Pavement patched with concrete.											

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL Michael J. Ficcaglia 06/15/2026
DESIGN ENGINEER DATE

DESIGNED: MHF DRAWN: MHF
CHECKED: DS CHECKED: DS


INDIANA
DEPARTMENT OF TRANSPORTATION

SOIL BORINGS
TB-02

SCALE	BRIDGE FILE
N/A	044-73-10858
	DESIGNATION
	2200652

SHEETS: 10 of 29
CONTRACT: B-44483

Plot: 5/28/2026 7:22:20 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_SoilBoring.dgn
Model: Borings 02-01



NOTES

1. All R/W and existing topography referenced from Line "C" unless otherwise noted.
2. Apparent Existing R/W was Acquired in 1941 but not Recorded in a Timely Fashion. Reacquisition Required.
3. Line "PR-PR" to be Constructed.

UTILITIES

See Index Sheet For Information.

EXISTING STRUCTURE

Existing structure is a Single Span Reinforced Concrete Slab Bridge with a 45° Left Skew (To be removed)


HYDRAULIC DATA

Drainage Area	0.65 Sq. Mi
Design Discharge (Q100)	627 Cfs
Backwater @ Q100	0.05 ft
Avg. Velocity @ Q100*	7.62 ft/s
Headwater Elevation @ Q100	878.50 ft
Waterway Opening Provided below Q100 (Structure)	83.99 Sft
Outlet Flowline Elevation	869.59 ft
Minimum Low Structure Elevation	876.28 ft
Skew	45° Lt.
Existing Waterway Opening Below Q100	76.44 sq ft
Existing Waterway Opening over Road @ Q100	57.90 sq ft
Road Overflow Waterway Area	55.89 sq ft
Existing Low Structure Elevation	875.24 ft
Existing Backwater @ Q100	0.14 ft
Existing Velocity @ Q100	7.96 ft/sec
Existing Headwater Elevation @ Q100	878.58 ft
Natural Q100	878.42 ft

HYDRAULIC SCOUR DATA*

Q100 Contraction Scour	2.87 ft
Q100 Total Scour	2.87 ft
Q100 Low Scour Elevation	866.72 ft
Q100 Max. Velocity	9.67 ft/sec
QMax Design Discharge	650 Cfs
QMax Elevation	876.35 ft
QMax Contraction Scour	3.76 ft
QMaxTotal Scour	3.76 ft
QMax Low Scour Elevation	865.83 ft
QMax Max. Velocity	9.70 ft/sec

* A culvert exists on a private property downstream of the structure. Ignoring the effect of this culvert produces the highest velocities and scour depths.



LEGEND


K	Area of Full Depth HMA Pavement (See Typ. Sections)
R	Area of Overlay & Shoulder Widening (See Typ. Sections)
O	Area of Aggregate Shoulder Widening (See Typ. Sections)
1	Guardrail End Treatment, Type OS
2	Guardrail Transition, Type MGS Without Curb
3	87.50 Lft of Guardrail, MGS, W-Beam 6'-3" Spa.
4	Guardrail Transition, Type TGB
5	Curved W-Beam Guardrail Terminal System, Type 1

EARTHWORK SUMMARY

Fill +20%	181 CYS
Common Excavation	535 CYS
70% Foundation Excavation	170 CYS
Borrow	0 CYS
Total Waterway Excavation	0 CYS
Foundation Excavation Unclassified	243 CYS
Benching (Estimated)	143 CYS

No direct payment for Benching. Benching will not be paid for as Common Excavation.

SIMPLE SPAN REINFORCED CONCRETE SLAB BRIDGE
SINGLE SPAN @ 30'-0"
40'-0" CLEAR ROADWAY; SKEW: 45° LT.
SR 44 OVER BRANCH OF LITTLE BLUE CREEK
SHELBY COUNTY, INDIANA



SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL Michael J. Ficcaglia 06/15/2026
DESIGN ENGINEER DATE

DESIGNED: MHF DRAWN: MHF
CHECKED: MJF CHECKED: MJF

INDIANA DEPARTMENT OF TRANSPORTATION


LAYOUT

HORIZONTAL SCALE	BRIDGE FILE
1" = 30'	044-73-10858
VERTICAL SCALE	DESIGNATION
1" = 5'	2200652

SHEETS		
11	of	29
CONTRACT		
B-44483		


Plot: 5/28/2026 7:22:39 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Layout.dgn
Model: Layout - Plan [Sheet]

STRUCTURE BUILT ON 170' VERTICAL CURVE




ELEVATION

Scale: ⅛" = 1'-0"




PLAN

Scale: ⅛" = 1'-0"




TYPICAL SECTION

Scale: ¼" = 1'-0"




RIPRAP DRAINAGE TURNOUT TYPICAL SECTION

No Scale



RIPRAP DRAINAGE TURNOUT SPLASH PAD PLAN

No Scale



RIPRAP KEY DETAIL

No Scale

GENERAL NOTES

Reinforcing Steel Cover Shall be 2½" in Top, 2" Min. in Bottom of Slabs, 2" All Other Parts Unless Noted.

DESIGN DATA

LIVE LOAD:
Designed for HL-93 Loading With Impact and Distribution in Accordance With the 2020 AASHTO LRFD Specifications, 9th Edition and Subsequent Interims.

DEAD LOAD:
Floor Slab Designed with a 1'-7½" min. Structural Depth and a ½" Integral Wearing Surface.

Actual Weight Plus 35 Psf (Composite) for Future Wearing Surface.

DESIGN STRENGTHS

Class "C" Concrete	f'c = 4,000 PSI
Reinforcing Steel	fy = 60,000 PSI

SEISMIC DESIGN DATA

Seismic Performance Zone	Zone 1
Acceleration Coefficient	0.120
Seismic Soil Profile Type	Class D

SIMPLE SPAN REINFORCED CONCRETE SLAB BRIDGE
SINGLE SPAN @ 30'-0"
40'-0" CLEAR ROADWAY; SKEW: 45° LT.
SR 44 OVER BRANCH OF LITTLE BLUE CREEK
SHELBY COUNTY, INDIANA

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER 06/15/2026 DATE

DESIGNED: DS DRAWN: MHF
CHECKED: MJF CHECKED: MJF

INDIANA
DEPARTMENT OF TRANSPORTATION


GENERAL PLAN

SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS 12 of 29
CONTRACT
B-44483


Plot:5/28/2026 7:22:47 PM

File:H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_General Plan.dgn
Model:LINE C - Plan-1 [Sheet]



PLAN

Scale: 3/16" = 1'-0"



SECTION "B-B"

Scale: 3/8"= 1'-0"

BILL OF MATERIALS

SUPERSTRUCTURE

EPOXY COATED REINFORCING STEEL

Size or Mark	Number of Bars	Length (ft)	Weight (Lb)
701	77	23' -8"	
702	3	32' -7"	
703	3	33' -0"	
704	8	6' -0"	
705	40	25' -4"	
706	40	23' -4"	
707	147	12' -3"	
708	12	32' -10"	
#7	92	40' -0"	
#7	3	31' -4"	
#7	12	31' -2"	
#7	3	30' -11"	
#7	92	25' -0"	
#7	77	22' -0"	
Total #7			29,523
601	142	16' -4"	
602	142	4' -5"	
603	2	17' -4"	
604	2	4' -0"	
605	2	17' -0"	
606	2	5' -4"	
607	2	19' -10"	
608	1	21' -10"	
609	3	22' -4"	
610	1	8' -5"	
611	1	9' -11"	
612	2	7' -3"	
613	2	8' -9"	
614	19	7' -2"	
615	10	7' -2"	
616	10	7' -7"	
#6	94	11' -6"	
#6	38	6' -10"	
#6	38	6' -9"	
#6	38	6' -8"	
#6	39	6' -6"	
Total #6			8,844
501	288	4' -0"	
502	6	5' -0"	
503	4	4' -6"	
504	9	5' -3"	
505	6	13' -2"	
506	6	17' -2"	
507	12	9' -4"	
508	16	32' -11"	
509	38	15' -4"	
5701	73	5' -6"	
#5	30	40' -0"	
#5	2	28' -9"	
#5	13	25' -0"	
#5	15	23' -6"	
#5	6	3' -2"	
Total #5			5,222
TOTAL EPOXY COATED			43,589

BILL OF MATERIALS

SUPERSTRUCTURE (CONTINUED)

CONCRETE	
Concrete, C, Superstructure (Cys)	179.2
MISCELLANEOUS	
Pile, Steel Pipe, 14 in Dia. x 0.250 in. (Lft) 7 Piles @ 52 Lft (Bent No. 1) 7 Piles @ 52 Lft (Bent No. 2)	728
Test Pile, Dynamic, Production (Lft) 1 Pile @ 62 Lft (Bent No. 1) 1 Pile @ 62 Lft (Bent No. 2)	124
Test Pile, Dynamic, Restrike (Each) (Bent No. 1 & 2, 1 Each)	2
Dynamic Pile Load Test (Each)	2
Conical Pile Tip, 14 in.	16
Flowable Backfill, Removable (Cys)	82
Epoxy Coated Threaded Tie Bar Assemblies (Each)	43

NOTES:

1. All Reinforcing Bars Shall be Epoxy-Coated.
2. See INDOT Std. Dwg. E 703-BRST-01 for Bars Bending Details.
3. See Sheet 15 for Section "A-A" Details.
4. See Next Sheet for Section "C-C" Details.
5. See Sheet 16 for Section "D-D" Details.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 06/15/2026 DATE

DESIGNED: DS | DRAWN: MHF

CHECKED: SC | CHECKED: DS

INDIANA DEPARTMENT OF TRANSPORTATION

SUPERSTRUCTURE DETAILS


SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS: 13 of 29

CONTRACT: B-44483


Plot:5/28/2026 7:22:52 PM

File:H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Superstructure Details.dgn
Model:Slab Sht i



SECTION "C-C"

Scale: ⅜"= 1'-0"




NOTE:

* - Measured Perpendicular to Skew

LONGITUDINAL SECTION

Scale: ½" = 1'-0"



DEAD LOAD DEFLECTION DIAGRAM

Not to Scale

NOTES:

1. All Reinforcing Bars Shall be Epoxy-Coated.
2. See INDOT Std. Dwg. E 703-BRST-01 for Bars Bending Details.
3. See Previous Sheet for Plan.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL Michael J. Ficcaglia 06/15/2026
DESIGN ENGINEER DATE

DESIGNED: DS DRAWN: MHF
CHECKED: SC CHECKED: DS


INDIANA
DEPARTMENT OF TRANSPORTATION

SUPERSTRUCTURE DETAILS

SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652


SHEETS 14 of 29
CONTRACT B-44483

Plot: 5/28/2026 7:22:54 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Superstructure Details.dgn
Model: Slab Sht ii



PLAN

Scale: ¼"= 1'-0"




THIS HALF SHOWING BENT REINFORCING

THIS HALF SHOWING SLAB REINFORCING


SECTION "A-A"

Scale: ¼"= 1'-0"



WING TYPICAL SECTION


Scale: ½" = 1'-0"



WING A ELEVATION

Scale: ½" = 1'-0"

1. 70 - 601 & 707 Bars at 9" Max. Spa.
2. 70 - 602 Bars at 9" Max. Spa.
3. 140 - 501 Bars at 9" Max. Spa.



WING B ELEVATION

Scale: ½" = 1'-0"

NOTES:

1. All Reinforcing Bars Shall be Epoxy-Coated.
2. See INDOT Std. Dwg. E 703-BRST-01 for Bars Bending Details.
3. See Sheet 13 for Section Plan.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 06/15/2026 DATE

DESIGNED: MHF | DRAWN: MHF

CHECKED: SC | CHECKED: DS

INDIANA DEPARTMENT OF TRANSPORTATION

SUPERSTRUCTURE DETAILS BENT NO. 1


SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS 15 of 29

CONTRACT B-44483


Plot: 5/28/2026 7:22:55 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Superstructure Details.dgn
Model: Bent 1




PLAN

Scale: ¼"= 1'-0"



WING C ELEVATION

Scale: ½" = 1'-0"




THIS HALF SHOWING BENT REINFORCING

THIS HALF SHOWING SLAB REINFORCING

SECTION "D-D"

Scale: ¼"= 1'-0"



WING D ELEVATION

Scale: ½" = 1'-0"

NOTES:

1. All Reinforcing Bars Shall be Epoxy-Coated.
2. See INDOT Std. Dwg. E 703-BRST-01 for Bars Bending Details.
3. See Sheet 13 for Section Plan.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 06/15/2026 DATE

DESIGNED: MHF | DRAWN: MHF

CHECKED: SC | CHECKED: DS

INDIANA DEPARTMENT OF TRANSPORTATION

SUPERSTRUCTURE DETAILS BENT NO. 2


SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS: 16 of 29

CONTRACT: B-44483

Plot: 5/28/2026 7:22:56 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Superstructure Details.dgn
Model: Bent 2



501 x 4'-0"

502 x 5'-0"

505 x 13'-2"

503 x 4'-6"

504 x 5'-3"

506 x 17'-2"


507 x 9'-4"

5701 x 5'-6"



508 x 32'-11"

509 x 15'-4"



601 x 16'-4"

602 x 4'-5"

603 x 17'-4"


604 x 4'-0"

606 x 5'-4"

605 x 17'-0"

607x 19'-10"

608 x 21'-10"




609 x 22'-4"

610 x 8'-5"


611 x 9'-11"

612 x 7'-3"


613 x 8'-9"




614 x 7'-2"



615 x 7'-2"




616 x 7'-7"




END BENT DETAIL (BETWEEN WINGWALLS)


Scale: ½"= 1'-0"




704 x 6'-0"



705 x 25'-4"
20 Bars Cut 40



706 x 23'-4"
20 Bars Cut 40



707 x 12'-3"

708 x 32'-10"

BAR BENDING DETAILS

Not to Scale

NOTES:

1. All Reinforcing Bars Shall Be Epoxy-Coated.
2. See Standard Drawing E 703-BRST-01 for Reinforcing Bar Notes.

SJCA

MICHAEL J. FICCAGLIA
REGISTERED
No. PE11800778
STATE OF INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 06/15/2026 DATE

DESIGNED: MHF | DRAWN: MHF

CHECKED: SC | CHECKED: DS

INDIANA
DEPARTMENT OF TRANSPORTATION

SUPERSTRUCTURE DETAILS


SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS: 17 of 29

CONTRACT: B-44483


Plot: 5/28/2026 7:22:57 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Superstructure Details.dgn
Model: Misc Sht




RAILING PLAN

Scale: ¼" = 1'-0"




NORTH RAILING ELEVATION

Scale: ¼" = 1'-0"



SOUTH RAILING ELEVATION

Scale: ¼" = 1'-0"



RAILING TYPICAL SECTION

Scale: 1" = 1'-0"

BILL OF MATERIALS
BRIDGE RAILING
NORTH RAIL

Size or Mark	Number of Bars	Length (ft)	Weight (Lb)
5704	48	3' -0"	
#5	8	15' -2"	
Total #5			278
Total from Concrete Rail Transition Type TFC (551 lbs x 2)			1,102
TOTAL EPOXY COATED			1,380
CONCRETE			
Railing, Concrete Type FC (CYS)			1.6
MISCELLANEOUS			
Barrier Delineators (Each)			2
Concrete Rail Transition Type TFC (Each)			2
Surface Seal (300 SFT)			1 LSUM

BILL OF MATERIALS
BRIDGE RAILING
SOUTH RAIL

Size or Mark	Number of Bars	Length (ft)	Weight (Lb)
5704	98	3' -0"	
#5	8	31' -5"	
Total #5			570
Total from Concrete Rail Transition Type TFC (551 lbs x 2)			1,102
TOTAL EPOXY COATED			1,672
CONCRETE			
Railing, Concrete Type FC (CYS)			3.1
MISCELLANEOUS			
Barrier Delineators (Each)			2
Concrete Rail Transition Type TFC (Each)			2
Surface Seal (403 SFT)			1 LSUM

NOTES:

1. All Reinforcing Bars Shall Be Epoxy-Coated.
2. See Standard Drawing E 703-BRST-01 for Reinforcing Bar Notes.
3. See Standard Drawing E 609-RCBA-01, 03, and 04 for Additional Reinforced Concrete Bridge Approach Details.
4. See Standard Drawing E 706-BRSF-01 and 02 For Concrete Bridge Raling, Type FC Details.
5. See Standard Drawing E 706-TTFC-01 Through 03 for Concrete Bridge Railing Transition, Type TFC Details.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL Michael J. Ficcaglia 06/15/2026
DESIGN ENGINEER DATE

DESIGNED: MHF DRAWN: MHF
CHECKED: SC CHECKED: DS


INDIANA
DEPARTMENT OF TRANSPORTATION

RAILING DETAILS

SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652


SHEETS: 18 of 29
CONTRACT: B-44483

Plot: 5/28/2026 7:22:57 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Superstructure Details.dgn
Model: Railing Sht



PLAN - WEST APPROACH

Scale: $\frac{3}{16}$" = 1'-0"



PLAN - EAST APPROACH


Scale: $\frac{3}{16}$" = 1'-0"

BILL OF MATERIALS
REIN. CONC. BRIDGE APPROACH
WEST APPROACH

EPOXY COATED REINFORCING STEEL			
Size or Mark	Number of Bars	Length (ft)	Weight (Lb)
591	80	20' -7"	
#5	42	40' -0"	
#5	61	20' -0"	
#5	42	18' -3"	
#5	6	5' -0"	
Total #5			5,573
Reinf. Conc. Br. Appr. Ext., Type TFC (230 Lbs x 2)			460
TOTAL EPOXY COATED			6,033
MISCELLANEOUS			
Reinforced Concrete Bridge Approach, 12" (Sys)			98
Subbase for PCCP (Cys)			25
Geotextile for Pavement, Type 2B (Sys)			98

BILL OF MATERIALS
REIN. CONC. BRIDGE APPROACH
EAST APPROACH


EPOXY COATED REINFORCING STEEL			
Size or Mark	Number of Bars	Length (ft)	Weight (Lb)
591	80	20' -7"	
#5	42	40' -0"	
#5	61	20' -0"	
#5	42	18' -3"	
#5	6	5' -0"	
Total #5			5,573
Reinf. Conc. Br. Appr. Ext., Type TFC (230 Lbs x 1)			230
TOTAL EPOXY COATED			5,803
MISCELLANEOUS			
Reinforced Concrete Bridge Approach, 12" (Sys)			95
Subbase for PCCP (Cys)			24
Geotextile for Pavement, Type 2B (Sys)			95



591 x 20'-7"

BAR BENDING DETAILS

Not To Scale



SECTION E-E

Scale: ½" = 1'-0"

NOTES:

1. All Reinforcing Bars Shall Be Epoxy-Coated.
2. See Standard Drawing E 703-BRST-01 for Reinforcing Bar Notes.
3. See Standard Drawing E 609-RCBA-01, 03, and 04 for Additional Reinforced Concrete Bridge Approach Details.
4. See Standard Drawing E 609-TBAE-01, 02 and 03 For RCBA Extension Details.
5. See Standard Drawing E 609-BRJT-01 for Joint, Type I-A Details.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL Michael J. Ficcaglia 06/15/2026
DESIGN ENGINEER DATE

DESIGNED: MHF | DRAWN: MHF

CHECKED: SC | CHECKED: SC

INDIANA
DEPARTMENT OF TRANSPORTATION

REINFORCED CONCRETE BRIDGE
APPROACH DETAILS

SCALE	BRIDGE FILE
AS NOTED	044-73-10858
	DESIGNATION
	2200652

SHEETS: 19 of 29

CONTRACT: B-44483

Plot: 5/28/2026 7:23:04 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_RCBA.dgn
Model: RCBA

SUMMARY OF BRIDGE QUANTITIES

ITEM	CONCRETE			REINF. BARS	REINF. BARS, EPOXY COATED	STRUCTURAL STEEL	THREADED TIE BAR ASSEMBLIES, EPOXY COATED	RAILING, CONCRETE, TYPE FC	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	REINF. CONC. BRIDGE APPROACH. 12 IN.	SUBBASE FOR PCCP	GEOTEXTILE FOR PAVEMENT, TYPE 2B	FLOWABLE BACKFILL, REMOVABLE	CLASS 1 RIPRAP	REVETMENT RIPRAP	COMPACTED AGGREGATE NO. 53	GEOTEXTILE FOR RIPRAP, TYPE 1A	EXCAVATION, FOUNDATION, UNCLASSIFIED	PILES					BARRIER DELINEATOR	BENCHMARK POST	LONGITUDINAL GROOVING	SURFACE SEAL **
	CLASS C	CLASS A	CLASS B																PILE, STEEL PIPE, 0.250 IN., DIAMETER 14 IN.	TEST PILE, DYNAMIC, PRODUCTION	TEST PILE, DYNAMIC, RESTRIKE	DYNAMIC PILE LOAD TEST	CONICAL PILE TIP, 14 IN.				
	SUPERSTR	SUBSTR	IN FTG.																								
	CYS	CYS	CYS	LBS	LBS	LBS	EACH	CYS	EACH	SYS	CYS	SYS	CYS	TONS	TONS	TON	SYS	CYS	LFT	LFT	EACH	EACH	EACH	EACH	EACH	SYS	SFT
SUPERSTRUCTURE	86.4				43589		43																			142	
BENT NO. 1	44.7												40	155		3	202	119	364	62	1	1	8		1		304
BENT NO. 2	48.1												42	151	84	3	344	124	364	62	1	1	8				328
RAILING - NORTH					1380			1.6	2															2			300
RAILING - SOUTH					1672			3.1	2															2			403
REINF. CONC. APPROACH SLAB - WEST					6033					98	25	98														92	
REINF. CONC. APPROACH SLAB - EAST					5803					95	24	95														92	
TOTALS	**179.2**				**58477**		**43**	**4.7**	**4**	**193**	**49**	**193**	**82**	**306**	**84**	**6**	**546**	**243**	**728**	**124**	**2**	**2**	**16**	**4**	**1**	**326**	**1335**

** Estimated quantity

PAVEMENT QUANTITIES AND APPROACH TABLE

LOCATION	DESCRIPTION (APPROACH TYPE OR CLASS)	WIDTH	LENGTH	RADII	DISTANCE BEYOND R/W LINE	SURFACE BEYOND R/W LINE			GRADE				EXCAVATION		HMA MATERIALS			HMA FOR APPR.		MILLING, ASPHALT, 1 1/2 IN.	SUBGRADE TREATMENT, TYPE II	SUBGRADE TREATMENT, TYPE IC	GEOGRID, TYPE IB	JOINT ADHESIVE		LIQUID ASPHALT SEALANT	SEAL COAT TYPE 5	HMA MATERIAL FOR:		COMPACTED AGGREGATE NO. 53		REMARKS
						COMPACTED AGGREGATE BASE	HMA	CONCRETE							QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	HMA, SURFACE, TYPE B	HMA, INTERMEDIATE, TYPE B						SURFACE	INTERMEDIATE			PRIME COAT	TACK COAT	DEPTH		
									1	2	3	4	CUT	FILL	LBS. PER SYD.																		
		FT	FT	FT	FT	SYS	SYS	SYS	%	%	%	%	CYS	CYS	TON	TON	TON	TON	TON	SYS	SYS	SYS	SYS	LFT	LFT	LFT	SYS	SYS	SYS	TON	TON	
LINE "PR-PR"																																
505+10.00 to 506+00.00													71	8	21	21	66			107		169	169	180	120				539		56	
506+00.00 to 507+38.56													186	63	52	88	284					688	688	416	416				1898		118	
508+11.44 to 508+50.00													99	19	16	26	80					192	192	116	116				529		23	
508+15.44	Class II	10.2'	52.3'	25', 15'	8.4'		10		2.00	0.20			15	15				9	13		78								152	25		
508+50.00 to 509+92.00													164	46	45	45	143			222		367	367	375	250				1172		90	
TOTALS													**535**	**151**	**134**	**180**	**573**	**9**	**13**	**329**	**78**	**1416**	**1416**	**1087**	**902**				**4290**	**25**	**287**	

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL Michael J. Ficcaglia 06/15/2026
DESIGN ENGINEER DATE

DESIGNED: DSR DRAWN: DSR
CHECKED: MJF CHECKED: MJF

INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE SUMMARY

SCALE	BRIDGE FILE
N/A	044-73-10858
	DESIGNATION
	2200652

SHEETS: 20 of 29
CONTRACT: B-44483

Plot: 5/28/2026 7:23:08 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Summary.dgn
Model: Bridge Summary

STRUCTURE DATA

STRUCTURE NUMBER	LOCATION					SIZE	DESCRIPTION		LENGTH	VIDEO INSPECTION LENGTH	SKEW	FLOW LINE			SERVICE LIFE	SITE DESIGNATION	pH	BACKFILL METHOD	STRUCTURE BACKFILL	TYPE	FLOWABLE BACKFILL	TYPE	BORROW	GEOTEXTILES	REVETMENT RIPRAP	SCOUR PROTECTION				CONCRETE, CLASS A, FOR STR.	VIDEO INSPECTION	PIPE END SECTION	GRATED BOX END SECTION			SAFETY METAL END SECTION			CONNECT TO STR.	REMARKS
	STATION	LEFT	RIGHT	CROSS	OFFSET		PIPE TYPE	MANHOLE, INLET, CATCH BASIN, OR SPECIALTY STRUCTURE				COVER	UP STREAM	DOWN STREAM												SUMP DEPTH	GEOTEXTILE	RIPRAP													
					FT	IN.			LFT	LFT		LFT	ELEV.	ELEV.	YRS				CYS		CYS		CYS	SYS	TON	IN.	SYS.	TYPE	TONS	CYS	LFT	EA.	TYPE	SLOPE	EA.	TYPE	SLOPE	EA.		
11	508+50.00	X			38.2	24"	3	PIPE	58			1.6	873.68	872.17	50	N	7.2	2	9	2			15								1				1	4:1	1		
	TOTALS																		**9**				**15**								**1**					**1**		

GUARDRAIL TABLE

LOCATION				W-BEAM GUARDRAIL	CONCRETE RAILING, TYPE FC *	GUARDRAIL, TRANSITION, TYPE MGS W/O CURB	GUARDRAIL, TRANSITION, TYPE TGB	GUARDRAIL, END TREATMENT, TYPE OS	CURVED W-BEAM GUARDRAIL SYSTEM		GUARDRAIL REMOVE	REMARKS
FROM STATION	TO STATION	LEFT	RIGHT	GUARDRAIL MGS W-BEAM, 6 FT, 3 IN. SPACING					TERMINAL SYSTEM			
				LFT	LFT	EACH	EACH	EACH	TYPE	EACH	LFT	
LINE "PR-PR"												
505+85.87	506+35.87		X					1				
506+35.87	507+23.37		X	87.5							143	
507+23.37	507+63.99		X			1						
507+63.99	508+26.00		X		15.6							
508+26.00	508+66.36		X			1					143	
508+66.36	509+16.63		X					1				
506+33.37	506+83.37	X						1				
506+83.37	507+23.99	X				1					143	
507+23.99	507+69.74	X			31.8							
507+69.74	507+94.74	X					1				132	
507+94.74	508+09.49	X							1	1		
TOTALS				**87.5**	**47.4***	**3**	**1**	**3**		**1**	**561**	

* - For information only; quantity included in bridge summary

MONUMENT AND R/W MARKER TABLE

STATION	OFFSET	MONUMENT					R/W MARKER
		A	B	C	D	SECTION CORNER	
LINE "PR-PR"							
506+00.00	0.00		1				
508+50.00	0.00		1				
LINE "C"							
405+03.00	40.00' RT						1
405+37.00	45.00' LT						1
405+86.66	45.00' LT						1
405+88.00	55.00' RT						1
406+53.83	55.00' RT						1
407+06.46	45.00' LT						1
407+60.00	45.00' LT						1
407+60.00	65.00' LT						1
408+08.00	55.00' RT						1
408+32.93	65.00' LT						1
409+85.00	40.00' LT						1
410+03.00	41.00' RT						1
TOTALS			**2**				**12**

SHEET SIGN & POST SUMMARY

SIGN					
PLAN SHEET NO. / LINE	SIGN LOCATION (STA.)	SIGN CODE	SIGN SIZE (IN. X IN.)	SIGN, SHEET, REMOVE	REFERENCE POST
				EACH	EACH
Line "PR-PR"					
	507+62.00	"44"			1
		"+27"			
	507+84.00			1	
			Total	1	1

MAILBOX APPROACHES

C/L BOX STATION	LT./RT.	DESCRIPTION	WIDTH "W" (FT.)	ASSEMBLY RESET		
				SINGLE	DOUBLE	
507+91.00 "PR-PR"	LT.	Paved Shoulder, Mailbox Beyond Drive	0		1	
TOTALS					1	

RIPRAP DITCH AND SODDING SUMMARY TABLE

LOCATION					RIPRAP DITCH		SODDING
FROM STATION	TO STATION	LEFT	MEDIAN	RIGHT	REVETMENT RIPRAP	GEOTEXTILES FOR RIPRAP TYPE 1A	FOR TURNOUT
					TONS	SYS	SYS
LINE "PR-PR"							
508+32.78	508+36.78			X			11
508+50.00	508+85.00	X			31	52	
TOTALS					**31**	**52**	**11**

PAVEMENT MARKINGS SUMMARY OF QUANTITIES

LOCATION					LINE, MULTI-COMPONENT	
FROM STATION	TO STATION	LEFT	MEDIAN	RIGHT	SOLID	BROKEN
					WHITE	YELLOW
					6 in	6 in
					LFT	LFT
LINE "PR-PR"						
505+40.00	509+75.00	X			435	
505+40.00	509+75.00		X			109
505+40.00	509+75.00			X	435	
TOTAL					**870**	**109**

	STRUCTURE NUMBER		
	11		
PIPE TYPE / SHAPE	3		
SMOOTH PIPE SIZE	24"		
CORRUGATED PIPE SIZE	24"		
RCP/RCHEP (S) CLASS II $D_{0.01}$ RATING = 1000	Y		
REINFORCED CONCRETE CIRCULAR PIPE (S)	Y		
NON-REINFORCED CONCRETE PIPE, CLASS 3 (S)	Y		
CORRUGATED PE PIPE, TYPE S (S)*	Y		
CORRUGATED PP PIPE (S)	Y		
RIBBED PE PIPE (S)*			
SMOOTH WALL PE PIPE (S)* / MAXIMUM DR = 26			
PROFILE WALL PVC PIPE (S)	Y		
SMOOTH WALL PVC PIPE (S)*			
VITRIFIED CLAY PIPE, EXTRA STRENGTH (S)	Y		
CORRUGATED STEEL PIPE / PIPE-ARCH: FULLY BIT. PAVED & LINED (S)	CORR. PROFILE		
	THICKNESS		
ZINC COATED (C)	CORR. PROFILE	2 2/3" X 1/2"	
	THICKNESS	0.109"	
ZINC COATED W/ BPI (C)	CORR. PROFILE	2 2/3" X 1/2"	
	THICKNESS	0.064"	
ALUM. COATED TYPE 2 (C)	CORR. PROFILE	2 2/3" X 1/2"	
	THICKNESS	0.064"	
ALUM. COATED TYPE 2 W/ BPI (C)	CORR. PROFILE		
	THICKNESS		
POLYMER PRECOATED GALVANIZED (C)	CORR. PROFILE		
	THICKNESS		
POLYMER PRECOATED GALVANIZED W/ BPI (C)	CORR. PROFILE		
	THICKNESS		
POLYMER PRECOATED GALVANIZED CORRUGATED	CORR. PROFILE	2 2/3" X 1/2"	
	THICKNESS	0.064"	
FIBER BONDED BITUMINOUS COATED (C)	CORR. PROFILE		
	THICKNESS		
FIBER BONDED BITUMINOUS COATED W/ BPI (C)	CORR. PROFILE		
	THICKNESS		
CORRUGATED ALUM. ALLOY PIPE (C)	CORR. PROFILE	2 2/3" X 1/2"	
	THICKNESS	0.060"	
CORRUGATED ALUM. ALLOY PIPE W/ BPI (C)	CORR. PROFILE		
	THICKNESS		
STR. PLATE ALUMINUM ALLOY PLATE (C)	CORR. PROFILE		
	THICKNESS		
STR. PLATE ALUMINUM ALLOY PLATE W/ CFP (C)	CORR. PROFILE		
	THICKNESS		
STR. PLATE STEEL PIPE (C)	CORR. PROFILE		
	THICKNESS **		
STR. PLATE STEEL PIPE W/ CFP (C)	CORR. PROFILE		
	THICKNESS **		

LEGEND

RCP-	Reinforced Concrete Pipe
RCHEP-	Reinforced Concrete Horizontal Elliptical Pipe
PE-	Polyethylene
DR-	Dimension Ratio
PVC-	Polyvinyl Chloride
BIT-	Bituminous
CORR-	Corrugation
PP-	Polypropylene
BPI-	Bituminous Paved Invert
ALUM-	Aluminum
STR-	Structural
CFP-	Concrete Field Paving
CIR-	Circular Pipe
DEF-	Deformed Pipe
(S)-	Smooth Pipe Material
(C)-	Corrugated Pipe Material
OK-	Acceptable for Use
(LS)-	Lock Seam Pipe Required
*-	Refer to Standard Drawings 715-PHCL-18 and -19 for nominal diameter appropriate for pay item diameter.
**-	Tabulated thickness refers to top and side plates. Bottom plates shall be of next greater available thickness.

SJCA

MICHAEL J. FICCAGLIA REGISTERED No. PE11800778 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER 06/15/2026 DATE

DESIGNED: DSR DRAWN: DSR

CHECKED: MJF CHECKED: MJF

INDIANA
DEPARTMENT OF TRANSPORTATION

MISCELLANEOUS TABLES


SCALE	BRIDGE FILE
N/A	044-73-10858
	DESIGNATION
	2200652

SHEETS: 21 of 29

CONTRACT: B-44483


Plot: 5/28/2026 7:23:10 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_Summary.dgn
Model: Misc Tables




505+40.00

Begin Incidental Construction
Sta. 505+40.00 "PR-PR"




505+35.00



505+10.00

Begin Incidental Construction
for Aggregate Shoulder
Sta. 505+10.00 "PR-PR"



505+00.00

SJCA

RECOMMENDED FOR APPROVAL
DESIGN ENGINEER DATE

DESIGNED: MHF
DRAWN: MHF
CHECKED: DS
CHECKED: DS


INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS
LINE "PR-PR"


HORIZONTAL SCALE	BRIDGE FILE
1" = 5'	044-73-10858
VERTICAL SCALE	DESIGNATION
1" = 5'	2200652

SHEETS		
22	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:23:27 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_XS.dgn
Model: PR-PR - 505+00.00 [Sheet]




506+50.00




506+00.00

BEGIN PROJECT
STA. 506+00.00 "PR-PR"



505+99.00



505+50.00

SJCA

RECOMMENDED FOR APPROVAL
DESIGN ENGINEER DATE

DESIGNED: MHF
DRAWN: MHF
CHECKED: DS
CHECKED: DS


INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS
LINE "PR-PR"


HORIZONTAL SCALE	BRIDGE FILE
1" = 5'	044-73-10858
VERTICAL SCALE	DESIGNATION
1" = 5'	2200652

SHEETS		
23	of	29
CONTRACT		
B-44483		


Plot: 5/28/2026 7:23:29 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_XS.dgn
Model: PR-PR - 505+50.00 [Sheet]



507+38.56



507+17.79



507+00.00

SJCA

RECOMMENDED FOR APPROVAL

DESIGN ENGINEER DATE

DESIGNED: MHF DRAWN: MHF

CHECKED: DS CHECKED: DS

INDIANA
DEPARTMENT OF TRANSPORTATION


CROSS SECTIONS
LINE "PR-PR"

HORIZONTAL SCALE	BRIDGE FILE
1" = 5'	044-73-10858
VERTICAL SCALE	DESIGNATION
1" = 5'	2200652


SHEETS		
24	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:23:31 PM


File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_XS.dgn
Model: PR-PR - 507+00.00 [Sheet]



507+90.94



507+59.06



507+50.00

SJCA

RECOMMENDED FOR APPROVAL

DESIGN ENGINEER DATE

DESIGNED: MHF DRAWN: MHF

CHECKED: DS CHECKED: DS

INDIANA
DEPARTMENT OF TRANSPORTATION


CROSS SECTIONS
LINE "PR-PR"

HORIZONTAL SCALE	BRIDGE FILE
1" = 5'	044-73-10858
VERTICAL SCALE	DESIGNATION
1" = 5'	2200652


SHEETS		
25	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:23:34 PM


File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_XS.dgn
Model: PR-PR - 507+50.00 [Sheet]



508+15.34



508+11.44



508+00.00

SJCA

RECOMMENDED FOR APPROVAL

DESIGN ENGINEER DATE

DESIGNED: MHF DRAWN: MHF

CHECKED: DS CHECKED: DS

INDIANA
DEPARTMENT OF TRANSPORTATION


CROSS SECTIONS
LINE "PR-PR"

HORIZONTAL SCALE	BRIDGE FILE
1" = 5'	044-73-10858
VERTICAL SCALE	DESIGNATION
1" = 5'	2200652


SHEETS		
26	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:23:35 PM

File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_XS.dgn
Model: PR-PR - 508+00.00 [Sheet]




508+51.00



508+50.00

END PROJECT
STA. 508+50.00 "PR-PR"



508+32.21

SJCA

RECOMMENDED FOR APPROVAL
DESIGN ENGINEER DATE

DESIGNED: MHF
DRAWN: MHF
CHECKED: DS
CHECKED: DS


INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS
LINE "PR-PR"

HORIZONTAL SCALE	BRIDGE FILE
1" = 5'	044-73-10858
VERTICAL SCALE	DESIGNATION
1" = 5'	2200652


SHEETS		
27	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:23:37 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_XS.dgn
Model: PR-PR - 508+32.21 [Sheet]




509+75.00

End Incidental Construction
Sta. 509+75.00 "PR-PR"



509+50.00



509+00.00

SJCA

RECOMMENDED FOR APPROVAL
DESIGN ENGINEER DATE

DESIGNED: MHF
DRAWN: MHF
CHECKED: DS
CHECKED: DS


INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS
LINE "PR-PR"


HORIZONTAL SCALE	BRIDGE FILE
1" = 5'	044-73-10858
VERTICAL SCALE	DESIGNATION
1" = 5'	2200652

SHEETS		
28	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:23:39 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_XS.dgn
Model: PR-PR - 509+00.00 [Sheet]




510+00.00



509+92.00

End Incidental Construction
for Aggregate Shoulder
Sta. 509+92.00 "PR-PR"



509+80.00

SJCA

RECOMMENDED FOR APPROVAL
DESIGN ENGINEER DATE

DESIGNED: MHF
DRAWN: MHF
CHECKED: DS
CHECKED: DS

INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS
LINE "PR-PR"

HORIZONTAL SCALE	BRIDGE FILE
1" = 5'	044-73-10858
VERTICAL SCALE	DESIGNATION
1" = 5'	2200652

SHEETS		
29	of	29
CONTRACT		
B-44483		

Plot: 5/28/2026 7:23:41 PM
File: H:\Projects\2024\Engineering\24EN017_SR_44_REPLACEMENT_DES_2200652_SJCA\EN\CAD\Sheets\24EN017_XS.dgn
Model: PR-PR - 509+80.00 [Sheet]