DESIGNATION	
2200957	
CONTRACT	BRIDGE FILE
B-44532	224-90-01545 B

INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE PREVENTIVE MAINTENANCE PLANS

FOR SPANS OVER 20 FEET


ROUTE: US 224 AT: RP 24+49

DESIGNATION NO. 2200957

STRUCTURE INFORMATION				
STRUCTURE	TYPE	SPAN AND SKEW	OVER	STATION
224-90-01545 B	Spread Prestressed Concrete Box Beam	Single Span: 41'-0" Skew: 30° Lt.	Eight Mile Creek	Sta. 703+55.00 Line "A"


KIN PROJECT INFORMATION	
DESIGNATION	PROJECT DESCRIPTION
2200946 (LEAD)	BRIDGE DECK OVERLAY ON SR 1 OVER WABASH RIVER
2200957	BRIDGE DECK OVERLAY ON US 224 OVER EIGHT MILE CREEK
2200542	BRIDGE DECK OVERLAY ON SR 1 OVER SIX MILE CREEK

Bridge Deck Overlay on US 224 over Eight Mile Creek
Located 0.51 Miles East of SR 301
Sections 5 and 32, T-27-N and T-28-N, R-13-E, Jefferson and Lancaster Townships, Wells County, Indiana



TRAFFIC DATA		
A.A.D.T.	(2027)	2,431 V.P.D.
A.A.D.T.	(2047)	2,451 V.P.D.
D.H.V.	(2047)	227 V.P.H.
DIRECTIONAL DISTRIBUTION		50 %
TRUCKS		16 % A.A.D.T.
		16 % D.H.V.

DESIGN DATA	
DESIGN SPEED	55 M.P.H.
PROJECT DESIGN CRITERIA	3R (NON-FREEWAY)
FUNCTIONAL CLASSIFICATION	MINOR ARTERIAL
RURAL/URBAN	RURAL
TERRAIN	LEVEL
ACCESS CONTROL	NONE



PROJECT LOCATION SHOWN BY
Wells County

LATITUDE: 40°49'51" N LONGITUDE: 85°04'53" W

BRIDGE LENGTH:	0.009	MI.
ROADWAY LENGTH:	0.016	MI.
TOTAL LENGTH:	0.025	MI.
MAX. GRADE:	0.20	%

HUC: 051201010901

Plans Prepared By:

fishbeck
Engineers | Architects | Scientists | Constructors

SCALE: 1" = 1000'

INDIANA DEPARTMENT OF TRANSPORTATION
STANDARD SPECIFICATIONS DATED 2026
TO BE USED WITH THESE PLANS.

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

PLANS PREPARED BY: FISHBECK (317) 577-9050 PHONE NUMBER

CERTIFIED BY: 4/9/2026 DATE

APPROVED FOR LETTING: Stephanie J. Wagner 09/03/2026 DATE
INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE FILE
224-90-01545 B
DESIGNATION
2200957
SHEETS
1 of 17
CONTRACT
B-44532

Plot: 8/11/2022
File: BR_Title Sheet.dgn
Model:BR_Title Sheet

UTILITIES

Electric:
Heartland REMC
350 Wedcor Ave
Wabash, IN 46992
Attn: Eric Wilson
Phone: 260-758-3652
Email: ewilson@heartlandremc.com

Communications:
Brightspeed
1401 W Center Street
Warsaw, IN 46580
Attn: Melissa Teague
Phone: 765-656-4663
Email: melissa.teague1@brightspeed.com

Cable:
Mediacom
532 Fairview Blvd
Kendallville, IN 46755
Attn: Victor Gregory
Phone: 845-395-6004
Email: victor.gregory@mediacomcc.com

Gas:
NIPSCO
1501 Hale Ave
Fort Wayne, IN 46802
Attn: Vanessa Chimitt
Phone: 260-298-8472
Email: vrivera@nisource.com

811 Know what's below. Call before you dig.

INDIANA UNDERGROUND
1-800-382-5544 OR CALL 811
24 HOURS A DAY 7 DAYS A WEEK

REVISIONS

SHEET NO.	DATE	REVISED

INDEX

SHEET NO.	SUBJECT
1	TITLE SHEET
2	INDEX
3	TYPICAL SECTIONS
4	PLAT NO. 1
5	MAINTENANCE OF TRAFFIC
6	APPROACH CONSTRUCTION DETAILS
7	EROSION CONTROL
8-9	GENERAL PLAN
10	REMOVAL DETAILS
11	SUPERSTRUCTURE DETAILS
12	RAILING DETAILS
13-15	APPROACH SLAB DETAILS
16	BRIDGE SUMMARY
17	ROAD SUMMARY

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: CPM 4/9/2026 | DRAWN: CPM 4/9/2026


CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

INDEX

SCALE	BRIDGE FILE
NONE	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	2 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026
File: BR_Index_Sheet.dgn
Model: BR_Index Sheet




HALF SECTION SHOWING PROPOSED GUARDRAIL

HALF SECTION SHOWING EXISTING GUARDRAIL

TYPICAL SECTION - FULL DEPTH HMA

Scale 1' = 5'




HALF SECTION SHOWING PROPOSED GUARDRAIL

HALF SECTION SHOWING EXISTING GUARDRAIL

TYPICAL SECTION - HMA WEDGE

Scale 1' = 5'



SAFETY EDGE DETAIL

Not to Scale

LEGEND

- (K) 165 lbs/syd QC/QA-HMA, 3, 58S, Surface, 9.5 mm on 275 lbs/syd QC/QA-HMA, 3, 58S, Intermediate, 19.0 mm on 660 lbs/syd QC/QA-HMA, 3, 58S, Base, 25.0 mm on Subgrade Treatment, Type IC on Geotextile for Pavement, Type 2B
- (JZ) 10 in. Compacted Aggregate, No. 53
- (R) Asphalt Material for Wedge 165 lbs/syd QC/QA-HMA, 3, 58S, Surface, 9.5 mm on Milling, Transition
- (29) Linear Grading
- (30) Mulched Seeding R
- (62) MGS W-Beam Guardrail
- (63) 6 in. Broken Yellow Paint Line
- (64) 6 in. Solid White Paint Line

NOTES

1. See sheet 6 for limits of full depth HMA and HMA wedge sections.

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: CPM 4/9/2026 | DRAWN: CPM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA DEPARTMENT OF TRANSPORTATION

TYPICAL SECTIONS

SCALE	BRIDGE FILE
AS NOTED	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	3 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026

File:

Model:Sheet

701+00 | 702+00 | 703+00 | 704+00 | 705+00 | 706+00

SECTION 32, T-28-N, R-13-E
JEFFERSON TOWNSHIP, WELLS COUNTY

W David D. Horne & Kathryn J. Horne

Michael D. Barger,
as Trustee of the
Truman D. Barger Trust

℄ Structure
Sta. 703+55.00 Line "A"
Skew: 30° Lt.

R/W
Const. Limits
R/W
Const. Limits
R/W

App. Ex. R/W
Begin Project
Sta. 702+89.28 Line "A"
Monument Type B Required
End Project
Sta. 704+20.72 Line "A"
Monument Type B Required
App. Ex. R/W
End Incidental Construction
Sta. 705+48.00 Line "A"

Line "A"
Begin Incidental Construction
Sta. 701+55.00 Line "A"
U.S. 224
Section & Township Line
Bearing = N 88° 27' 07" E

App. Ex. R/W
App. Ex. R/W

R/W
Const. Limits
R/W
R/W

GRS Holdings, LLC

App. Ex. R/W
App. Ex. R/W
Eight Mile Creek

Michael D. Barger,
as Trustee of the
Truman D. Barger Trust

SECTION 5, T-27-N, R-13-E
LANCASTER TOWNSHIP, WELLS COUNTY

NOTES:

1. All R/W, existing topography, offsets, and stationing described from Line "A" unless otherwise noted.
2. Line "A" to be constructed.

Plot: 4/9/2026
File:
Model:BR_Layout

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER


RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: CPM 4/9/2026 | DRAWN: CPM 4/9/2026
CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION


PLAT NO. 1

SCALE	BRIDGE FILE
1" = 20'	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	4 of 17
	CONTRACT
	B-44532




XW20-3 (1) | XW20-2 (2) | XW20-3 (18) | XW20-3 (19) | XG20-5 (Place 14 days prior to closure. Remove when road is closed and detour signs are in place.) (20)

CONSTRUCTION SIGNS




XM4-8 M3-4 M1-4 M6-3 (3) | XM4-8 M3-4 M1-4 M5-1 (R) (4) | XM4-8 M3-4 M1-4 M6-1 (R) (5) | XM4-8a M3-4 M1-4 M6-1 (L) (6) | XM4-8 M3-4 M1-4 M5-1 (L) (21) | XM4-8 M3-4 M1-4 M6-1 (L) (22)




XM4-8 M3-2 M1-4 M6-3 (7) | XM4-8 M3-2 M1-4 M5-1 (R) (8) | XM4-8 M3-2 M1-4 M6-1 (R) (9) | XM4-8 M3-2 M1-4 M5-1 (L) (10) | XM4-8 M3-2 M1-4 M6-1 (L) (11) | XM4-8a M3-2 M1-4 M6-1 (R) (12)

DETOUR ROUTE MARKER ASSEMBLIES




R11-3b XM4-10 (R) (13) | R11-3b (14) | Black on Orange 48 X 48 Mount on Trailing Barricade (15) | R11-2 (16) | R11-3b XM4-10 (L) (17)

ROAD CLOSURE SIGNS



DETOUR PLAN

Scale: 1" = 5000'



DETAIL A

Not to Scale

NOTES

1. See INDOT Standard Drawings E 801-TCDT-01 and E 801-TCDT-04 for additional detour details.
2. Access to all drives shall be maintained during construction.
3. Traffic control devices shall be in accordance with INDOT Standard Specifications, Standard Drawings, and the Indiana Manual of Uniform Traffic Control Devices.
4. If temporary pavement markings are needed, only removable tape pavement markings will be allowed for temporary MOT on bridge deck and bridge approach wearing surfaces. Permanent markings will only be allowed once the final wearing surface is placed on the deck and approach slabs. No grinding, blasting, nor any other harsh removal method shall be allowed on the final wearing surfaces. Any damages sustained by the final wearing surfaces before project acceptance will be removed and replaced at the contractor expense.

MOT SUMMARY TABLE		
DESCRIPTION	UNIT	QUANTITY
DETOUR ROUTE MARKER ASSEMBLY	EACH	36
CONSTRUCTION SIGN, A	EACH	14
ROAD CLOSURE SIGN ASSEMBLY	EACH	8
BARRICADE, III-A	LFT	80
BARRICADE, III-B	LFT	220

LEGEND

- — — - Detour Route
- ▨ - Work Zone
- ⊤ - Sign
- ≡ - Type III Barricade

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: CPM 4/9/2026 | DRAWN: CPM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026


INDIANA DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC

SCALE	BRIDGE FILE
AS NOTED	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	5 of 17
	CONTRACT
	B-44532


Plot: 4/9/2026

File: BR_MOT Sheet.dgn
Model:RD_Index Sheet



PLAN

Scale 1' = 15'



HMA APPROACH DETAIL

Scale: Not To Scale

REFERENCE TIES

SECTION 5, T-27-N, R-13-E
LANCASTER TOWNSHIP, WELLS COUNTY

10000
Type of Marker: Rebar
Northing: 220477.42
Easting: 834444.19
Sta. 707+57.44, 36.17' Lt.

10001
Type of Marker: Mag Nail
Northing: 220451.70
Easting: 834107.64
Sta. 704+20.31, 19.55' Lt.

10002
Type of Marker: Rebar
Northing: 220396.76
Easting: 833660.21
Sta. 699+71.56, 23.29' Rt.

BENCHMARK INFORMATION

TBM #1 - Mag Nail in Pavement
Sta. 707+51.80, 14.40' Lt.
El. 830.23

TBM #2 - Cut "X" in NE Corner of Headwall Footer
Sta. 704+03.70, 20.62' Rt.
El. 831.02

TBM #3 - Mag Nail in Pavement
Sta. 699+85.02, 17.34' Lt.
El. 831.89

NOTES:

1. All R/W, exisiting topography, offsets, and stationing described from Line "A" unless otherwise noted.
2. Line "A" to be constructed.
3. For drive details see Standard Drawing E 610-DRIV-03.

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: CPM 4/9/2026 | DRAWN: CPM 4/9/2026


CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA DEPARTMENT OF TRANSPORTATION

APPROACH CONSTRUCTION DETAILS

SCALE	BRIDGE FILE
AS NOTED	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	6 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026
File:
Model:Sheet



EROSION CONTROL PLAN

NOTES

1. Disturbed areas shall be restored with Mulch Seeding, R.
2. Temporary Seeding shall take place on all disturbed areas that expected to be inactive for more than seven days.

TEMPORARY EROSION CONTROL TABLE

LOCATION					FILTER SOCK	SEDIMENT, REMOVE
FROM STATION	TO STATION	LEFT	MEDIAN	RIGHT	LFT	CYS
701+79	705+43	X			340	3.4
701+79	705+43			X	300	3.0
TOTALS					640	7

ADAM MONCZNIK
REGISTERED
No.11700255
STATE OF
INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: DLC 4/9/2026 | DRAWN: DLC 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026


INDIANA
DEPARTMENT OF TRANSPORTATION

EROSION CONTROL

SCALE	BRIDGE FILE
1" = 20'	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	7 of 17
	CONTRACT
	B-44532


Plot: 4/9/2026

File:
Model:BR_Erosion Control




RIPRAP DRAINAGE TURNOUT TYPICAL SECTION

Not to Scale



RIPRAP DRAINAGE TURNOUT TOE OF SLOPE DETAIL

Not to Scale



SPAN A

ELEVATION

Scale 1" = 15'

HYDRAULIC DATA


Drainage Area	7.40	sq mi
Design Discharge, Q100	1,430	cfs
Q100 Elevation	828.24	ft
Low Structure Elev.	829.08	ft

HYDRAULIC SCOUR DATA

Q100 Contraction Scour	12.48	ft
Q100 Total Scour	12.48	ft
Flowline Elevation	817.00	ft
Q100 Low Scour Elevation	804.52	ft
Q100 Max. Velocity	6.29	ft/s
Q100 Avg. Velocity	5.01	ft/s

GENERAL NOTES

1. Plans for the existing structure are on file at the INDOT Central Office under bridge file 224-90-01545 A.
2. Stations, elevations, and existing bridge details shown are based on existing plans and are for reference only.
3. No additional construction joints (including logitudinal construction joints) shall be added without the approval of the INDOT Fort Wayne District Bridge Asset Engineer.
4. When patching concrete, the minimum depth of the reinforcing steel cover will be 2 inches and shall not extend beyond the neat lines of the original surface. The final surface will meet the original neat line of the surface to be patched. If 2 inches of cover over the reinforcing steel cannot be achieved without extending beyond the original neat lines, less cover will be allowed if approved by the Engineer.
5. The boundaries of all removal areas shall be saw cut. All saw cuts shall be a minimum of 1" deep.
6. Where new work is to be fitted to old work, the Contractor shall verify all dimensions and conditions in the field and report any errors or discrepancies to the Engineer and assume responsibility for the correctness and the fit of the new part to the existing.
7. Chamfer exposed concrete edges 1" unless otherwise noted.
8. Raised pavement markers shall not be placed on the bridge deck or approach slab wearing surfaces.



PLAN

Scale 1' = 15'

MATERIAL NOTES

Bridge Deck Overlay: 2" (Min.) Latex Modified Portland Cement Concrete
OR
2" (Min.) Silica Fume Modified Structural Concrete

DESIGN DATA

LIVE LOAD

Original structure designed for HS20-44 loading with impact and distribution loads in accordance with the 1977 AASHTO Specifications and Interim Specifications.

DEAD LOAD

Original structure designed for actual loads plus an additional 35 psf future wearing surface. Deck slab designed for a 6½" structural depth.

DESIGN STRENGTH

CONCRETE

Class C	f'c = 4,000 psi
Class B	f'c = 3,000 psi
Class A	f'c = 3,500 psi

REINFORCING STEEL

Grade 60 f'c = 60,000 psi

BRIDGE MAINTENANCE KEY

1. Mill the existing deck a depth of 1/2" and remove unsound concrete using hydrodemolition. Construct full depth patches at locations determined by the engineer (Est. Qty. = 50 Sq. Ft.). Full depth patching will be performed in accordance with Spec. 722.06 and 722.07. Where deck concrete is removed for more than half of its original depth, the remaining concrete will be removed and full depth patching performed in accordance with Spec. 722.06 and 722.07. Install a concrete overlay with a minimum depth of 2".
2. Remove exisiting approach slabs and install new RCBA on Lean Concrete Base on Geotextiles for Pavement, Type 2B per Std. Dwg. E 609-RCBA.
3. Remove 10' of existing approach pavement and replace with full depth HMA pavement. See Approach Construction Details.
4. Mill 110' of approach pavement and overlay with HMA. See Approach Construction Details.
5. Remove existing approach guardrail and install MGS bridge transition assembly and MGS approach guardrail. See Approach Construction Details.
6. Remove and reconstruct portions of the existing mudwalls. Remove existing BS joints and replace with type PCF joints.
7. Fill existing deck drains as detailed in the plans. Mid-span deck drains are to remain open. See Special Provision for Deck Drain Clean and Fill.
8. Patch deteriorated prestressed concrete beam ends at locations determined by the Engineer (Est. Qty. = 63 Sq. Ft.). Wrap all beam ends with a fiber reinforced polymer composite system.
9. Apply surface seal to the bridge railing, bridge railing transitions, and deck copings.
10. Perform concrete patching at bridge deck copings (Est. Qty. = 40 Sq. Ft.), and abutments (Est. Qty. = 60 Sq. Ft.). Perform epoxy injection of cracked concrete at abutments (Est. Qty. = 40 Lft.).
11. Install revetment riprap for scour protection along abutments. Depth varies from 1'-6" at the top of slope to 2'-6" at the toe of slope. If existing footing is exposed during excavation cease the excavation immediately and contact the Engineer. See Approach Construction Details and Riprap Special Provision.
12. Remove existing bridge railing transition section, portions of existing wingwall, and existing bridge railing transition pad. Install concrete bridge railing transition, type TFC on RCBA extension for bridge railing transition.
13. Remove existing bridge railing transition section. Install new bridge railing, type FC modified and concrete bridge railing transition, type TFC on approach slab.
14. Install riprap drainage turnout. See Approach Construction Details.
15. Reconstruct drive approach to tie into reconstructed approach pavement. See Approach Construction Details.
16. Future 1'-0" channel dredging (by others).

SPREAD PRESTRESSED CONCRETE BOX BEAM
1 SPAN: 41'-0"
44'-0" CLEAR ROADWAY; 30° LT. SKEW
US 224 OVER EIGHT MILE CREEK
WELLS COUNTY

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: CPM 4/9/2026 | DRAWN: CPM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026


INDIANA DEPARTMENT OF TRANSPORTATION

GENERAL PLAN

SCALE	BRIDGE FILE
AS NOTED	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	8 of 17
	CONTRACT
	B-44532


Plot: 4/9/2026

File:
Model:BR_Layout




EXISTING TYPICAL SECTION

Scale ½" = 1'




PROPOSED TYPICAL SECTION

Scale ½" = 1'



OVERLAY AT DECK DRAIN DETAILS

Scale: 1" = 1'-0"



SECTION D-D

Scale: 1" = 1'-0"

SPREAD PRESTRESSED CONCRETE BOX BEAM
1 SPAN: 41'-0"
44'-0" CLEAR ROADWAY; 30° LT. SKEW
US 224 OVER EIGHT MILE CREEK
WELLS COUNTY

LEGEND

- Indicates Removal

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: CPM 4/9/2026 | DRAWN: CPM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026


INDIANA
DEPARTMENT OF TRANSPORTATION

GENERAL PLAN

SCALE	BRIDGE FILE
AS NOTED	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	9 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026

File:
Model:General Plan Sections




REMOVAL PLAN

Scale: 1" = 5'


SECTION E-E

Scale: ½" = 1'-0"




SECTION A-A

Scale: ½" = 1'-0"




SECTION B-B

Scale: ½" = 1'-0"



SECTION C-C

Scale: ½" = 1'-0"



SECTION D-D

Scale: ½" = 1'-0"

NOTES

1. Damage to the epoxy coating on the existing reinforcing bars to remain shall be repaired in accordance with Spec. 703.04.

LEGEND

- Indicates Removal

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: PSM 4/9/2026 | DRAWN: PSM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026


INDIANA DEPARTMENT OF TRANSPORTATION

REMOVAL DETAILS

SCALE	BRIDGE FILE
1" = 5'	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	10 of 17
	CONTRACT
	B-44532


Plot: 4/9/2026

File:
Model:BR_Layout




MUDWALL CONSTUCTION DETAILS

(Abutment No. 1 Shown, Abutment No. 2 Similar)
(Deck, Beams, Railings, and Approach Slab Not Shown)
Scale: 1" = 5'



SECTION C-C

Scale: 1" = 1'-0"




TYPE PCF BRIDGE EXPANSION JOINT END AT RAILING DETAIL

Not to Scale

BILL OF MATERIALS
MUDWALLS

EPOXY COATED REINFORCING BARS			
Size or Mark	No. of Bars	Length (ft-in)	Weight (lbs)
#5	8	27'-0"	
		Total #5	226
Total Epoxy Coated Reinforcing Bars			226
CONCRETE			
Concrete, C, Superstructure			5.2 Cys
MISCELLANEOUS			
Threaded Tie Bar Assembly			44 Each
Field Drilled Holes in Concrete			44 Each



501a x 4'-9"

THREADED TIE BAR ASSEMBLY, EPOXY COATED

Not to Scale

NOTES


1. All reinforcing bars shall be epoxy-coated.
2. For reinforcing bar notes see Standard Drawing E 703-BRST-01.
3. The Type PCF Bridge Expansion Joint at Abutment No. 1 shall match the existing joint opening width of 2 inches and be able to accommodate both the minimum and maximum joint opening widths as shown below

   W (min.) = 0.8 in.
   W (max.) = 3.2 in.


   The Type PCF Bridge Expansion Joint at Abutment No. 2 shall match the existing joint opening width of 1 5/8 inches and be able to accommodate both the minimum and maximum joint opening widths as shown below

   W (min.) = 0.7 in.
   W (max.) = 2.8 in.


   For additional Type PCF Bridge Expansion Joint details see Standard Drawing E 503-BATJ-02.



TYPICAL BEAM END ELEVATION



SECTION A-A



SECTION B-B
(EX. DECK NOT SHOWN)

BEAM END REPAIR DETAILS

Scale: ½" = 1'-0"

ADAM MONCENIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE


DESIGNED: PSM 4/9/2026 | DRAWN: PSM 4/9/2026
CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

SUPERSTRUCTURE DETAILS


SCALE	BRIDGE FILE
AS NOTED	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	11 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026
File:
Model: Mudwall Const




SECTION A-A

Scale: 1" = 1'-0"




SECTION B-B

Scale: 1" = 1'-0"




SECTION C-C

Scale: 1" = 1'-0"




SECTION D-D

Scale: 1" = 1'-0"



SECTION E-E

Scale: 1" = 1'-0"




SECTION F-F

Scale: 1" = 1'-0"


BILL OF MATERIALS
BRIDGE RAILING

EPOXY COATED REINFORCING BARS			
Size or Mark	No. of Bars	Length (ft-in)	Weight (lbs)
501c	26	3'-3"	
503c	16	2'-7"	
504c	7	3'-5"	
505c	7	3'-5"	
5802c	36	5'-3"	
5804c	57	5'-1"	
5808c	36	4'-7"	
5809c	57	4'-5"	
5816c	33	2'-9"	
#5	30	10'-9"	
#5	3	6'-9"	
#5	42	6'-0"	
#5	2	2'-3"	
		Total #5	1835
#4	7	7'-6"	
#4	14	5'-3"	
		Total #4	84
Total Epoxy Coated Reinforcing Bars			1919
CONCRETE			
Railing, Concrete Type FC, Modified			1.9 Cys
MISCELLANEOUS			
Concrete Bridge Railing Transition, Type TFC, Modified			3 Each
Field Drilled Hole in Concrete			40 Each
Surface Seal (Est. Quantity)			1244 Sft




SECTION G-G


Scale: 1" = 1'-0"




501c x 3'-3"




503c x 2'-9"



504c x 3'-5"




505c x 3'-5"




5802c x 5'-3"




5804c x 5'-1"



5808c x 4'-7"




5809c x 4'-5"



5816c x 2'-9"

NOTES

1. All reinforcing bars shall be epoxy-coated.
2. For reinforcing bar notes, see Standard Drawing E 703-BRST-01.
3. For bridge railing transition attachment of guardrail see Standard Drawing E 706-CBRT-04.




RAILING ELEVATION

Scale: ½" = 1'-0"

Northwest Transition Looking North Shown, Southeast Transition Looking South Similar

BAR BENDING DIAGRAMS

(Not to Scale)



RAILING ELEVATION

Scale: ½" = 1'-0"

Northeast Transition Looking North Shown

Plot: 4/9/2026

File:
Model:Railing Sheet

ADAM MONCZNIK
REGISTERED
No.11700255
STATE OF
INDIANA
PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE


DESIGNED: PSM 4/9/2026 | DRAWN: PSM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026


INDIANA
DEPARTMENT OF TRANSPORTATION

RAILING DETAILS

SCALE	BRIDGE FILE
AS NOTED	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	12 of 17
	CONTRACT
	B-44532



EAST APPROACH SLAB PLAN - TOP REINFORCEMENT



EAST APPROACH SLAB PLAN - BOTTOM REINFORCEMENT

NOTES

1. All reinforcing bars shall be epoxy-coated

2. For reinforcing bar notes, see Standard Drawing E 703-BRST-01.

3. For additional details, see Standard Drawing E 609-RCBA.

4. For details for RCBA Extension for TFC, see Standard Drawing E 609-TBAE.

5. For Bill of Material and Typical Section Through Approach see sheet 15.

ADAM MONCENIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: PSM 4/9/2026 | DRAWN: PSM 4/9/2026


CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION


APPROACH SLAB DETAILS

SCALE	BRIDGE FILE
¼" = 1'-0"	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	13 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026
File:
Model: East Approach Sheet



WEST APPROACH SLAB PLAN - TOP REINFORCEMENT



WEST APPROACH SLAB PLAN - BOTTOM REINFORCEMENT

NOTES

1. All reinforcing bars shall be epoxy-coated

2. For reinforcing bar notes, see Standard Drawing E 703-BRST-01.

3. For additional details, see Standard Drawing E 609-RCBA.

4. For details for RCBA Extension for TFC, see Standard Drawing E 609-TBAE.

5. For Bill of Material and Typical Section Through Approach see sheet 15.

ADAM MONCENIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: PSM 4/9/2026 | DRAWN: PSM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA DEPARTMENT OF TRANSPORTATION


APPROACH SLAB DETAILS

SCALE	BRIDGE FILE
¼" = 1'	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	14 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026

File:

Model: West Approach Sheet




TYPICAL SECTION THROUGH APPROACH

BILL OF MATERIALS WEST RCBA

EPOXY COATED REINFORCING BARS			
Size or Mark	No. of Bars	Length (ft-in)	Weight (lbs)
501d	33	30'-3"	
502d	9	24'-9"	
503d	8	27'-3"	
504d	44	30'-0"	
505d	3	22'-6"	
506d	2	29'-9"	
591d	89	20'-9"	
#5	4	26'-6"	
#5	108	23'-0"	
#5	67	20'-0"	
#5	1	6'-0"	
#5	6	5'-0"	
		Total #5	9073
RCBA Extension - 1 @ 230			230
Total Epoxy Coated Reinforcing Bars			9303
CONCRETE			
12" Reinf. Conc. Bridge Approach			167 Sys
MISCELLANEOUS			
Lean Concrete Base, 9 In.			167 Sys
Geotextile for Pavement, Type 2B			167 Sys
Longitudinal Grooving			163 Sys

BILL OF MATERIALS EAST RCBA


EPOXY COATED REINFORCING BARS			
Size or Mark	No. of Bars	Length (ft-in)	Weight (lbs)
501d	33	30'-3"	
502d	9	24'-9"	
503d	8	27'-3"	
504d	44	30'-0"	
505d	3	22'-6"	
506d	2	29'-9"	
591d	89	20'-9"	
#5	4	26'-6"	
#5	108	23'-0"	
#5	67	20'-0"	
#5	1	6'-0"	
#5	6	5'-0"	
		Total #5	9073
RCBA Extension - 1 @ 230			460
Total Epoxy Coated Reinforcing Bars			9533
CONCRETE			
12" Reinf. Conc. Bridge Approach			169 Sys
MISCELLANEOUS			
Lean Concrete Base, 9 In.			169 Cys
Geotextile for Pavement, Type 2B			169 Sys
Longitudinal Grooving			163 Sys



591d x 20'-9"

BAR BENDING DIAGRAMS

(Not to Scale)



BAR CUTTING DETAILS

Not to Scale

CUT BAR DIAGRAM

MARK	L	A	B	C	D	INC.	N	DESCRIPTION
501d	30'-3"	2'-7"	27'-8"	14'-11 1/8"	15'-3 7/8"	4 5/8"	32	33 - #5 x 30'-3" cut 66 - 501d
502d	24'-9"	2'-6"	22'-3"	11'-9 1/2"	12'-11 1/2"	1'-2"	8	9 - #5 x 24'-9" cut 18 - 502d
503d	27'-3"	5'-0"	22'-3"	13'-0 5/8"	14'-2 3/8"	1'-1 7/8"	7	8 - #5 x 27'-3" cut 16 - 503d
504d	30'-0"	2'-6"	27'-6"	14'-10 1/4"	15'-1 3/4"	3 1/2"	43	44 - #5 x 30'-0" cut 88 - 504d
505d	22'-6"	2'-7"	19'-11"	9'-6 1/4"	12'-11 3/4"	3'-5 5/8"	2	3 - #5 x 22'-6" cut 6 - 505d
506d	29'-9"	9'-9"	20'-0"	13'-2"	16'-7"	3'-5"	1	2 - #5 x 29'-0" cut 4 - 506d

NOTES

1. All reinforcing bars shall be epoxy-coated

2. For reinforcing bar notes, see Standard Drawing E 703-BRST-01.

3. For additional details, see Standard Drawing E 609-RCBA.

4. For details for RCBA Extension for TFC, see Standard Drawing E 609-TBAE.

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: PSM 4/9/2026 | DRAWN: PSM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA DEPARTMENT OF TRANSPORTATION

APPROACH SLAB DETAILS

SCALE	BRIDGE FILE
½" = 1'	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	15 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026

File:
Model:Extension Sheet

SUMMARY OF BRIDGE QUANTITIES

ITEM	CONCRETE		RAILING, CONCRETE TYPE FC, MODIFIED	REINF. BARS, EPOXY COATED	REINF. CONC. BRIDGE APPROACH (12 IN)	BRIDGE EXP. JOINT SEAL, TYPE PCF, REPLACE	SURFACE SEAL**	GEOTEXTILE FOR PAVEMENT, TYPE 2B	LEAN CONCRETE BASE, 9 IN.	FIELD DRILLED HOLE IN CONCRETE	THREADED TIE BAR ASSEMBLY, EPOXY COATED	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC MODIFIED	FIBER WRAP CONCRETE CASING SYSTEM**	PATCHING CONCRETE STRUCTURES	BRIDGE DECK OVERLAY, RIGID	HYDRODEMOLITION	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	LONGITUDINAL GROOVING	BRIDGE DECK PATCHING, FULL DEPTH	OVERLAY DAM	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	EPOXY INJECTION, CRACK PREPARATION
	CLASS C	CLASS A																				
	SUPERSTR	SUBSTR																				
	CYS	CYS	CYS	LBS	SYS	LFT	SFT	SYS	SYS	EACH	EACH	EACH	SFT	SFT	SYS	SYS	SYS	SYS	SFT	SFT	GAL	LFT
Superstructure	5.2			226		105				42	44		425	103	209	200	209	209	50	102		
Substructure														60							2	40
Reinforced Concrete Bridge Approach				18836	336			336	336									326				
Bridge Railing			1.9	1919			1244			40		3										
TOTALS	5.2	0	1.9	20981	336	105	1244	336	336	82	44	3	425	163	209	200	209	535	50	102	2	40

**Estimated Quantity

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL _____ 4/9/2026
DESIGN ENGINEER DATE

DESIGNED: PSM 4/9/2026 | DRAWN: PSM 4/9/2026
CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA
DEPARTMENT OF TRANSPORTATION

BRIDGE SUMMARY

SCALE	BRIDGE FILE
NONE	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	16 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026
File:
Model: Bridge Summary

PAVEMENT QUANTITIES AND APPROACH TABLE

LOCATION	DESCRIPTION (APPROACH TYPE OR CLASS)	WIDTH	LENGTH	EXCAVATION		HMA FOR ROADS			HMA FOR APPROACHES			ASPHALT MATERIAL FOR		COMPACTED AGGREGATE FOR BASE NO. 53		COMPACTED AGGREGATE FOR SHOULDER NO. 53 DEPTH 10 IN.	JOINT ADHESIVE	SUBGRADE TREATMENT, TYPE 1C	SUBGRADE TREATMENT, TYPE II	GEOTEXTILE FOR PAVEMENT, TYPE 2B	MILLING, TRANSITION	LINEAR GRADING	REMARKS
						SURFACE QC/QA, 3, 58S, 9.5MM	INTERMD QC/QA, 3, 58S, 19.0MM	BASE QC/QA, 3, 58S, 25.0MM	SURFACE TYPE B	INTERMD TYPE B	BASE TYPE B	PRIME COAT	TACK COAT	DEPTH										
				CUT	FILL	LBS PER SYD			LBS PER SYD					6 IN									
		FT	FT	CYS	CYS	TONS	TONS	TONS	TONS	TONS	TONS	SYS	TON	CYS	TONS	TONS	FT	SYS	SYS	SYS	SYS	LFT	
701+79 to 702+89		41.5	110			43							0.4			41	330				508	110	
702+89 to 702+99		44.7	10	120		4	7	17					0.1				60	55		55		56	
703+04	Drive	13.0	17.6						3	5			0.1	6					35				
704+11 to 704+21		44.7	10	125		5	7	17					0.1				60	55		55		53	
704+21 to 705+31		42.3	110			43							0.3			61	330				517	110	
TOTALS				245	0	95	14	34	3	5	0	0	1	6	0	102	780	110	35	110	1025	329	

GUARDRAIL SUMMARY TABLE

LOCATION		LEFT	MEDIAN LEFT	MEDIAN RIGHT	RIGHT	MGS W-BEAM GUARDRAIL STANDARD POST AT 6 FT 3 IN. SPA.	GUARDRAIL TRANSITION, MGS WITHOUT CURB	GUARDRAIL HEIGHT TRANSITION, MGS	GUARDRAIL END TREATMENT TYPE OS	GUARDRAIL REMOVE	REMARKS
FROM STATION	TO STATION					LFT	EACH	EACH	EACH	LFT	
701+59	703+05	X					1		1	147	
703+65	705+33	X				62.5	1		1	145	
704+05	704+88				X		1	1		82	
TOTALS						63	3	1	2	374	

PERMANENT EROSION CONTROL SUMMARY TABLE

LOCATION		LEFT	MEDIAN	RIGHT	RIPRAP, REVETMENT	GEOTEXTILE FOR RIPRAP, TYPE 1A	SODDING	MULCHED SEEDING, TYPE R	REMARKS
FROM STATION	TO STATION				TONS	SYS	SYS	SYS	
701+05	705+48	X			169	168	8	435	
701+05	705+48			X	176	177	10	552	
TOTALS					345	345	18	987	

PAVEMENT MARKINGS TABLE

LOCATION		LINE, PAINT		SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE
		SOLID WHITE 6 IN.	BROKEN YELLOW 6 IN.	
		LFT	LFT	EACH
701+79	705+31	704	88	5
TOTALS		704	88	5

RIGHT OF WAY MARKERS

STATION	OFFSET	LEFT	RIGHT
701+50.00	45.00'	X	
702+75.00	45.00'	X	
702+75.00	55.00'	X	
702+82.03	55.00'	X	
704+00.00	55.00'	X	
704+00.00	40.00'	X	
705+50.00	40.00'	X	
701+70.00	40.00'		X
703+24.75	40.00'		X
703+24.55	54.00'		X
704+30.00	54.00'		X
704+30.00	45.00'		X
705+50.00	45.00'		X

MONUMENTS

LOCATION				TYPE	
STATION	LEFT	CENTER	RIGHT	B	CASTING ADJUST TO GRADE
702+81.32		X			X
702+89.28		X		X	
704+20.72		X		X	

ADAM MONCZNIK REGISTERED No.11700255 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL — DESIGN ENGINEER — 4/9/2026 DATE

DESIGNED: PSM 4/9/2026 | DRAWN: PSM 4/9/2026

CHECKED: APM 4/9/2026 | CHECKED: APM 4/9/2026

INDIANA DEPARTMENT OF TRANSPORTATION

ROAD SUMMARY

SCALE	BRIDGE FILE
NONE	224-90-01545 B
	DESIGNATION
	2200957
	SHEETS
	17 of 17
	CONTRACT
	B-44532

Plot: 4/9/2026

File:
Model:Bridge Summary