DESIGNATION	BRIDGE FILE
1900048	035-27-10469
CONTRACT	
B-45063	

STRUCTURE INFORMATION				
STRUCTURE	TYPE	SPAN AND SKEW	OVER	STATION
035-27-10469	COMPOSITE PRESTRESSED CONCRETE BULB-TEE BEAM BRIDGE	1 Span: 115'-0" Skew: 15° Rt.	Deer Creek	1271+60 Line "A"

INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE PLANS

FOR SPANS OVER 20 FEET

ROUTE: US 35 AT: RP 81+58

DESIGNATION NO. 1900048 P.E.

Bridge Replacement on US 35 over Deer Creek
Located 0.25 miles west of SR 9
Section 1, T-23-N, R-7-E & Section 36, T-24-N, R-7-E, Franklin & Liberty Township, Grant County, Indiana


SCALE: 1" = 2000'

TRAFFIC DATA

A.A.D.T.	(2026)	3,451 V.P.D.
A.A.D.T.	(2046)	3,769 V.P.D.
D.H.V	(2046)	322 V.P.H.
DIRECTIONAL DISTRIBUTION		50.14 %
TRUCKS		20.98 % A.A.D.T.
		15.90 % D.H.V.

DESIGN DATA

DESIGN SPEED	55 M.P.H.
Project Design Criteria	3R (NON-FREEWAY)
FUNCTIONAL CLASSIFICATION	PRINCIPAL ARTERIAL
RURAL/URBAN	RURAL
TERRAIN	LEVEL
ACCESS CONTROL	NONE



PROJECT LOCATION SHOWN BY
Grant County

LATITUDE: N 40°28'49.56" LONGITUDE: W 85°40'37.16"

BRIDGE LENGTH:	0.022	MI.
ROADWAY LENGTH:	0.126	MI.
TOTAL LENGTH:	0.148	MI.
MAX. GRADE:	2.95	%

HUC: 051201030508

INDIANA DEPARTMENT OF TRANSPORTATION
STANDARD SPECIFICATIONS DATED 2026
TO BE USED WITH THESE PLANS.

Plot: 7/13/2026 9:24 AM

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

PLANS PREPARED BY: David Riyad, PE (317)232-0682 PHONE NUMBER

CERTIFIED BY: David Riyad 7/24/2026 DATE

RECOMMENDED FOR LETTING: Stephanie J. Wagner 09/22/2026 DATE
INDIANA DEPARTMENT OF TRANSPORTATION

BRIDGE FILE
035-27-10469
DESIGNATION
1900048
SHEETS
1 of 36
CONTRACT
B-45063

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Title.dgn
Model:BR_Title Sheet

UTILITIES

ELECTRIC:
AMERICAN ELECTRIC POWER
J. JAY MARLOW (260) 408-3447

COMMUNICATIONS:
AT&T DISTRIBUTION
MATT SPINDLER (317) 220-7043
g09871@att.com
240 N. MERIDIAN ST., ROOM 1791, INDIANAPOLIS, IN 46204

GAS:
CENTERPOINT ENERGY (NORTH) (FORMERLY VECTREN)
JON EASTHAM (765) 287-2119
publicproject@centerpointenergy.com
1800 W. 26TH ST., MUNCI, IN 47302

FIBER OPTIC
CHILLICOTHE CO. DBA HORIZON TELCOM
JIM LUMP (740) 777-8256
jim.lump@horizonconnects.com
68 E. MAIN STREET, CHILLICOTHE, OH 45601

CABLE TV:
BRIGHT HOUSE NETWORKS
MARION

PIPELINE:
BUCKEYE
TRACI MCCLERNON (610) 904-4475
tmcclernon@buckeye.com
9999 HAMILTON BLVD BREINIGSVILLE, PA 18031

FIBER OPTIC:
IN FIBER NETWORK DBA INTELLIGENT FIBER NETWORK
SHAWN WRIGHT (317) 777-7119
swright@intelligentfiber.com
KEITH HAMM (317) 777-7583
khamm@intelligentfiber.com
5520 W. 76TH ST. INDIANAPOLIS, IN 46268

SEWER, WATER:
SWAYZEE UTILITIES
TREY BOSWELL (765) 922-7645
trey.boswell@yahoo.com
PO BOX 85 SWAYZEE, IN 46986

TELEPHONE:
SWEETSER TELEPHONE/ OAKHILL CABLE
DAVE FOX (765) 661-0589
fox@comteck.com
210 N MAIN ST SWEETSER, IN 46987

FIBER OPTIC:
ZAYO BANDWIDTH
JOHN SENESE (317) 524-5711
jsenese@zayo.com
625 EAST 11TH STREET INDIANAPOLIS, IN 46202

811 Know what's below. Call before you dig.

INDIANA UNDERGROUND
1-800-382-5544 OR CALL 811
24 HOURS A DAY 7 DAYS A WEEK

REVISIONS

SHEET NO.	DATE	REVISED

INDEX

SHEET NO.	
1	TITLE
2	INDEX
3	TYPICAL CROSS SECTIONS
4	DETOUR DETAIL
5	PLAN & PROFILE
6	APPROACH DETAILS
7	TEMPORARY EROSION CONTROL DETAILS
8-9	SOIL BORINGS
10	LAYOUT
11-12	GENERAL PLAN
13-17	END BENT DETAILS
18	FRAMING PLAN
19-20	BEAM DETAILS
21-22	FLOOR DETAILS
23	RAILING DETAILS
24	SCREED DETAILS
25	APPROACH SLAB DETAILS
26	BRIDGE SUMMARY
27	ROAD SUMMARY
28	PIPE MATERIALS
29 - 36	CROSS SECTIONS

GENERAL NOTES

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 6/2021 DRAWN: DR 6/2021
CHECKED: MTC 6/2021 CHECKED: MTC 6/2021


INDIANA
DEPARTMENT OF TRANSPORTATION

INDEX SHEET

SCALE	BRIDGE FILE
N/A	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	2 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:24 AM

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Index.dgn
Model:BR_Index Sheet




TYPICAL FULL DEPTH SECTION LINE "A"

Sta. 1268+85 to Sta. 1270+76.06
Sta. 1272+43.94 to Sta. 1272+85
Scale: 3/8" = 1'-0

* Except as shown on cross sections.

LEGEND


- (K) 165 lb/syd. QC/QA-HMA, 3, 58H, Surface 9.5 mm on
  275 lb/syd. QC/QA-HMA, 3, 58H, Intermediate 19.0 mm on
  880 lb/syd. QC/QA-HMA, 3, 58S, Base, 25.0 mm on
  Subgrade Treatment Type IC on Geotexile for Pavement, Type 2B.
- (K1) Widening with HMA, Type C, Consisisting of
  275 lb/syd. HMA Intermediate, Type C on
  880 lb/syd. HMA Base, Type C on
  Subgrade Treatment Type IC on Geotexile for Pavement, Type 2B.
- (R1) 165 lb/syd. QC/QA-HMA, 3, 58H, Surface 9.5 mm on
  275 lb/syd. QC/QA-HMA, 3, 58H, Intermediate 19.0 mm on
  Mill the existing asphalt pavement up to 4 inches for vertical alignment purposes.
- (R2) 165 lb/syd. QC/QA-HMA, 3, 58H, Surface 9.5 mm on Widening with HMA, Type C (K1)
- (R) 165 lb/syd. QC/QA-HMA, 3, 58H, Surface 9.5 mm on existing pavement.
  Mill existing asphalt pavement 1½"
- (O) Variable Depth Compacted Aggregate, Size #53



TYPICAL WIDENING AND RESURFACE SECTION LINE "A"

Sta. 1267+25 to Sta. 1268+85
Sta. 1272+85 to Sta. 1273+20
Scale: 3/8" = 1'-0


* Except as shown on cross sections.



TYPICAL WIDENING AND RESURFACE SECTION LINE "A"

Sta. 1266+50 to Sta. 1267+25
Sta. 1273+20 to Sta. 1274+35
Scale: 3/8" = 1'-0


* Except as shown on cross sections.



** Vary slope to match existing at the end of milling transition

TYPICAL INCIDENTAL SECTION LINE "A"

Sta. 1266+00 to Sta. 1266+50
Sta. 1274+35 to Sta. 1275+25
Scale: 3/8" = 1'-0




* Except as shown on cross sections.

TYPICAL GUARDRAIL SECTION


Sta. 1270+66.16 to Sta. 1271+05.91 Lt.
Sta. 1272+39.16 to Sta. 1274+04.18 Lt.

Sta. 1269+15.81 to Sta. 1270+80.83 Rt.
Sta. 1272+14.07 to Sta. 1273+04.09 Rt.
Scale: 3/8" = 1'-0



SAFETY EDGE ON HMA PAVEMENT

Not To Scale



MILLING AND RESURFACE DETAILS LINE "A"

Not to Scale

NOTES

1. For guardrail limits, see plan and profile sheet and approach detail sheet.
2. For additional information on ditches and embankment slopes, see cross-section sheets

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR	5/2021	DRAWN: TLA	5/2021
CHECKED: MTC	5/2021	CHECKED: DR	5/2021

INDIANA
DEPARTMENT OF TRANSPORTATION


TYPICAL CROSS-SECTIONS

SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	3 of 36
	CONTRACT
	B-45063


Plot: 7/13/2026 9:24 AM


pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Typical Cross Section.dgn


DETAIL B
SCALE: NONE





DETOUR PLAN
SCALE: NONE











DETAIL A
SCALE: NONE

MAINTENANCE OF TRAFFIC QUANTITIES		
Description	Quantity	Unit
Construction Sign, Type A	12	EACH
Construction Sign, Type C	2	EACH
Detour Route Marker Assembly	24	EACH
Road Closure Sign Assembly	4	EACH
Type IIIA Barricade	72	LFT
Type IIIB Barricade	72	LFT
Maintaining Traffic	1	LSM

LEGEND

Sign/Sign assembly

Barricade (Total 18 ft / Barricade)

NOTES

1. Detour route marker assembly shall be placed per Standard Drawings E 801-TCDT- 01 & 04.
2. For signs details see Standard Drawing E 801-TCSN-01 to 06.
3. The contractor should adjust Type IIIA barricades location during construction to accommodate construction activities and to maintain access to all drives within construction limits.

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Rizad 7/24/2026
DESIGN ENGINEER DATE


DESIGNED: MTC	1/2021	DRAWN: TLA	1/2021
CHECKED: MH	1/2021	CHECKED: MTC	1/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

DETOUR DETAIL

SCALE	BRIDGE FILE
NONE	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	4 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:24 AM
File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Detour.dgn
Model:BR_Detour



DATE	REVISION

400 NORTH 165650.5549 EAST 792987.2041 LINE "A"
#5 Rebar With Control Point Cap
RB-5/8"
A-254°-28.33' to Mag Nail In EOP
B-291°-8.11' to Mag Nail in NE Face of Telephone Pole
C-123° - 58.16' to Mag Nail in EOP
O.P.O.T. 1263+15.89, 28.58' Lt

501 NORTH 165622.1049, EAST 793071.3603 LINE "A"
Mag Spike Set Flush
A-292°-109.97' Mag Nail Set at EOP
B-307°-31.43' Mag Nail Set at EOP
C-161°-19.21 Mag Nail Set at EOP
P.O.T. 1264+00.00-Begin Project

GPS_BASE NORTH 165651.3395 EAST 793993.7663 LINE "A"
#5 Rebar With Control Point Cap
A-258°-30.02' to Mag Nail In EOP
B -284°-18.24' to Mag Nail in NE Face of Telephone Pole
C- 141° - 13.37' to Mag Nail in EOP
O.P.O.T. 1273+22.45, 27.85' Lt

502 NORTH 165624.4337 EAST 794621.3585 LINE "A"
Mag Spike Set (Flush)
A -24.58 - 314° - Mag Nail Set at EOP
B -23.57 - 69° - Mag Nail Set at EOP
C -23.28' - 143° - Mag Nail Set at EOP
P.O.T. 1279+50.00

401 NORTH 165595.9230 EAST 794645.7700 LINE "A"
#5 Face P/P #P-65
#5 Face P/P #P-66
#5 Face P/P #P-67
#5 Face P/P #P-68
#5 Face P/P #P-69
#5 Face P/P #P-70
A - 284° - 88.37' Mag Nail Set in
B - 336° - 7.06' Mag Nail Set in
C - 92° - 62' Pavement Mag Nail Set in
O.P.O.T. 1279+74.37, 28.55' Rt

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL: David Riyad — DESIGN ENGINEER — 7/24/2026 DATE


DESIGNED: DR	6/2021	DRAWN: DR	6/2021
CHECKED: MH	6/2021	CHECKED: MH	6/2021

INDIANA DEPARTMENT OF TRANSPORTATION


PLAN AND PROFILE LINE "A"

SCALE	BRIDGE FILE
HORIZONTAL 1"=50'	035-27-10469
VERTICAL 1"=10'	DESIGNATION
	1900048
	SHEETS
	5 of 36
	CONTRACT
	B-45063


Plot: 7/13/2026 9:25 AM
File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\Sht PlanProfile 50.dgn
Model:Default




ROADWAY, SHOULDER, AND GUARDRAIL DETAILS
Not To Scale



GUARDRAIL TAPER DETAILS
(Detail A)
Not To Scale



MAILBOX APPROACH DETAILS (West Approach)
Scale : 1" = 10'-0"



MAILBOX APPROACH DETAILS (East Approach)
Scale : 1" = 10'-0"

PERMANENT PAVEMENT MARKING		
Description	Quantity	Unit
Line Paint, Solid, Yellow, 6 IN	1850	LFT
Line Paint, Solid, White, 6 IN	1850	LFT

LEGEND

(SW) Solid White (Paint)

(SY) Solid Yellow (Paint)

NOTES

1. For mailbox approach details see Standard Drawing No. E 610-MBAP-01
2. For guardrail details see Standard Drawings No. E 601-MGSA-01 through 23
3. For more detail in signs relocation see road summary sheet.
4. If temporary striping is needed, only temporary tape will be used.
5. Paint will not be used until the final mot placement. There will be no grinding nor blasting of any sort allowed on the finished deck nor the approach slabs.
6. For class II drive details see Standard Drawings No. E 610-DRIV-03 & 10
7. For class V drive details see Standard Drawings No. E 610-DRIV-06
8. * For sign relocation information see roadway summary sheet.

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 6/2021 DRAWN: DR 6/2021

CHECKED: MTC 6/2021 CHECKED: MTC 6/2021


INDIANA
DEPARTMENT OF TRANSPORTATION

APPROACH DETAILS


SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	6 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:25 AM

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Approach Details 01.dgn
Model:BR_Detail Sheet



PLAN VIEW
Scale: 1"=50'-0"



DETAIL A
Scale: 1"=25'-0"

STORMWATER MANAGEMENT ITEMS		
ITEM	QUANTITY	UNIT
Dewatering	1	LS
Sediment Remove	10	CYS
Mobilization and Demoblization for suface stablization	2	Each
Temporary Check Dam, Revetment Riprap	83	Ton
Temporary Geotextile	374	Syd
Temporary Filter Stone (#5 or #8)	21	Ton
Temporary Filter Sock	1,777	Lft
Temporary Mulch Stabilization, Type A	2,903	Syd
Temporary Seed Mixture	90	Lbs
Rock Filter Berm	72	Lft

TEMPORARY EROSION CONTROL QUANTITY		
ITEM	QUANTITY	UNIT
Cofferdam (Sand Bag)	1	LS

PERMANENT EROSION CONTROL QUANTITIES		
ITEM	QUANTITY	UNIT
Mobilization & Demobilization for Seeding	2	Ls
Water	20	Kgal
Erosion Control Blanket	1,934	Sys
Mulched Seeding R	1,934	Sys
Class1 Riprap	648	Ton
Revetment Riprap	350	Ton
Geotextile for Riprap Type 2B	1,310	SYS
Sodding	204	SYS

FILTER SOCK LOCATION		
North West	539	Lft
South West	567	Lft
North East	287	Lft
South East	384	Lft
TOTAL	1777	Lft

LEGEND

- Temporary Cofferdam (Sandbag)
- Filter Sock
- Temporary Rock Filter Berm
- Dewatering Pump
- Filter Bags on Levelling Pad with Filter Fabric
- Sump Hole
- Diffuser (Energy Dissipator), (Geotextile Under Riprap)
- Check Dam(Modified)
- Wetland A 0.003 Acre
- Riprap Class I
- Revetment Riprap

NOTES

1. Temporary seeding shall be applied at the end of the day to any disturbed soils due to construction operations, and due to any loose or moist soils, when additional work is not scheduled for at least 7 days and as directed by the engineer.
2. For temporary check dams (modified) see Standard Drawings No. E-205-TECD-06, 07, & 8
3. For temporary construction entrance see Standard Drawings No. E-205-TECP-2
4. For filter sock placement see Standard Drawings No. E-205-TECP-10

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 2/2022 | DRAWN: DR 2/2022
CHECKED: MH 2/2022 | CHECKED: MH 2/2022

INDIANA
DEPARTMENT OF TRANSPORTATION

EROSION AND SEDIMENT CONTROL

SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	7 of 36
	CONTRACT
	B-45063

AM
7/13/2026

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Erosion Control.dgn

INDOT BORING LOG

BORING NO.: TB-01B
SHEET 1 OF 3
LATITUDE : 40.480401
LONGITUDE : -85.677133
DATUM : NAD 83 (IN East)
DATE STARTED : 10-13-21
DATE COMPLETED : 10-13-21

ROUTE # : US 35 COUNTY : Grant
PROJECT TYPE : Bridge Replacement
LOCATION : Marion, Indiana
DES NO. : 1900048 PROJECT NO.: 2063-2045.50

ELEVATION	: 847.0	BORING METHOD	: HSA	HAMMER	: Auto
STATION	: 81+48	RIG TYPE	: Truck	DRILLER/INSP	: KC/AM
OFFSET	: 8.0 ft Left	CASING DIA.	: 3.3 in	TEMPERATURE	: 77 °F
LINE	: "US-35'	CORE SIZE	: 2 in	WEATHER	: Partly Cloudy
DEPTH	: 44.5 ft				

GROUNDWATER: ▽ Encountered at 13.5 ft ▼ At completion 9.1 ft (15.4 ft prior to adding water)

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	POCKET PEN., tsf	UNCONF. COMP., tsf	ATTERBERG LIMITS LL	PL	PI	REMARKS
845.0		Pavement Depth Not Recorded in Field. 2.0											
	2.5	**Sand** Brown, Slightly Moist To Moist, Very Loose, (Visual).	SS 1	2 3 2	56	5							
	5.0		SS 2	2 2 3	67	5							
838.5	7.5	8.5					17.6	1.5		31	19	12	
	10.0	**Silty Clay Loam A-6 (10)**, Brown, Slightly Moist, Soft, (Lab No. 11).	SS 3	2 2 2	78	4							
833.5 ▽	12.5	13.5											
	15.0	**Gravelly Sand** Gray, Wet, Very Dense, (Visual).	SS 4	13 25 34	83	59							
828.5	17.5	18.5											
	20.0	**Sand** Gray, Moist, Medium Dense, (Visual).	SS 5	10 13 14	100	27							

Continued on next page

INDOT BORING LOG

INDOT BORING LOG

BORING NO.: TB-01B
SHEET 2 OF 3
LATITUDE : 40.480401
LONGITUDE : -85.677133
DATUM : NAD 83 (IN East)

ROUTE # : US 35 COUNTY : Grant
PROJECT TYPE : Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	POCKET PEN., tsf	UNCONF. COMP., tsf	ATTERBERG LIMITS LL	PL	PI	REMARKS
	22.5	**Sand** Gray, Moist, Medium Dense, (Visual). 23.5											
823.5	25.0		SS 6	19 41 46	83	87							
	27.5	**Gravelly Sand** Gray, Wet, Very Dense, (Visual). 28.5											
818.5	30.0		SS 7	50/2	100								
	32.5	**Limestone** Gray, Highly Weathered, (Visual). 34.5											
812.5	35.0		SS 8	50/3	100								
	37.5		RC 1 RQD= 97%		97								
	40.0	**Limestone** Gray, Moderately Weathered, Hard, Crystalline, Thinnly bedded, Slightly fractured, (Visual).											
	42.5		RC 2 RQD= 100%		100								
802.5		44.5											

Continued on next page

INDOT BORING LOG


INDOT BORING LOG

BORING NO.: TB-01B
SHEET 3 OF 3
LATITUDE : 40.480401
LONGITUDE : -85.677133
DATUM : NAD 83 (IN East)

ROUTE # : US 35 COUNTY : Grant
PROJECT TYPE : Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	POCKET PEN., tsf	UNCONF. COMP., tsf	ATTERBERG LIMITS LL	PL	PI	REMARKS
	45.0	Bottom of Boring at 44.5 ft											
	47.5												
	50.0												
	52.5												
	55.0												
	57.5												
	60.0												
	62.5												
	65.0												
	67.5												

INDOT BORING LOG 2063-2045.50 US 35 BRIDGE (DES #1900048).GPJ INDOT 4.GDT 11/16/21



PLAN
SCALE : 1/32" = 1'-0"

PILE LOADING FOR GEOTECHNICAL TESTING		
	Bent No. 1	Bent No. 2
PILE SIZE, TYPE & GRADE	HP 12x53 50 ksi	HP 12x53 50 ksi
FACTORED DESIGN LOAD, Q (kips)	280	280
FACTORED DESIGN SOIL RESISTANCE, R _ (kips)	280	280
RESISTANCE FACTOR ϕ _	0.7	0.7
DOWNDRAG LOAD, DD (kips)	0	0
MAXIMUM NOMINAL SOIL RESISTANCE, Rnmax (kips)	400	400
DOWNDRAG FRICTION, R_{sdd} (kips)	0	0
SCOUR LOAD - Rs_	0	0
RELAXATION OF TIP IN SHALE, R _	0	0
MAXIMUM NOMINAL DRIVING RESISTANCE, $R_{ndr\ max}$(kips)	400	400
ESTIMATED PILE TIP ELEVATION	812 / Limestone	817.5 / Limestone
TESTING METHOD	BY FORMULA, ISS 701.05(a)	

NOTES

1. Piles shall be driven to refusal.
2. Hardened piles shoes are requlred.
3. Restrike for piles bearing in limestone bedrock shall be after 24 hours.

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 1/2022 DRAWN: DR 1/2022
CHECKED: MH 1/2022 CHECKED: MH 1/2022

INDIANA
DEPARTMENT OF TRANSPORTATION

SOIL BORINGS
SHEET NO.1

SCALE	BRIDGE FILE
N/A	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	8 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:25 AM

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Borings .dgn

INDOT BORING LOG

BORING NO.: TB-02
SHEET 1 OF 3
LATITUDE : 40.480448
LONGITUDE : -85.676672
DATUM : NAD 83 (IN East)
DATE STARTED : 10-19-21
DATE COMPLETED : 10-19-21

ROUTE # : US 35 COUNTY : Grant
PROJECT TYPE : Bridge Replacement
LOCATION : Marion, Indiana
DES NO. : 1900048 PROJECT NO.: 2063-2045.50

ELEVATION	: 856.0	BORING METHOD	: HSA	HAMMER	: Auto
STATION	: 81+46	RIG TYPE	: Truck	DRILLER/INSP	: KC/AM
OFFSET	: 8.0 ft Right	CASING DIA.	: 3.3 in	TEMPERATURE	: 68 °F
LINE	: "US-35"	CORE SIZE	: 2 in	WEATHER	: Partly Cloudy
DEPTH	: 50.5 ft				

GROUNDWATER: ▽ Encountered at 18.5 ft ▼ At completion 9.9 ft (21.1 ft prior to adding water)

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	POCKET PEN., tsf	UNCONF. COMP., tsf	ATTERBERG LIMITS LL	PL	PI	REMARKS
854.9		**Asphalt** (VISUAL). 1.1											
854.6		**Concrete** (VISUAL). 1.4											
854.2		**Base**, (VISUAL). 1.8											
	2.5		SS 1	3 1 2	44	3	15.7	0.25		23	13	10	
	5.0	**Loam A-4 (2)**, Gray, Moist, Very Soft, (Lab No. 12).					20.5	0.5					
			SS 2	1 1 1	83	2	17.7	1.0		17	12	5	
847.5		8.5	ST 1		100			4.5					
	10.0												
	12.5	**Loam A-4 (0)**, Gray, Slightly Moist, Hard, (Lab No. 15).	SS 4	13 20 21	100	41	7.6	4.5		17	11	6	
	15.0												
	17.5												
837.5 ▽		18.5					21.6						
	20.0	**Sandy Loam** Gray, Moist, Dense, (Visual).	SS 5	9 22 24	89	46							

Continued on next page

INDOT BORING LOG

BORING NO.: TB-02
SHEET 2 OF 3
LATITUDE : 40.480448
LONGITUDE : -85.676672
DATUM : NAD 83 (IN East)

ROUTE # : US 35 COUNTY : Grant
PROJECT TYPE : Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	POCKET PEN., tsf	UNCONF. COMP., tsf	ATTERBERG LIMITS LL	PL	PI	REMARKS
	22.5	**Sandy Loam** Gray, Moist, Dense, (Visual).											
832.5		23.5					16.2						
831.8		**Silt** Gray, Slightly Moist To Moist, Dense, (Visual). 24.3	SS 6	11 23 26	100	49							
	25.0	**Sand** Gray, Wet, Dense, (Visual).											
	27.5												
827.5		28.5	SS 7	31 36 20	94	56							
	30.0	**Sandy Gravel** Gray, Wet, Very Dense, (Visual).											
	32.5												
822.5		33.5	SS 8	11 23 30	100	53	11.0	4.5+		19	11	8	
	35.0	**Loam A-4 (1)**, Gray, Moist, Hard, (Lab No. 18).											
	37.5												
817.5		38.5	SS 9	28 50/3	100								
816.5		**Limestone** Gray, Highly Weathered, (Visual). 39.5											
	40.0	**Limestone** Gray, Slightly Weathered, Hard, Crystalline, Thinnly bedded, Slightly fractured, (Visual).	RC 1 RQD= 80%		87								
	42.5												

Continued on next page

INDOT BORING LOG

BORING NO.: TB-02
SHEET 3 OF 3
LATITUDE : 40.480448
LONGITUDE : -85.676672
DATUM : NAD 83 (IN East)

ROUTE # : US 35 COUNTY : Grant
PROJECT TYPE : Bridge Replacement

STRATUM ELEVATION	SAMPLE DEPTH	SOIL/MATERIAL DESCRIPTION	SAMPLE NUMBER	SPT per 6"	% RECOVERY	N	MOISTURE CONTENT	POCKET PEN., tsf	UNCONF. COMP., tsf	ATTERBERG LIMITS LL	PL	PI	REMARKS
	45.0												
	47.5	**Limestone** Gray, Slightly Weathered, Hard, Crystalline, Thinnly bedded, Slightly fractured, (Visual).	RC 2 RQD= 77%		98								
805.5	50.0	50.5											
		Bottom of Boring at 50.5 ft											
	52.5												
	55.0												
	57.5												
	60.0												
	62.5												
	65.0												
	67.5												

INDOT BORING LOG 2063-2045.50 US 35 BRIDGE (DES #1900048).GPJ INDOT 4.GDT 11/16/21

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 1/2022 DRAWN: DR 1/2022
CHECKED: MH 1/2022 CHECKED: MH 1/2022


INDIANA
DEPARTMENT OF TRANSPORTATION

SOIL BORINGS
SHEET NO.2

SCALE	BRIDGE FILE
N/A	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	9 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:26 AM

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Borings .dgn



PRESENT STRUCTURE

Single Span Earth Filled Reinforced Concrete
Arch Bridge, Span Length 60 ft, Skew 15°
(To Be Removed)

HYDRAULIC DATA

Waterway Opening Required	446.6	Sq. ft.
Waterway Opening Provided	693	Sq. ft.
Drainage Area	31.0	Sq. mi.
Design Discharge, Q100	3300	Cfs.
Velocity	6.65	Fps.
Q100 Elev.	845.15	
Backwater at Q100	1.2	ft.
Existing Waterway Opening	308.3	Sq. ft.
Existing Backwater	2.28	ft.
Proposed Low Structure Elev.	846.20	
Existing Low Structure Elev.	849.6	

HYDRAULIC SCOUR DATA

Scour Depth Q100 (Contraction)	6.10	ft.
Scour Depth Q100 (Total)	6.10	ft.
Low Scour Elev. Q100	831.01	
Scour Depth Q500 (Contraction)	8.14	ft.
Scour Depth Q500 (Total)	8.14	ft.
Low Scour Elev. Q500	828.97	

EARTHWORK TABULATION

Fill + 20%	990 Cys.
Common Excavation	585 Cys.
Usable Waterway Excavation (70%)	1420 Cys.
Surplus Foundation Excavation	N/A
Waste	1,015 Cys.
Total Waterway Excavation	2025 Cys.
Benching (Estimated)	305 Cys.

PRESTRESSED CONCRETE BULB-TEE BEAM
1 SPAN @ 115'-0", SKEW 15° 00' 00" RT.
35'-4" CLEAR ROADWAY,
ON US 35 OVER DEER CREEK
GRANT COUNTY, INDIANA

DATE	REVISION

Plot: 7/13/2026 9:26 AM

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE


DESIGNED: DR 6/2021 DRAWN: DR 6/2021
CHECKED: MH 6/2021 CHECKED: MH 6/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

LAYOUT

SCALE	BRIDGE FILE
HORIZONTAL 1"=50'	035-27-10469
VERTICAL 1"=10'	DESIGNATION
	1900048
	SHEETS
	10 of 36
	CONTRACT
	B-45063

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\Sht Layout 50.dgn
Model:Default



PRESTRESSED CONCRETE BULB-TEE BEAM
1 SPAN @ 115'-0",
35'-4" CLEAR ROADWAY, SKEW 15° 00' 00" RT.
ON US 35 OVER DEER CREEK
GRANT COUNTY, INDIANA

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE


DESIGNED: DR 5/2021 DRAWN: TLA 5/2021
CHECKED: MH 5/2021 CHECKED: MH 5/2021

INDIANA DEPARTMENT OF TRANSPORTATION

GENERAL PLAN SHEET NO. 1


SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	11 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:26 AM
pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht General Plan 1.dgn
Model: BR_Detail Sheet



TYPICAL SECTION

Scale: ⅜" = 1'-0"



RIPRAP DRAINAGE TURNOUT - SECTION A-A

Scale: ¼" = 1'-0"

GENERAL NOTES

1. Reinforcing steel cover shall be 2½"in top and 1" minimum in bottom of floor slab, and 2" in all other parts, unless noted.
2. The following surfaces shall be surface sealed:

   All exposed surfaces of Concrete Bridge Railings, and Concrete Bridge Railing Transitions.

DESIGN DATA

Design for HL-93 loading, in accordance with AASHTO LRFD Bridge Design Specifications, 9th Edition, 2020 and interim updates.

DEAD LOAD
Actual weight plus 35 lb/ft² for future wearing surface and 15 lb/ft² for permanent metal deck forms.

FLOOR SLAB
Designed with a 7½" structural depth plus ½" sacrificial wearing surface.

DESIGN STRESSES

CONCRETE
Class "C": f'c = 4,000 psi
Class "A": f'c = 3,500 psi
Class "B": f'c = 3,000 psi

REINFORCING STEEL
Grade 60 f'y = 60,000 psi

CONSTRUCTURE LOADING
The exterior girder has been checked for strength, deflection, and overturning using the construction loads shown below. Cantillever overhang brackets were assumed for support of the deck overhang past the edge of the exterior girder. Finishing machine was assumed to be supported 6 in. outside the vertical coping form. The top overhang brackets were assumed to be braced against the intersection of the girder bottom flange and web.

DECK FALSEWORK LOADS
Designed for 15 lb/ft² for permanent metal stay-in-place deck forms, removable deck forms, and 2-ft exterior walkway.

CONSTRUCTION LIVE LOADS
Designed for 20 lb/ft² extending 2 ft past the edge of coping and 75 lb/ft vertical force applied at a distance of 6 in. outside the face of coping over a 30-ft length of the deck centered with the finishing machine.

FINISHING-MACHINE LOAD
4500 lb distributed over 10 ft along the coping.

WIND LOAD
Designed for 70 mph horizontal wind loading in accordance with LRFD 3.8.1.

SEISMIC DESIGN DATA

Seismic Performance Zone	1
Acceleration Coefficient	0.065
Seismic Soil Profile Type	C

PRESTRESSED CONCRETE BULB-TEE BEAM
1 SPAN @ 115'-0",
35'-4" CLEAR ROADWAY, SKEW 15° 00' 00" RT.
ON US 35 OVER DEER CREEK
GRANT COUNTY, INDIANA

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE


DESIGNED: DR 5/2021 DRAWN: TLA 5/2021
CHECKED: MTC 5/2021 CHECKED: DR 5/2021


INDIANA
DEPARTMENT OF TRANSPORTATION

GENERAL PLAN
SHEET NO.2


SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	12 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:26 AM
File: pw:\dotwise.indot.in.gov:DOTWIse\Documents\Crawfordsville\1601095\Design\MS\General Plan 2.dgn
Model:BR_Detail Sheet


Wing A End Bent 1
Wing D End Bent 2
Wing B End Bent 1
Wing C End Bent 2
BENT No.1
BENT No.2
Skew 15°0'0"
℄ End Bent
℄ Bridge
7"
3'-10" End Bent (Typ.)
16-616E
8 Spaced w/ below construction joint Bars &
8 Spaced W/ above construction joint Bars
16-617E
8 Spaced w/ below construction joint Bars &
8 Spaced W/ above construction joint Bars
12'-11¾"
15'-10⅝"
14'-1¾"
1'-0"
12'-0"
1'-0"
6-717E x 26'-10"
6-#7E x 23'-10"
6-#7E x 23'-10"
#7E Min. Lap 4'-4"
6-717E x 26'-4"
6-#7E x 23'-10"
6-#7E x 23'-10"
6½"
2'-1⅞"
℄ of Bent,
Bearing & Piles
710E, 714E, 715E or 716E
2-612E
710E, 711E, 712E or 713E
3'-10"
1'-11"
1'-11"
7⅞"
7⅞"
7⅞



ELEVATION
BENT No.1 SHOWN
FRONT REINFORCEMENT
(BENT No.2 Similar)
Scale:½"=1'-0"



ELEVATION
BENT No.1 SHOWN
BACK REINFORCEMENT
(BENT No.2 Similar)
Scale:½"=1'-0"

NOTES
1. For end bent plan see end bent detail sheet No. 1
2. All reinforcing bars shall be epoxy-coated.
3. For section A-A & B-B see end bent detail sheet No. 3

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE


DESIGNED: DR 6/30/2022 DRAWN: DR 6/30/2022
CHECKED: MTC 7/2022 CHECKED: MH 7/2022

INDIANA
DEPARTMENT OF TRANSPORTATION

END BENT DETAILS
SHEET 2


SCALE	BRIDGE FILE
Not To Scale	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	14 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:26 AM
File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht End Bent.dgn
Model:BR_End Bent 02




SECTION A-A AT BEAMS

Scale: ½" = 1'-0"



SECTION B-B BETWEEN BEAMS

Scale: ½" = 1'-0"



SECTION C-C BETWEEN BEAMS

Scale: ½" = 1'-0"

NOTES

1. All reinforcing bars shall be epoxy- coated.
2. For reinforcing bar notes, see Standard Drawing E 703-BRST-01
3. For section A-A, B-B, & C-C location details see end bent details, sheet No. 2

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 6/30/2022 DRAWN: DR 6/30/2022

CHECKED: MTC 7/2022 CHECKED: MH 7/2022


INDIANA
DEPARTMENT OF TRANSPORTATION

END BENT DETAILS
SHEET 3


SCALE	BRIDGE FILE
Not To Scale	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	15 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:26 AM

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht End Bent.dgn
Model:BR_End Bent 03




614E x 4'-9" 613E x 5'-10" 611E x 15'-7" 610E x 18'-10" 612E x 18'-11"




616E x 3'-11"


617E x 4'-5"




411E x 4'-10"




412E x 4'-11"




615E x 10'-7"




711E x 13'-10"




710E x 13'-4"




713E x 13'-2"




712E x 12'-4"




714E x 12'-8"



715E x 11'-2"



716E x 12'-0"



717E x 26'-10"

BILL OF MATERIALS EPOXY COATED REINFORCING STEEL FOR END BENT No.1			
SIZE & MARK	No. OF BARS	LENGTH ft in	WEIGHT lbs
710E	10	13' - 4"	
711E	2	13' - 10"	
712E	2	12' - 4"	
713E	1	13' - 2"	
714E	2	12' - 8"	
715E	2	11' - 2"	
716E	1	12' - 0"	
717E	12	26' - 10"	
#7E	34	23' - 10"	
#7E	6	9' - 4"	
#7E	3	7' - 3"	
#7E	6	5' - 11"	
#7E	4	3' - 4"	
		Total #7E	3102
610E	31	18' - 10"	
611E	29	15' - 7"	
612E	4	18' - 11"	
613E	35	5' - 10"	
614E	64	4' - 9"	
615E	64	10' - 7"	
616E	16	3' - 11"	
617E	16	4' - 5"	
#6E	4	10' - 0"	
#6E	6	9' - 4"	
#6E	4	8' - 0"	
		Total #6E	3842
411E	158	4' - 10"	
412E	8	4' - 11"	
#4E	4	15' - 5"	
		Total #4E	578
		Total Epoxy Coated Reinforcing	7522
CONCRETE			
Concrete, Class C, Superstructure			57.3 Cys.
MISCELLANOUS			
Agg. For End Bent Backfill			40.5 CYS
Geotextile for underdrain Type 2B			87.5 Sys.
6" End Bent Drain Pipe			70 LFT
HP 12 x 53, 5 @ 37'			185 LFT
Test Pile, Indicator, Production 1 @ 42'			47 LFt.
Test Pile, Indicator, Restrike			1 Each
Pile Shoe HP 12 x 53			6 Each

BILL OF MATERIALS EPOXY COATED REINFORCING STEEL FOR END BENT No. 2			
SIZE & MARK	No. OF BARS	LENGTH ft in	WEIGHT lbs
710E	10	13' - 4"	
711E	2	13' - 10"	
712E	2	12' - 4"	
713E	1	13' - 2"	
714E	2	12' - 8"	
715E	2	11' - 2"	
716E	1	12' - 0"	
717E	12	26' - 10"	
#7E	34	23' - 10"	
#7E	6	9' - 4"	
#7E	3	7' - 3"	
#7E	6	5' - 11"	
#7E	4	3' - 4"	
		Total #7E	3102
610E	31	18' - 10"	
611E	29	15' - 7"	
612E	4	18' - 11"	
613E	35	5' - 10"	
614E	64	4' - 9"	
615E	64	10' - 7"	
616E	16	3' - 11"	
617E	16	4' - 5"	
#6E	4	10' - 0"	
#6E	6	9' - 4"	
#6E	4	8' - 0"	
		Total #6E	3842
411E	158	4' - 10"	
412E	8	4' - 11"	
#4E	4	15' - 5"	
		Total #4E	578
		Total Epoxy Coated Reinforcing	7522
CONCRETE			
Concrete, Class C, Superstructure			57.3 Cys.
MISCELLANOUS			
Agg. For End Bent Backfill			40.5 CYS
Geotextile for underdrain Type 2B			87.5 Sys
6" End Bent Drain Pipe			70 LFT
HP 12 x 53, 5 @ 35'			175 LFT
Test Pile, Indicator, Production 1 @ 45'			45 LFt.
Test Pile, Indicator, Restrike			1 Each
Pile Shoe HP 12 x 53			6 Each

NOTES

1. All reinforcing bars shall be epoxy-coated.
2. For reinforcing bar notes, see Standard Drawing E 703-BRST-01

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 6/30/2022 DRAWN: DR 6/30/2022
CHECKED: MTC 7/2022 CHECKED: MH 7/2022


INDIANA
DEPARTMENT OF TRANSPORTATION

END BENT DETAILS
SHEET 4


SCALE	BRIDGE FILE
Not To Scale	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	16 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:26 AM

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht End Bent.dgn
BR_End Bent 04




ELEVATION




SECTION A-A

BILL OF MATERIALS			
FOR TWO WINGWALLS			
EPOXY COATED REINFORCING STEEL			
SIZE & MARK	No. OF BARS	LENGTH ft in	WEIGHT lbs
#7E	72	11' - 8"	
	Total #7E		1717
512E	52	2' - 7"	
#5E	52	8' - 9"	
	Total #5E		615
		Total Epoxy Coated Reinforcing	2332
CONCRETE			
Concrete, Class "C" in Superstructure			5.7 CYS




512E x 2'-7"

WINGWALL DETAILS
Scale: ½" = 1'-0"




PLAN VIEW


BEARING ASSEMBLY
SECTION C-C




END VIEW



CONCRETE BEAM
SECTION A-A



SIDE VIEW
SECTION B-B



Detail A
SCALE 3"= 1'-0"

BEARING ASSEMBLY
SCALE: 1" = 1'-0"

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 6/30/2022 | DRAWN: DR 6/30/2022
CHECKED: MTC 7/2022 | CHECKED: MH 7/2022


INDIANA
DEPARTMENT OF TRANSPORTATION

END BENT DETAILS
SHEET 5


SCALE	BRIDGE FILE
Not To Scale	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	17 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:26 AM

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht End Bent.dgn



FRAMING PLAN
Scale: 3/16 = 1'-0"



DETAIL A
Scale: 3/8 = 1'-0"

NOTE
For structural steel diaphragms details see Standard Drawing E 707-SDPC 03 & 04

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE


DESIGNED: DR 3/2022 | DRAWN: DR 3/2022
CHECKED: MH 12/2022 | CHECKED: MH 12/2022

INDIANA
DEPARTMENT OF TRANSPORTATION


FRAMING PLAN DETAILS

SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	18 of 36
	CONTRACT
	B-45063


Plot: 7/13/2026 9:26 AM
File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Framing.dgn
Model:BR_Framing



BEAM PLAN
SCALE:¼" = 1'-0"



BEAM ELEVATION
SCALE: Horiz.:¼" = 1'-0"
Vet.:½" = 1'-0"



BEAM END DETAIL
SCALE: Horiz.:¼" = 1'-0"
Vet.:½" = 1'-0"

TABLE OF CAMBERS (in.)			
Beam	Initial Camber at Erection	Deflection due to Deck pour	Residual Beam Camber
1	5.77	2.93	2.85
2	5.77	3.10	2.66
3	5.77	3.10	2.66
4	5.77	2.93	2.85

DESIGN DATA

1. Prestressing steel shall be 0.6" Diameter 270 Ksi, uncoated low relaxation, seven wire strand (Area = 0.217 sq. in) .
2. Initial pull per strand 43.94 kips
3. Concrete strength at release fci' = 6,500 psi
4. Concrete strength at 28 days, f'c = 8,000 psi
5. Reinforcing Steel shall be grade 60 Ksi minimum yield strength.
6. Hold down force = 2.59 Kips per strand.

GENERAL BEAM NOTES

1. Estimated elastic Beam shortening is 0.67 in allowance in the beam length should be made during fabrication.
2. For fabrication tolerances of prestressed beams, see Standard Drawing E 707-BPBF-01 through 04.
3. For reinforcing bar notes, see Standard Drawing E 703-BRST-01.
4. Reinforcing bars designated "E" shall be epoxy coated.
5. Top of beams shall be scored transversely at about 3" on center with pointed tool.
6. For fabrication tolerances of prestressed beams, see Standard Drawings E 707-BPBF-01 throgh-04.
7. For beam sections and bar bending diagrams, see beam details sheet No. 2.

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Rizad 7/24/2026
DESIGN ENGINEER DATE


DESIGNED: DR 06/2022 DRAWN: DR 06/2022
CHECKED: MTC 06/2022 CHECKED: MTC 06/2022

INDIANA
DEPARTMENT OF TRANSPORTATION

BEAM DETAILS
SHEET NO. 1


SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	19 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:26 AM
File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Beam Details 1.dgn
Model:BR_Beam Details 1




SECTION SHOWING DIMENSIONS BULB - TEE BEAM TYPE BT 48 x 49

Scale: ¾" = 1'-0"




SECTION SHOWING REINFORCEMENT

Scale: ¾" = 1'-0"




301 x 6'-5"

Not To Scale




302 x 2'-8"

Not To Scale



403 x 12'-3"

Not To Scale




END VIEW



SIDE VIEW


401aE x 9'-9"

Not To Scale




END ELEVATION

SCALE 1½"= 1'-0"



Detail A

SCALE 3"= 1'-0"



Area to be coped at beam end


Extend and bend up without the use of heat

Debond 6'-0" each end of beam

Debond 38'-10" Centered @ midspan

MID-SPAN SECTION


Scale: ¾" = 1'-0"



END SECTION


Scale: ¾" = 1'-0"

STRANDS TABLE		
	Strands Midspan	Strands End of Span
1	17	17
2	19	16
3	13	10
4	3	0
5	3	0
6	0	3
7	0	3
8	0	3
9	0	3
10	4	4




SECTION A-A

Scale: ¾" = 1'-0"



ELEVATION ALONG CENTER OF BEAM

Scale: ¾" = 1'-0"



SIDE ELEVATION

SCALE 1½"= 1'-0"

BEAM DETAILS AT END BENT

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 06/2022 DRAWN: DR 06/2022
CHECKED: MTC 06/2022 CHECKED: MTC 06/2022


INDIANA
DEPARTMENT OF TRANSPORTATION

BEAM DETAILS
SHEET NO. 2


SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	20 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:26 AM


File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Beam Details 2.dgn
Model:BR_Beam Details 2



FLOOR PLAN
SHOWING TOP REINFORCING STEEL
Scale:⅛" = 1'-0"



FLOOR PLAN
SHOWING BOTTOM REINFORCING STEEL
Scale:⅛" = 1'-0"



DETAIL A
Scale:¾" = 1'-0"

BILL OF MATERIALS			
FOR SUPERSTRUCTURE			
EPOXY COATED REINFORCING STEEL			
SIZE & MARK	No. OF BARS	LENGTH ft in	WEIGHT lbs
601E	354	22' - 4"	
#6E	354	22' - 3"	
	Total #6E		23705
501E	352	9' - 11"	
502E	4	3' - 8"	
#5E	232	32' - 3"	
	Total #5E		11460
#4E	232	31' - 9"	
	Total #4E		4920
Total Epoxy Coated Reinforcing			40085
CONCRETE			
Concrete, Class "C" in Superstructure			126.7 CYS
MISCELLANOUS			
Epoxy Coated Threaded Tie Bar Assemblies			40 EACH



601E x 22'-4" | 501E x 9'-11" | 502 E x 3'-8"

BAR BENDING DETAIL
Note To Scale

NOTES
1. All reinforcing bars shall be epoxy coated.
2. For section A-A, see floor detail sheet No. 2
3. The top reinforcing in the deck shall be securely tied down to the deck forms and/or beams to prevent lifting during concrete placement
4. Suitable restraint shall be provided to prevent the rotation of the exterior beams from construction loads
5. For reinforcing bar notes, see Standard Drawing E 703-BRST-01.
6. For epoxy-coated threaded Tie-Bar assembly details see Standard Drawing E 609-RCBA-04.

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE


DESIGNED: DR 3/2022 | DRAWN: DR 3/2022
CHECKED: MH 4/2022 | CHECKED: MH 4/2022

INDIANA
DEPARTMENT OF TRANSPORTATION

FLOOR DETAIL
SHEET NO. 1

SCALE	BRIDGE FILE
AS Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	21 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:27 AM
pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Floor Details.dgn
Model: BR_Detail Sheet



TYPICAL SECTION
Scale: ¾" = 1'-0"

NOTES

1. For plan detail, bar bending and bill of materials, see floor detail sheet No. 1
2. All reinforcing bars shall be epoxy-coated.
3. For reinforcing bar notes, see Standard Drawing E 703-BRST-01.

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 3/2022 | DRAWN: DR 3/2022


CHECKED: MH 4/2022 | CHECKED: MH 4/2022

INDIANA
DEPARTMENT OF TRANSPORTATION

FLOOR DETAIL
SHEET NO. 2

SCALE	BRIDGE FILE
AS Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	22 of 36
	CONTRACT
	B-45063


Plot: 7/13/2026 9:27 AM
File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Floor Details.dgn
Model:BR_Floor Details 2



ELEVATION (North Side)

Vertical Scale: ⅛"=1'-0"


Horizontal Scale: ¼" = 1'-0"



ELEVATION (South Side)


Vertical Scale: ⅛"=1'-0"

Horizontal Scale: ¼" = 1'-0"



SECTION A-A

Scale: 1" =1'-0'



5701E x 5'-6"



5704E x 3'-0"

BILL OF MATERIALS			
FOR BRIDGE RAILING (2 SIDES)			
EPOXY COATED REINFORCING STEEL			
SIZE & MARK	No. OF BARS	LENGTH ft in	WEIGHT lbs
5701E	310	5' - 6"	
5704E	620	3' - 0"	
#5E	48	35' - 11"	
	Total #5E		5516
Epoxy Coated Reinforcing Steel for Railing Transition 4 x551			2204 lb
Total Epoxy Coated Reinforcing			7720 lb
CONCRETE, C IN RAILING			
Concrete Railing Type FC			19.6 Cys.
MISCELLANEOUS			
Concrete Bridge Railing Transition, Type TFC			4 Each
Delineators			10 Each
*Surface Seal for Bridge Railing			1300 SFt.
* Surface Seal for Bridge Railing Transitions			400 SFt.

* For Information Only

NOTES

1. All reinforcing bars shall be epoxy-coated.
2. For reinforcing bar notes see Standard Drawing E703-BRST-01
3. For more details on concrete bridge railing, type FC see Standard Drawing E706-BRSF-01 & 02.
4. For concrete bridge railing transition type "TFC" see Standard Drawing E706-TTFC-01 through -03, & Standard Drawing E706-CBRT-01.
5. For bridge railing transition end details and "TFC" attachment of guardrail see Standard Drawing E706-CBRT-01 & 04.
6. For more details see General Plan Sheet No. 1

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Rixad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 1/2023 | DRAWN: DR 1/2023

CHECKED: MH 1/2023 | CHECKED: MH 1/2023


INDIANA
DEPARTMENT OF TRANSPORTATION

BRIDGE RAILING DETAILS

SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	23 of 36
	CONTRACT
	B-45063


Plot: 7/13/2026 9:27 AM

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Railing Details.dgn
Model:BR_Railing Details




SCREED PLAN

⅛"=1'-0"



DEAD LOAD DEFLECTION DIAGRAM

Not to Scale



TYPICAL SECTION

Scale: ¼" = 1'-0"

POINT	LOCATION	1	2	3	4	5	6	7	8	9	10	11	12	13
A	Top of Coping Form	851.45	851.67	851.97	852.25	852.52	852.78	853.02	853.25	853.46	853.66	853.85	854.02	854.16
	Top of Fasica Beam													
	Distance Top of Beam to Top of Coping													
B	Top of Screed	852.47	851.70	852.99	853.27	853.54	853.80	854.04	854.27	854.48	854.68	854.87	855.05	855.18
	Top of Beam													
	Distance Top of Beam to Top of Screed													
C	Top of Screed	851.48	851.70	851.99	852.27	852.55	852.80	853.05	853.27	853.49	853.68	853.87	854.05	854.18
	Top of Beam													
	Distance Top of Beam to Top of Screed													
D	Top of Screed	851.54	851.76	852.05	852.33	852.60	852.86	853.10	853.33	853.54	853.74	853.93	854.11	854.24
	Top of Beam													
	Distance Top of Beam to Top of Screed													
E	Top of Screed	851.62	851.84	852.13	852.41	852.68	852.94	853.19	853.41	853.62	853.82	854.01	854.19	854.32
	Top of Beam													
	Distance Top of Beam to Top of Screed													
F	Top of Screed	851.67	851.90	852.19	852.47	852.74	853.00	853.24	853.47	853.68	853.88	854.07	854.25	854.38
	Top of Beam													
	Distance Top of Beam to Top of Screed													
G/PG	Top of Screed	851.72	851.94	852.23	852.51	852.78	853.04	853.28	853.51	853.72	853.92	854.11	854.29	854.42
	Top of Beam													
	Distance Top of Beam to Top of Screed													
H	Top of Screed	851.64	851.86	852.15	852.43	852.70	852.96	853.20	853.43	853.64	853.84	854.03	854.21	854.34
	Top of Beam													
	Distance Top of Beam to Top of Screed													
I	Top of Screed	851.53	851.75	852.04	852.32	852.60	852.85	853.10	853.32	853.54	853.73	853.92	854.10	854.23
	Top of Beam													
	Distance Top of Beam to Top of Screed													
J	Top of Screed	851.37	851.59	851.88	852.16	852.44	852.69	852.94	853.16	853.38	853.57	853.76	853.94	854.07
	Top of Beam													
	Distance Top of Beam to Top of Screed													
K	Top of Screed	851.26	851.48	851.77	852.06	852.33	852.59	852.83	853.06	853.27	853.47	853.65	853.83	853.96
	Top of Beam													
	Distance Top of Beam to Top of Screed													
L	Top of Screed	851.25	851.47	852.76	853.05	853.32	853.58	853.82	854.05	854.26	854.46	854.64	854.82	854.95
	Top of Beam													
	Distance Top of Beam to Top of Screed													
M	Top of Coping Form	851.21	851.43	851.72	852.01	852.28	852.54	852.78	853.01	853.22	853.42	853.60	853.78	853.91
	Top of Fasica Beam													
	Distance Top of Beam to Top of Coping													

PROCEDURE AND NOTES

1. After beams are set, take elevations at all screed point on top of beams. Enter these elevations in the table. Subtract these elevations from the tabulated elevations and use the resulting dimensions as the height for setting screed forms above these points. These dimensions remain constant regardless of how much or in what order the concrete is poured.
2. Do not set screed forms by leveling.
3. No concrete in the floor slab shall be poured until the above operations are completed.
4. Screed elevations as shown in the table include an allowance for concrete dead load deflections.

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026

DESIGN ENGINEER DATE

DESIGNED: DR 6/2022 DRAWN: DR 3/2022

CHECKED: DJ 7/2022 CHECKED: DJ 7/2022


INDIANA
DEPARTMENT OF TRANSPORTATION


SCREED DETAILS


SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	24 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:27 AM


File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Screed
Model:BR_Screed








Group A
54 - #5E x 15'-0"
Not To Scale



Group B
12 - #5E x 39'-4"
Not To Scale



Group C
72 - #5E x 15'-1"
Not To Scale


BILL OF MATERIALS			
EPOXY COATED REINFORCING STEEL			
FOR ALL APPROACH SLAB			
SIZE & MARK	No. OF BARS	LENGTH ft in	WEIGHT lbs
591E	144	20' - 9"	
#5E	12	39' - 4"	
#5E	4	36' - 10"	
#5E	84	35' - 7"	
#5E	2	28' - 4"	
#5E	2	21' - 1"	
#5E	110	20' - 2"	
#5E	72	15' - 1"	
#5E	54	15' - 0"	
#5E	2	13' - 7"	
#5E	2	12' - 2"	
#5E	2	6' - 2"	
#5E	12	5' - 0"	
#5E	2	3' - 4"	
	Total #5E		11410
	Total Epoxy Coated Reinforcing		11410
Reinforcing Steel Epoxy Coated for Slab Extension (2 x 230 Lb)			460 Lb
	Total Epoxy Coated Reinforcing		11,870 Lb
CONCRETE			
Reinforced Concrete Bridge Approach (12")			202.1 SYS
RCBA Extension (2 x 2.6 Sys)			5.3Sys
	Total RCBA		207.4
MISCELLANOUS			
Subbase for PCCP			52 CYS
Integral Concrete curb Type B Modified			41 LFT
* Reinforcing Steel Epoxy Coated for Integral Concrete curb (#5 x 3'-0")			18 Each

* Not a pay item For information only


* Group A, B & C, Half of bars are in each approach slab (Typ. cut bars)

PLAN SHOWING TOP REINFORCING
Scale: 3/16" = 1'-0"


PLAN SHOWING BOTTOM REINFORCING
Scale: 3/16" = 1'-0"




SECTION THROUGH APPROACH
SCALE: ½" = 1'-0"



591E x 20'-9"
Not to Scale



PAVEMENT LEDGE DETAIL
Scale: ¾" = 1'-0"



INTEGRAL CONCRETE CURB TYPE B Modified DETAILS
SCALE 3"=1'

NOTES

1. All reinforcing bars shall be epoxy-coated
2. For more details on RCBA, see Standard Drawing E 609-RCBA-01 through 04
3. For slab extension details, see Standard Drawing E 609-TBAE-01 through 03
4. For type 1A joint, see Standard Drawing E 609-BRJT-01
5. For curb details, see Standard Drawing E 605-CCIN-01

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Rixad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: MH 4/2022 DRAWN: TLA 4/2022
CHECKED: DR 4/2022 CHECKED: DR 4/2022

INDIANA
DEPARTMENT OF TRANSPORTATION

APPROACH SLAB DETAILS

SCALE	BRIDGE FILE
As Noted	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	25 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:27 AM

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht RCBA.dgn
Model:BR_Approach Slab

SUMMARY OF BRIDGE QUANTITIES

ITEM	CONCRETE				CONCRETE RAILING CLASS C FC	REINF. BARS	REINF. BARS, EPOXY COATED	BARRIER DELIN-EATORS	REINF. CONC. BRIDGE APPROACH (12")	SUBBASE FOR PCCP	CONC, BRIDGE RAIL TRANSITION TFC	ANCHOR PLATES MK-AP	THREADED TIE BAR ASSEMBLY, E.C.	TERMINAL JOINT	AGGR. FOR END BENT BACKFILL	PILES									GRATES BASINS, & FITTINGS, CAST IRON	EXP. JOINT TYPE __	CONC. STR. MEMBERS		SURFACE SEAL**	
	CLASS C	CLASS A	CLASS B													STEEL H (HP 12X 53)	STEEL H EPOXY COATED	STEEL H REINF. CONC. ENCASED	TEST PILE, INDICATOR, PRODUCTION	TEST PILE, INDICATOR, RESTRIKE	PILE SHOE HP 12 x 53	PILE TIP STEEL H (SIZE)	CORED HOLE IN ROCK 24 " Ø					HYBRID BULB-TEE BEAM 48" x 49"	I BEAM TYPE & SIZE		
	SUPERSTR	SUBSTR	ABOVE FTG.	IN FTG.																			NO.	LFT					
	CYS	CYS	CYS	CYS	CYS	LBS	LBS	EACH	SYS	CYS	EACH	EACH	EACH	LFT	CYS	LFT	LFT	LFT	LFT	EACH	EACH	EACH			LBS	LFT	LFT	LFT	SFT	
SUPERSTRUCTURE	126.7						40,085						40														466			
END BENT NO. 1	57.3						7522								40.5	165			33	1	6									
WINGWALL A & B	5.7						2332																							
END BENT NO. 2	57.3						7522								40.5	150			30	1	6									
WINGWALL C & D	5.7						2332																							
RAILING					19.6		5,516	10																					1300	
RAILING TRANSITION							2,204				4																		400	
R.C.B.A.							11,410		202.1	51																				
R.C.B.A. SLAB EXTENSION							460		5.3																					
TOTALS	252.7				19.6		79383	10	207.4	51	4		40		81	315			63	2	12						466		1700	

** Estimated Quantity

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 5/2021 | DRAWN: DR 5/2021
CHECKED: MTC 5/2021 | CHECKED: MTC 5/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

BRIDGE SUMMARY

SCALE	BRIDGE FILE
N/A	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	26 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:27 AM

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Bridge Summary.dgn

PAVEMENT QUANTITIES AND APPROACH TABLE

LOCATION	DESCRIPTION (APPROACH TYPE OR CLASS)	WIDTH	LENGTH	RADII	DISTANCE BEYOND R/W/LINE	SURFACE BEYOND R/W LINE: COMPACTED AGGREGATE BASE	SURFACE BEYOND R/W LINE: HMA	SURFACE BEYOND R/W LINE: PCCP	GRADE: 1	GRADE: 2	EXCAVATION: CUT	EXCAVATION: FILL	CLEAR ZONE AT DRIVE	HMA FOR APPROACHES: SURFACE TYPE B	HMA FOR APPROACHES: INTERMD TYPE B	HMA FOR APPROACHES: SUB GRADE TREATMENT Type II	HMA FOR APPROACHES:	HMA FOR ROADS: SURFACE QC/QA-HMA 3, 58H, 9.5mm	HMA FOR ROADS: INTERMD QC/QA-HMA 3, 58H, 19 mm	HMA FOR ROADS: BASE QC/QA-HMA 3, 58S, 25 mm	HMA FOR ROADS: WIDENING WITH HMA TYPE C	HMA FOR ROADS:	HMA FOR ROADS:	SEAL COAT TYPE __	ASPHALT MATERIAL FOR: PRIME COAT	ASPHALT MATERIAL FOR: TACK COAT	COMPACTED AGGREGATE FOR BASE NO. 53: DEPTH 6"	COMPACTED AGGREGATE FOR BASE NO. 53: DEPTH Variable	COMPACTED AGGREGATE FOR SURFACE NO. 73: DEPTH	COMPACTED AGGREGATE FOR SURFACE NO. 73:	JOINT ADHESIVE	SUBGRADE TREATMENT TYPE IC	GEOTEXTILE FOR PAVEMENT TYPE 2B				REMARKS
														LBS PER SYD				LBS PER SYD																					
														165	275			880																					
		FT	FT	FT	FT	SYS	SYS	SYS	%	%	CYS	CYS	FT	TONS	TONS	SYS	TONS	TONS	TONS	TONS	TONS	TONS	SYS	SYS	TON	CYS	TONS	TONS	TONS	LFT	SYS	SYS				
US 35 Line "A"																		240	195	391	285					3		418			3558	1643	1851				
Wilde Life Crossing																												45									
Sta 1267+05 Rt.	Class II Drive	12	20	15/25										4.5	7.5	54										9											
Sta 1273+32 Rt.	Class II Drive	12	20	15/25										4.5	7.5	54										9											
TOTAL														9	15	108		240	195	391	285					3	18	463			3558	1643	1851				

STRUCTURE DATA

STRUCTURE NUMBER	LOCATION: STATION	LOCATION: LEFT	LOCATION: CROSS	LOCATION: RIGHT	SIZE	PIPE TYPE	MANHOLE, INLET, CATCH BASIN, OR SPECIALTY STRUCTURE AND TYPE	LENGTH	SKEW	FLOW LINE: COVER	FLOW LINE: UP STREAM	FLOW LINE: DOWN STREAM	SERVICE LIFE	SITE DESIGNATION	pH	BACKFILL METHOD	STRUCTURE BACKFILL	REVETMENT RIPRAP CONCRETE, CLASS A, FOR STR.	VIDEO INSPECTION	PIPE END SECTION	GRATED BOX END SECTION			SAFETY METAL END SECTION			REMARKS
					IN.			LFT		FT	ELEV.	ELEV.	YR				TYPE	CYS	TONS	CYS	LFT	EA.	TYPE	SLOPE	EA.	SIZE	SLOPE	EA.	
011	1267+05.00			x	15	3		28		1	847.05	846.47	75	Abrasive	5	2	1	5	8			2							
012	1273+32.00			x	15	3		28		1	854.11	852.90	75	Abrasive	5	2	1	5	8			2							
	1271+01	x			6	1		70																					6" End Bent Drain Pipe
	End Bent No.1																												
	1272+20	x			6	1		70																					6" End Bent Drain Pipe
	End Bent No.2																												
	Total																	10	16			4							

RIGHT OF WAY MARKER AND MONUMENT TABLE
Line "A"

STATION	LT.	CL	RT.	RIGHT OF WAY MARKER: OFFSET	RIGHT OF WAY MARKER: EACH	MONUMENT TYPE "B"	DESCRIPTION
1266+00	X			35'	1		
1266+00			X	35'	1		
1266+50	X			70'	1		
1266+50			X	70'	1		
1266+50		X				1	Begin Project
1270+21.78			X	70'	1		
1270+48.35	X			70'	1		
1274+35		X				1	End Project
1274+35	X			70'	1		
1274+35			X	70'	1		
1275+00	X			30'	1		
1275+00			X	30'	1		
Totals					10	2	

PAVED SIDE DITCH, RIPRAP DITCH AND SODDING SUMMARY TABLE

LOCATION: FROM STATION	LOCATION: TO STATION	LEFT	MEDIAN	RIGHT	PAVEMENT SIDE DITCH: ACTUAL LENGTH	PAVEMENT SIDE DITCH: CUT OFF WALLS (8 FT EQUIVAL LENGTH EACH)	TOTAL EQUIVALENT PAY LENGTHS TYPE					RIPRAP DITCH: RIPRAP, REVETMENT	RIPRAP DITCH: CLASS I RIPRAP	RIPRAP DITCH: GEOTEXTILES FOR RIPRAP TYPE 2B	SODDING: FOR PAVED SIDE DITCHES	SODDING: FOR DITCHES	SODDING: FOR MEDIAN	SODDING: FOR SHOULDER BREAK	SODDING: AT BRIDGE CONE	SODDING: TOTAL SODDING	NURSERY SODDING FOR LAWNS
					LFT	EACH	LFT	LFT	LFT	LFT	LFT	TONS	TONS	SYS	SYS	SYS	SYS	SYS	SYS	SYS	SYS
1272+45.00	1274+10.00	x			165											142				142	
1274+10.00	1274+56.00	x			46							30		56							
1266+00.00	1266+75.00			x	75							48.5		92							
1266+75.00	1266+91.00			x	16											14				14	
1267+19.00	1267+58.00			x	39											34				34	
1272+13.00	1273+18.00			x	105							67		128							
1273+46.00	1274+96.00			x	150							96.5		184							
Apron at Pipes												9		13							
Riprap Drainage Turnout												31.5		60		14					
Bridge Cone													641	641							
1266+29.50	1266+41.40	x										7.5		10							
TOTALS												290	641	1184		204				190	

SIGN QUANTITIES

AT STATION	LEFT	RIGHT	OFFSET +/- (FT)	SIGN DESCRIPTION	NEW POST SQUARE	RELOCATION	QUANTITY
			FT		FT		EA.
1272+30		X	12	Speed Limit Sign(45 Mph) & Auxillary Sign (BEGIN)	8	X	*1
1272+50	X		12	Speed Limit Sign(55 Mph)	8	X	1
1273+80		X	12	Signal Ahead(W3-3	8	X	1
1273+80	X		12	Signal Ahead(W3-3	8	X	1
TOTALS					32		4

* Sign Sheet Assembly Relocate

GUARDRAIL SUMMARY TABLE

LOCATION: FROM STATION	LOCATION: TO STATION	LEFT	MEDIAN LEFT	MEDIAN RIGHT	RIGHT	MGS W-BEAM GUARDRAIL LENGTH: STANDARD POST AT 6 FT 3 IN. SPA.	STANDARD POST AT 3 FT 1.5 IN. SPA.	DOUBLE FACED AT 6 FT 3 IN. SPA.	DOUBLE FACED AT 3 FT 1.5 IN. SPA.		SHOP CURVED AT ____ FT. SPA.	NESTING GUARDRAIL	GUARDRAIL MGS TRANSITION WITH CURB	GUARDRAIL MGS TRANSITION WITHOUT CURB	GUARDRAIL TRANSITION TYPE TGB	Strong Post W-Beam AT 6 FT 3 IN. SPA.	GUARDRAIL END TREATMENT TYPE OS		CURVED W-BEAM GUARDRAIL SYSTEM: TERMINAL SYSTEM TYPE	CURVED W-BEAM GUARDRAIL SYSTEM: TERMINAL SYSTEM EACH	CURVED W-BEAM GUARDRAIL SYSTEM: CONNECTOR SYSTEM TYPE	CURVED W-BEAM GUARDRAIL SYSTEM: CONNECTOR SYSTEM EACH	GUARDRAIL REMOVE	GUARDRAIL RESET	IMPACT ATTENUATOR TYPE ___	IMPACT ATTENUATOR TYPE ___	REMARKS
						LFT	LFT	LFT	LFT	LFT	LFT	EACH	EACH	EACH	EACH	LFT	EACH		TYPE	EACH	TYPE	EACH	LFT	LFT	EACH	EACH	
1269+15.81	1270+80.83				X	75								1			1											
1270+66.16	1271+05.91	X													1				1	1								
1272+14.07	1273+04.09				X								1				1											
1272+39.16	1274+04.18	X				75								1			1											
North East Corner		X																					90				
North West Corner		X																					88				
South East Corner					X																		78				
South West Corner					X																		232				
Total						150							1	2	1		3			1			488				

MAILBOX APPROACHES

LT./RT.	℄ BOX STATION	DESCRIPTION	WIDTH, W (FT)	ASSEMBLY REQ'D: SINGLE	ASSEMBLY REQ'D: DOUBLE		
LT.	1267+26	Private Residence Box	10'	1			
LT.	1273+34	Private Residence Box	10'	1			
		TOTAL		2			

DATE	REVISION

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: DR 5/2021 DRAWN: DR 5/2021
CHECKED: MTC 5/2021 CHECKED: MTC 5/2021

INDIANA DEPARTMENT OF TRANSPORTATION

ROAD SUMMARY

SCALE	BRIDGE FILE
N/A	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	27 of 36
	CONTRACT
	B-45063

Plot: 7/13/2026 9:27 AM

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Road Summary.dgn
Model:RD_Summary Sheet

			STR No.		011	012	STRUCTURE NUMBER																		
			PIPE TYPE		3/CIR	3/CIR																			
			SMOOTH PIPE SIZE		15"	15"																			
			CORRUGATED PIPE SIZE																						
			RCP/RCHEP (S)	CLASS	II	II																			
				D 0.01 RATING	1000	1000																			
			NON-REINFORCED CONCRETE PIPE CLASS 3 (S)																						
			CORRUGATED PE PIPE TYPE S (S)																						
			RIBBED PE PIPE (S)																						
			SMOOTH WALL PE PIPE (S) / MAXIMUM DR.																						
			PROFILE WALL PVC PIPE (S)																						
			SMOOTH WALL PIPE (S)																						
			VIRTIFIED CLAY PIPE EXTRA STRENGTH (S)																						
CORRUGATED STEEL PIPE / PIPE - ARCH			FULLY BIT. PAVED & LINED (S)	CORR. PROFILE																					
				THICKNESS																					
			ZINC COATED (C)	CORR. PROFILE																					
				THICKNESS																					
			ZINC COATED W/ BPI (C)	CORR. PROFILE																					
				THICKNESS																					
			ALUM.COATED TYPE 2 (C)	CORR. PROFILE																					
				THICKNESS																					
			ALUM. COATED TYPE 2 W/ BPI (C) (S) IA, OR IIA	CORR. PROFILE																					
				THICKNESS																					
			POLYMER PRECOATED GALVANIZED (C)(LS)/(RIVETED)	CORR. PROFILE																					
				THICKNESS																					
			POLYMER PRECOATED GALVANIZED (S) IA, OR IIA	CORR. PROFILE																					
				THICKNESS																					
			CORRUGATED ALUM. ALLOY PIPE (C)	CORR. PROFILE																					
				THICKNESS																					
			CORRUGATED ALUMN. ALLOY PIPE W/ BPI (LS))/(RIVETED)	CORR. PROFILE																					
				THICKNESS																					
			STR. PLATE ALUMINUM ALLOY PIPE (C)	CORR. PROFILE																					
				THICKNESS																					
			STR. PLATE ALUMINUM ALLOY PIPE W/ BPI (C)	CORR. PROFILE																					
				THICKNESS																					
			STR. PLATE STEEL PIPE (C)	CORR. PROFILE																					
				THICKNESS																					
			STR. PLATE STEEL PIPE W/ CFP (C)	CORR. PROFILE																					
				THICKNESS																					

LEGEND

RCP	Reinforced Concrete Pipe
RCHEP	Reinforced Concrete Horizontal Elliptical Pipe
PE	Polyethylene
DR	Dimension Ratio
PVC	Polyvinyl Chloride
BIT	Bituminous
CORR	Corrugation
BPI	Bituminous Paved Invert
ALUM	Aluminum
STR	Structural
CFP	Concrete Field Paving
CIR	Circular Pipe
DEF	Deformed Pipe
(S)	Smooth Pipe Material
(C)	Corrugated Pipe Material
OK	Acceptable for Use
(LS)	Lock Seam Pipe Required
*	Refer to Standard Drawing 715-PHCL-18 and -19 for nominal diameter appropriate for pay item diameter.
**	Tabulated thickness refers to top and side plates. Bottom plates shall be of next greater available thickness.

DAVID S. RIYAD REGISTERED No. 12000678 STATE OF INDIANA PROFESSIONAL ENGINEER

RECOMMENDED FOR APPROVAL David Riyad 7/24/2026
DESIGN ENGINEER DATE

DESIGNED: MM 7/2021 | DRAWN: MM 7/2021
CHECKED: MTC 7/2021 | CHECKED: MTC 7/2021


INDIANA
DEPARTMENT OF TRANSPORTATION

PIPE MATERIALS SHEET

SCALE	BRIDGE FILE
N/A	035-27-10469
	DESIGNATION
	1900048
	SHEETS
	28 of 36
	CONTRACT
	B-45063


Plot: 7/13/2026 9:27 AM

File: pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\MS\Sht Pipe Material.dgn
Model:RD_Pipe Material Sheet




MAINLINE		BENCHING
Ac = 46.76 SFT	Af = 11.4 SFT	Ab = 12.27 SFT
Vc = 111.3 CYS	Vf = 18 CYS	Vb = 11.40 CYS

1267+00.00



MAINLINE		BENCHING
Ac = 73.47 SFT	Af = 8.0 SFT	Ab = 0.00 SFT
Vc = 68 CYS	Vf = 7.4 CYS	Vb = 0.00 CYS

Begin Project Sta. 1266+50.00, Line "A" 1266+50.00



MAINLINE		BENCHING
Ac = 0.0 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 0 CYS	Vf = 0 CYS	Vb = 0.00 CYS

Begin Incidental Construction Sta. 1266+00.00, Line "A" 1266+00.00

STA. 1266+00.00 TO STA. 1267+00.00

Plot: 7/13/2026 9:27 AM

RECOMMENDED FOR APPROVAL
DESIGN ENGINEER DATE

DESIGNED: DR 6/2021 DRAWN: DR 6/2021


CHECKED: MH 6/2021 CHECKED: MH 6/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTION
LINE "A"


HORIZONTAL SCALE	BRIDGE FILE
1" = 10'	035-27-10469
VERTICAL SCALE	DESIGNATION
1" = 10'	1900048
	SHEETS
	29 of 36
	CONTRACT
	B-45063

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\New Inroad\prSections_ LineA.dgn




MAINLINE		BENCHING
Ac = 18.26 SFT	Af = 30.00 SFT	Ab = 7.90 SFT
Vc = 32.1 CYS	Vf = 50.9 CYS	Vb = 7.30 CYS

1268+00.00



MAINLINE		BENCHING
Ac = 16.43 SFT	Af = 25.00 SFT	Ab = 0.00 SFT
Vc = 57.2 CYS	Vf = 29.6 CYS	Vb = 0.00 CYS

1267+50.00



MAINLINE		BENCHING
Ac = 52.25 SFT	Af = 10.5 SFT	Ab = 0.00 SFT
Vc = 9.2 CYS	Vf = 2 CYS	Vb = 1.10 CYS

Str. #011
20 Ft of 15" Ø Pipe
W/ Two End Sections
Req'd.

Class II Drive Rt. Sta. 1267+05.00, Line "A" 1267+05.00

STA. 1267+25.00 TO STA. 1268+00.00

RECOMMENDED FOR APPROVAL

DESIGN ENGINEER DATE

DESIGNED: DR 6/2021 DRAWN: DR 6/2021


CHECKED: MH 6/2021 CHECKED: MH 6/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTION
LINE "A"


HORIZONTAL SCALE	BRIDGE FILE
1" = 10'	035-27-10469
VERTICAL SCALE	DESIGNATION
1" = 10'	1900048
	SHEETS
	30 of 36
	CONTRACT
	B-45063

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\New Inroad\prSections_ LineA.dgn




MAINLINE		BENCHING
Ac = 23.15 SFT	Af = 64.25 SFT	Ab = 34.84 SFT
Vc = 51.6 CYS	Vf = 107.6 CYS	Vb = 51.90 CYS

1269+50.00



MAINLINE		BENCHING
Ac = 32.57 SFT	Af =52.00 SFT	Ab = 21.18 SFT
Vc = 36.5 CYS	Vf = 91.6 CYS	Vb = 37.70 CYS

1269+00.00



MAINLINE		BENCHING
Ac = 6.83 SFT	Af = 46.94 SFT	Ab = 19.57 SFT
Vc = 23.2 CYS	Vf = 71.2 CYS	Vb = 25.40 CYS

1268+50.00

STA. 1268+50.00 TO STA. 1269+50.00

RECOMMENDED FOR APPROVAL

DESIGN ENGINEER DATE

DESIGNED: DR 6/2021 DRAWN: DR 6/2021

CHECKED: MH 6/2021 CHECKED: MH 6/2021


INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTION
LINE "A"

HORIZONTAL SCALE	BRIDGE FILE
1" = 10'	035-27-10469
VERTICAL SCALE	DESIGNATION
1" = 10'	1900048
	SHEETS
	31 of 36
	CONTRACT
	B-45063


Plot: 7/13/2026 9:27 AM

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\New Inroad\prSections_ LineA.dgn




Ac = 0.0 SFT	Af = 148.22 SFT	Ab = 31.36 SFT
Vc = 0 CYS	Vf = 15.9 CYS	Vb = 4.80 CYS

Class V Drive Lt. Sta. 1270+54.00, Line "A" **1270+54.00**



Ac = 0.0 SFT	Af = 66.76 SFT	Ab = 33.06 SFT
Vc = 9.7 CYS	Vf = 151.8 CYS	Vb = 66.10 CYS

1270+50.00



Ac =10.45 SFT	Af =97.15 SFT	Ab = 38.31 SFT
Vc = 31.1 CYS	Vf = 149.4 CYS	Vb = 67.70 CYS

1270+00.00

STA. 1270+00.00 TO STA. 1270+54.00

Plot: 7/13/2026 9:27 AM

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER DATE

DESIGNED: DR 6/2021 DRAWN: DR 6/2021


CHECKED: MH 6/2021 CHECKED: MH 6/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTION
LINE "A"


HORIZONTAL SCALE	BRIDGE FILE
1" = 10'	035-27-10469
VERTICAL SCALE	DESIGNATION
1" = 10'	1900048
	SHEETS
	32 of 36
	CONTRACT
	B-45063

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\New Inroad\prSections_ LineA.dgn



MAINLINE		BENCHING
Ac = 0.0 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc =0.0 CYS	Vf = 0 CYS	Vb = 0.00 CYS


1272+00.00



MAINLINE		BENCHING
Ac = 0.0 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 0.0 CYS	Vf = 0 CYS	Vb = 0.00 CYS

℄ Structure Sta. 1271+60.00, Line "A"

1271+50.00



MAINLINE		BENCHING
Ac =0.00 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 0.0 CYS	Vf = 126.3 CYS	Vb = 26.70 CYS

1271+00.00

STA. 1271+00.00 TO STA. 1272+00.00

Plot: 7/13/2026 9:27 AM

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER DATE

DESIGNED: DR 6/2021 | DRAWN: DR 6/2021


CHECKED: MH 6/2021 | CHECKED: MH 6/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTION
LINE "A"


HORIZONTAL SCALE	BRIDGE FILE
1" = 10'	035-27-10469
VERTICAL SCALE	DESIGNATION
1" = 10'	1900048
	SHEETS
	33 of 36
	CONTRACT
	B-45063

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\New Inroad\prSections_ LineA.dgn




MAINLINE		BENCHING
Ac = 87.25 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 90.4 CYS	Vf = 0 CYS	Vb = 0.00 CYS

Class II Drive Rt. Sta. 1273+32.00, Line "A" 1273+32.00



MAINLINE		BENCHING
Ac = 65.31 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 134.3 CYS	Vf = 0 CYS	Vb = 0.00 CYS

1273+00.00



MAINLINE		BENCHING
Ac = 79.71 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 51.7 CYS	Vf = 0 CYS	Vb = 0.00 CYS

1272+50.00

STA. 1272+50.00 TO STA. 1273+32.00

Plot: 7/13/2026 9:27 AM

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER DATE


DESIGNED: DR 6/2021	DRAWN: DR 6/2021
CHECKED: MH 6/2021	CHECKED: MH 6/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTION
LINE "A"


HORIZONTAL SCALE	BRIDGE FILE
1" = 10'	035-27-10469
VERTICAL SCALE	DESIGNATION
1" = 10'	1900048
	SHEETS
	34 of 36
	CONTRACT
	B-45063

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\New Inroad\prSections_ LineA.dgn



MAINLINE		BENCHING
Ac = 0.0 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 8.4 CYS	Vf = 0.3 CYS	Vb = 0.00 CYS


1274+50.00



MAINLINE		BENCHING
Ac = 30.25 SFT	Af = 1.00 SFT	Ab = 0.00 SFT
Vc = 42.7 CYS	Vf = 1.3 CYS	Vb = 0.00 CYS


End Project Sta. 1274+35.00, Line "A"

1274+35.00



MAINLINE		BENCHING
Ac = 35.61 SFT	Af = 1.00 SFT	Ab = 0.00 SFT
Vc = 80.3 CYS	Vf = 0.9 CYS	Vb = 0.00 CYS

1274+00.00



MAINLINE		BENCHING
Ac = 51.08 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 46.1 CYS	Vf = 0 CYS	Vb = 0.00 CYS

1273+50.00

STA. 1273+50.00 TO STA. 1274+50.00

Plot: 7/13/2026 9:27 AM

RECOMMENDED FOR APPROVAL

DESIGN ENGINEER DATE


DESIGNED: DR 6/2021	DRAWN: DR 6/2021
CHECKED: MH 6/2021	CHECKED: MH 6/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTION
LINE "A"


HORIZONTAL SCALE	BRIDGE FILE
1" = 10'	035-27-10469
VERTICAL SCALE	DESIGNATION
1" = 10'	1900048
	SHEETS
	35 of 36
	CONTRACT
	B-45063

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\New Inroad\prSections_ LineA.dgn



MAINLINE		BENCHING
Ac = 0.0 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 0 CYS	Vf = 0 CYS	Vb = 0.00 CYS

End Incidental Construction Sta. 1275+25.00, Line "A" **1275+25.00**



MAINLINE		BENCHING
Ac = 0.0 SFT	Af = 0.0 SFT	Ab = 0.00 SFT
Vc = 0 CYS	Vf = 0 CYS	Vb = 0.00 CYS

1275+00.00

STA. 1275+00.00 TO STA. 1275+50.00

Plot: 7/13/2026 9:27 AM

RECOMMENDED FOR APPROVAL _____ DESIGN ENGINEER DATE

DESIGNED: DR	6/2021	DRAWN: DR	6/2021
CHECKED: MH	6/2021	CHECKED: MH	6/2021

INDIANA
DEPARTMENT OF TRANSPORTATION

CROSS SECTION
LINE "A"

HORIZONTAL SCALE	BRIDGE FILE
1" = 10'	035-27-10469
VERTICAL SCALE	DESIGNATION
1" = 10'	1900048
	SHEETS
	36 of 36
	CONTRACT
	B-45063

pw:\\indot-pw.bentley.com:indot-pw-01\Documents\Fort Wayne\1900048\Design\InRoads\New Inroad\prSections_ LineA.dgn